M.R.O. 14—10,000—21-4-22.

MADRAS RECORD OFFICE.

Government of Madras.

Revenue **DEPARTMENT.**

G.O. No. 329 Press ~~Mis.~~

373-374

Dated 17. 2 - 1862

Not to be folded or roughly handled

Proceedings of the Madras Government, Revenue Department,
17th February 1862.

No. 373. Read the following Proceedings of the Madras Government in the Public Works Department, dated 10th February 1862, No. 176 :—

Referring Plan and Estimate for Rupees 450, for re-constructing a portion of the Sea Custom House at Davipatam in Madura. } (Vide Public Works Proceedings, 10th February 1862, Nos. 147, 148.)

No. 374. ORDER THEREON, 17th February 1862, No. 349.

The revised estimate amounting to Rupees (450) four hundred and fifty is accordingly sanctioned. Orders will be issued from the Public Works Department as to the funds from which the work should be executed.

(Signed) C. G. MASTER,
Deputy Secretary to Government.

PUBLIC WORKS DEPARTMENT.

Public.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following letter from Colonel W. I. BIRDWOOD, Deputy Chief Engineer, Southern Circle, to Lieutenant-Colonel W. H. HORSLEY, Chief Engineer and Secretary to Government, Public Works Department, dated Chepauk, 3rd February 1862, No. 10,152 :—

SIR,

1 Letter from District Engineer, No. 904, dated 14th October 1861.
1 Proceedings of Board Revenue, No. 6,757, dated 5th December 1861.
1 Plan, 1-9,914 1861.
1 Specification, 2-9,914 1861.
1 Abstract estimate, 3-9,914 1861.
* No. 6,757, dated 5th December 1861.

I have the honor to forward, for submission to Government, a plan, specification and estimate, amounting to Rupees 450, for re-constructing a portion of the Sea Custom House at Davipatam, in the District of Madura, countersigned by the Collector, and approved* of by the Board of Revenue.

2. Provision is made in the estimate for the re-construction of the portions of the building colored yellow in the accompanying plan, with sun-dried bricks and clay, and roofing with palmirah couples, flat and pan tiles; fixing three windows in the old building, and for making one country wood batten door.

3. The rate (Rupees 10) allowed for roofing being considered inadequate to secure good materials and workmanship, it has been increased to Rupees 16, in accordance with the data of the District. Plastering with chunam was provided for in the estimate at a cost of Rupees 50-12-2; but as the walls are to be constructed with sun-dried bricks, this is unnecessary, the charge, therefore, for this item was omitted, and white-washing substituted.

4. The estimate has been examined in this Office and corrected. The rates given in it are those prevailing in the Madura District, and are not more than that absolutely necessary to complete the work. I request, therefore, that you will be good enough to obtain the early sanction of Government thereto, the amount, viz., Rupees 450, to be defrayed from the general funds placed at the disposal of the District Engineer, for expenditure during the current official year.

ORDER THEREON, 10th February 1862, No. 176.

Referred to the Revenue Department for consideration.

(True Extract.)

W. H. Horsley, Lieut-Colonel,
Chief Engr. and Secy. to Govt., D.P.W.

To the Revenue Department, with five enclosures.

Exd. T. McMootry.

Rev-1862 Departt.
Proc: of Govt for Feby
Rs. 410.

Proceedings of the
Madras Govt: in the
P. W. Departt.

Dated 10th July 1862
Received 12th "
No. 176.

E. 5.

Reporting Plan
and Estimate for Rs 450
for re-constructing a
portion of the Sea Custom
House at Danishtaun
in Madura.

No 373 & 374.

No. 349.

The revised Estimate
amounting to Rs 450/ four
hundred & fifty is according
-ly sanctioned. Orders will
be issued from the P. W. D
as to the funds from which
the work should be ex
-ecuted.

Fort St. George
19th July 1862

Copy
Pd. of Revn with Proc. dated 12th inst. No. 176.
" P. W. D with 5 Encls

No. 3419-17 Pol.
Military Order