M.R.O. 1—77,006—8-6-37.

(1) Number of pages

(2) Date of repair 23-7-62

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 935 Press ~~Mis.~~

92-93

Dated 3—52 1862.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 3rd May 1862.

No. 92. Read the following Proceedings of the Madras Government in the Marine Department, dated 26th April 1862, No. 117 :—

Sanctioning the estimate for constructing a Flag Staff at Mangalore. (Vide Marine Proceedings, 29th April 1862, Nos. 57-58.)

No. 93. ORDER THEREON, 3rd May 1862, No. 935.

Communicated to the Deputy Chief Engineer, Central Circle, for information and guidance.

(Signed) W. H. HORSLEY, Lieut.-Colonel,
Secretary to Government.

BUILDINGS

ABSTRACT of Estimate No. of 186 -6

DISTRICT South Canara

WORK Constructing a Flag staff at Mangalore.

Quantities.	Description of Work.	Rate. Rs.	A.	P.	Amount. Rupees.	Amount of each part. Rupees.
1676	Cubic ft. of Laterite in Chunam 700 Cft	12			201	
1	Main Mast of 46 f. length.				130.	
1	Top — d- of 36 f.				25.	
1	Cross Yard including Iron Hoop at each end &c Complete				15.	
1	Wooden Cradle with Railing &c Complete at the Top of the Main Mast as per Plan	"	"	"	50.	
3201 1	Iron band at the bottom of Main Mast with lugs &c	"	"	"	5.	
	Plastering the base of the Flagstaff and Gun plat form	"	"	"	8.	
	Wooden Trestle trees complete for fixing the top mast.	"	"	"	5.	
32	Large Blocks for Rigging	2	8	"	80.	
1	Rope Ladder with Pegs &c Complete	"	"	"	45.	
	Carried Over				564	

Quantities.	Description of Work.	Rate. Rs.	A.	P.	Amount. Rupees.	Amount of each part. Rupees.
	Brought over				564	
	Ropes for Rigging &c	"	"	"	300	
	Flags for Signals	"	"	"	45.	
	Painting with Tar to the Mast & cross Yard and Cradle &c				12	
	Cartharie for Conveying Guns and fixing				10.	
	Excavating foundation &c				5.	
	Sundry Charges for fixing Mast including high Scaffolding &c				94.	
	Superintendence &c				50.	
	Total Rupees				1080.	

Deputy Chief Engr Office
Chepauk.
17th April 1862.

Gantzendale Lieut. C.E.
Acting Deputy Chief Engr C.E.

Enclosure
Ina P.W.D. Letter No. 12
From The Acting Dpt. Chief Engineer SC.
To the Secretary to Government. F.W.D.
Dated 17th } Recd. 22nd
No. 12797
Abstract Estimate
For Constructing a Flag Staff at Mangalore.
Amounting to Rupees 1080.
Recd 23rd April 1862

MARINE DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following letter from Lieutenant Colonel J. CARPENDALE, Acting Deputy Chief Engineer, C. C.; to Lieutenant Colonel W. H. HORSLEY, Secretary to Government, P. W. D., dated 17th April 1862, No. 12,797.

Marine.

Enclosures 5.
1 Letter from the District Engineer South Canara, No. 163, dated 23rd November 1861.
1 Letter from the Superintendent of Marine, No. 910, dated 19th March 1862.
1 Do. No. 1,071, dated 3rd April 1862.
1 Revised Plan.
1 Do. Estimate.

With reference to paragraph 10 of the Proceedings of Government, No. 1,826, dated 4th October 1861, I have the honor to forward a revised Plan, and Estimate, amounting to Rupees 1,080, for constructing a Flag Staff at Mangalore in the District of South Canara.

2. On the 23rd November 1861, the District Engineer sent in an incomplete Estimate for the above work and stated his inability to fix a price for the spars and rigging required for the same, as he had no data to be guided by.

3. A revised Plan and Estimate were then prepared in this Office and forwarded to the Superintendent of Marine for approval. That Officer has approved of the same, and informed me that the Port Funds would admit of the charges being defrayed, but at the same time intimated that no provision was made for the outlay in the current or ensuing year's Budget. Nevertheless, I beg to recommend that the authority of Government may be granted for the expenditure on the above work from the Reserve Fund of 1862-63 and to be charged to the Port Funds of Mangalore.

4. The site selected for its erection is in front of the Collector's Cutcherry about 150 yards back from the Wharf.

Referred to the Marine Department for consideration,
(Signed) W. H. HORSLEY, Lieut. Colonel,
Secy. to Government, P. W. D.

23rd April 1862.

ORDER THEREON, 29th April 1862, No. 117.

The Government sanction the Estimate for constructing a Flag Staff at Mangalore. The amount (Rupees 1,080) one thousand and eighty Rupees will be defrayed as proposed, to be ultimately debited to the Port Fund.

(True Extract.)

Chief Secretary.

To the Public Works Department,
(with 5 enclosures returned.)
" Superintendent of Marine.
" Collector of South Canara.

Exd. F. Cartledge.

45 Oct. 61 N: 27-28:

Public Works 1862 Dept.
Pro: of Govt. for May
N: 1266.
Pro: of the Accord Govt.
in the Marine Dept.
Dated 27 April/62
Received 2 May/62
N: 117
Enclos: 5.

Sanctioning the estimate
for constructing a
Flag staff at Cannanore.

N: 92-93.

N: 925 - 3 May

Lieut
Authority
1/5/62

Lieut

N: 935.

Communicated to the Deputy
Chief Engineer C Circle for information
and guidance.

Chepauk
3 May 1862

To

7 Copies
13.
2

The Chief Engr with Marine Corr. Disp. 5
The Dy Chf Engr CC with 3 Encls & Marine Corr.
Accountant General with Marine Corr.

N: 87