

(1) Number of pages 6(2) Date of repair 11-8-42

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public works. DEPARTMENT.

G.O. No.	1704.	Press
		~~Mis.~~
Dated	29-6-1963.	

Not to be folded or roughly handled

(Signed) W. I. BIRDWOOD, Colonel, R.E.,
Secretary to Government.

Robert Coleman, Jr. of 1862/63.
 Justice of the Peace, Salus. Samma lundieji
 Estimate for constructing a 1st Class Deputy Collector's
 house at Chintagondan.

Description of Charges		Rate	Amount	Total
18	C. feet stone in Bonds	@ 1.6	468 6 7	
18	do Stone in Chingam	@ 2 "	92 5 9	
	P. feet Bricks Work	@ 4 "	80 12 "	
10	Squares of Plastering 2 Coats with Chum	@ 6 "	283 14 6	
	do of flooring with blue stone slabs	@ 12 "	153 5 9	
	do Roofing with blue stone slabs, 2 courses flat tiles, 1 course pells 3 inches thick; 2 Coats plastering per square	@ 20 "	144 "	
	do Roofing with 3 course flat tiles 3 Coats plastering per square	@ 20 "	228 "	
	Slabs for above doors and windows	@ 1 "	12 "	
	Gap wood Brims	@ 50 "	100 "	
	Joists for main beam	@ 3.4 "	99 "	
	do for side do	@ 1.8 "	49 8 "	
	Country wood rafters	@ 2 "	126 "	
	Roofing feet sleepers	@ 2 "	269 8 "	
	do Sheathing Boards	@ 4 "	28 4 "	
	Wooden posts	@ 7 "	56 "	
	Breastsummers	@ 5 "	45 "	
	Roofing feet wall plate	@ 4 "	28 "	
	Moulds of reaper & rafter bails	@ 5 "	25 "	
	Kip rafters	@ 5 "	10 "	
	Sideen posts	@ 8 "	2 "	
	Balanced doors complete	@ 25 "	100 "	
	Ventilation Windows complete with wooden bars	@ 16 "	128 "	
	Trusses	@ 25 "	100 "	
	Square feet painting Sides and Joists with wood oil 2 Coats per square	@ 3 "	15 "	
	do Painting doors and windows with 2 Coats of green paint per sq. ft.	@ 7 1/2 "	36 4 "	
8	C. Yard & excavating foundation	@ 2 "	24 12 "	2655 " 9
	Superintendence			132 12 "
	Carriage in poundmeters			132 3 3
	Estal Estimated by			2920 " "

up Cheyapaad
 March 1863
 Wm. J. Hall, R.E.
 Civil Engineer
 Justice of the Peace
 Samuel P. Dutcher, Esq.
 H. Amell

Cheyapaad
 March 1863
 Wm. J. Hall, R.E.
 Civil Engineer
 Justice of the Peace
 Samuel P. Dutcher, Esq.
 H. Amell

Dec = 1358/63
~~Dec 1824/63~~

PROCEEDINGS OF THE MADRAS GOVERNMENT.

SIR,

- 1 Plan.
1 Abstract Estimate.
1 Report.
1 Procs. Board of Revenue, No. 669.

1. I have the honor to solicit sanction for the accompanying estimate amounting to Rupees 2,920 for a Cutcherry for a First Class Deputy Collector proposed to be constructed at Chin-tagunta in the Jammalmadgu Talook, Cuddapah District.

2. The plan prepared at the request of the Collector was submitted for the approval of the Board of Revenue, at whose suggestion one end of the verandah has been enclosed.

3. As the work, though much required, is not of an emergent nature, I beg to suggest that the estimate may be sanctioned for entry in the Budget of 1864-65.

Referred to the Revenue Department.

Chepauk,
11th June 1863.

(Signed) W. I. BIRDWOOD, Colonel, R. E.,
Secretary to Government, P.W.D.

REON, 20th June 1863, No. 1,086.

Approved.

(True Extract.)

L. Davis

Secretary to Government.

To the Board of Revenue.

Public Works Department

with 4 pencils

Printed for Anne
Dec 21/14

My dear Mother in the
Evening of 1841

Sheet 207. Pine-Is.
December 22

2000
 1086
 1086

estimating of the
 estimate of 22,000 for an-
 nouncing a 100 New City
 Records, cutting at 100
 pounds in the Capital
 District.

1. Don't say Order!
1/2/76-29 June.

111
Henry.

Communicated to the
Sunderland Engineer J. J. Division

for information and guidance -

To the Superintendent of Engineers 33rd Ave. with
2 letters to Genl. of the A. S. Co.
Accountant General with A. S. Co.
Contractor & Auditor
P. M. West with A. S. Co.

09