

(1) Number of pages 5

(2) Date of repair 7-9-07

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 3805	Press Mis.
579-580	
Dated 23-12-18	63

Not to be folded or roughly handled

78

H

*Proceedings of the Madras Government, Public Works Department,
23rd December 1863.*

No. 579. Read the following Proceedings of the Madras Government in the Ecclesiastical Department:—

Sanctioning Estimate of Rupees 440 for raising eastern wall } (Here enter 16th December 1863, No. 296.)
of the Cemetery at Pursewankum.

No. 580. ORDER THEREON, 23rd December 1863, No. 3,805.

1. Communicated to the Superintending Engineer, 4th Division, for information and guidance.
2. The cost of the work will be met from the current year's Reserve.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 4th Division.
„ Accountant General.
„ Controller and Auditor of Public Works Accounts.

Exd. S. T. Augustin.

27

Abstract Estimate No 105 of 1863/64.
Presidency District.

Work For raising a portion of the eastern wall of the Pandanahum Burial Ground,
prepared agreeably to the orders of the Superintending Engineer 4th Division No 2690 dated
30th September 1863

2016 1/4 Bricks work in chunam	25	304 8 7
1900 ft Plastering with 2 coats chunam	20	38 3 2
55 ft - Filing broken bottles in chunam to 275 Running feet of wall inc.		
including using old broken bottles	9	25 2 6
Cooly hire for removing the present coping	10	
1900 - Plastering with 2 coats blue chunam	233	41 13 9
Sundry charges		20 14 "

Total Reques. 440 "

Pres. Assist. Engr's Office
Northern Range
Madras
10th October 1863.

James Cunningham Esq. Lieut. R.E.
Assistant Engineer Presidency
Northern Range

W. J. P.

34

**ECCLESIASTICAL DEPARTMENT.
PROCEEDINGS OF THE MADRAS GOVERNMENT.**

Read the following letter from Lieutenant Colonel A. J. M. BOILEAU, R. E., Superintending Engineer, 4th Division; to Colonel C. A. ORR, R. E., Secretary to Government, Public Works Department, dated Madras, 5th December 1863, No 3327.

In September last the Vepery Church Committee brought to my notice that in consequence of the ground outside the Cemetery at Purawakum being a good deal higher than that inside, the people in the neighbourhood were in the habit of throwing therein the rubbish from their premises, a nuisance which it was manifestly desirable should be prevented.

The accompanying estimate, Rupees 440, has accordingly been prepared for raising a portion of the eastern wall three feet. The work has been approved of by the Reverend the Commissary of the Diocese, and also by the Barrack Master, and I beg to recommend that the estimate be sanctioned for immediate execution from the Reserve Fund of this year.

Referred to the Ecclesiastical Department.

CHEPAUK,

(Signed) CHARLES A. ORR, Colonel, R. E.,

5th December 1863.

Secretary to Government, D. P. W.

ORDER THEREON, 16th December 1863, No. 296.

Estimate, amounting to Rupees (440) four hundred and forty, sanctioned.

(True Extract.)

Chief Secretary.

To the Department Public Works,
(with two enclosures returned.)
Accountant General.

Ed. T. McMootry.

Very truly Yours

Wm. M. D. 1885

1885

Wm. M. D. 1885

Wm. M. D. 1885

Wm. M. D. 1885

Wm. M. D. 1885

Wm. M. D. 1885

Wm. M. D. 1885

Wm. M. D. 1885

Wm. M. D. 1885

Wm. M. D. 1885

Wm. M. D. 1885

1. Communicate to the
Superintending Engineer of the
Division for information & guidance

2. The cost of the materials
he needs from the last year's
Revenue

Chapman &
23 Dec 1885

Wm. M. D. 1885

Wm. M. D. 1885

Wm. M. D. 1885

Wm. M. D. 1885