

(1) Number of pages 6

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works
DEPARTMENT.

G.O. No.	3816	Press
		~~Mis.~~
601-602.		
Dated	23-12-	1863.

Not to be folded or roughly handled

Calicut
9/9/63

*Proceedings of the Madras Government, Public Works Department,
23rd December 1863.*

No. 601. Read the following Proceedings of the Madras Government in the Military Department:—

Approving, for immediate execution, of the Estimate amounting to Rupees 225 for erecting a wooden pent roof on the outer Verandah in front of the Guard-room Artillery Barracks, Fort Saint George } (Here enter 17th December 1863, No. 4,001.)

No. 602. ORDER THEREON, 23rd December 1863, No. 3,816.

1. Communicated to the Superintending Engineer, 4th Division, for information and guidance.

2. The cost of the work will be met from the current year's Reserve.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 4th Division.

„ Accountant General.

„ Controller and Auditor of Public Works Accounts.

Ed. S. T. Augustin.

Abstract Estimate No 85 of 1863 & 64. 3 1/2
District Presidency

Work Has erecting a wooden pent roof in the outer Verandah in front of the Guard room to shield the sentries from the sun at the Artillery Barracks in the Fort.

<i>Quantity</i>	<i>Description of work</i>	<i>Rate</i>	<i>Amount</i>
$7\frac{1}{2}$ Cft.	Brick work in chunam for erecting the bed under the foundations of the 5 posts	2 5	1 2 1
5	Granite grooved stones of 6 inches Cube of 2 lines dressed for fixing under the posts	1 4	6 4
21-6-6 $\frac{1}{2}$ Cft.	Teakwood wrought and put up	2 15	63 4 7
374 Supt.	Lining teakwood planks of $\frac{3}{4}$ " thick over lapping of 2" over the rafters with nails to the pent roof	24 12	92 9
5	Teakwood Caps with Cornice work to the posts	8	2 8
5	Iron clamps for posts of $\frac{1}{2}$ " sq. by 2" by $\frac{1}{4}$ " thick	6	1 14
154 Supt.	Removing the tiles of the old Verandah roof for inserting the rafters & planks of the new pent roof & recovering with new palm-leaf reapers and 3" new flat mantles and laying chunam borders	8 8	13 1 5
1000 D.	Lead Colour 3 Coats to the posts & rafters and planks	2 12	27 8
	Cooly here for laying putty to the crevices of the planks		5
	Removing the rubbish Sundry charges & scaffolding		11 12 11

Total Rupees 225 ..

Fort Saint George
23. November 1863

Approved
Asst. Engineer

By order
William D. D. D.
Bartholomew

Recd. No. 5007 of 1863
3/43/63

P. W. 5007/63

MILITARY DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following letter:—

From the Superintending Engineer 4th Division, Madras, 4th December 1863, No. 3781; to the Secretary to Government, Public Works Department.

I have the honor to forward for the sanction of Government, an Estimate amounting to Rupees 225 prepared on the requisition of the Barrack Master, for erecting a Wooden pent roof in the outer Verandah in front of the Guard-room Artillery Barracks, Fort Saint George, to protect the Sentries from the sun.

Enclosures.
1 Abstract Estimate.
1 Specification

2. As the work is evidently much needed and has been approved of by the Major General Commanding the Division, I request permission to order its execution on emergency, and that the required amount Rupees 225 may be disbursed from the Reserve Fund of the current official year.

Referred to the Military Department

7th December 1863.

(Signed) C. A. ORR, Colonel, R. E.,
Secretary to Government, P. W. D.

ORDER, No. 4001, 17th December 1863.

Approved for immediate execution.

(True Extract.)

Mumtaz
Dy. Secretary to Government.

To the Public Works Dept., with two enclosures.
" Quarter Master General.
" Barrack Master.
" Brigade Major Fort Saint George.

20 spec. Copies

Exd. T. Stubbs.

Per 1863 Department
P. No. of 333

Pro: Madras Government
in the following Department

Dated 17th Decr 1863
Recd 21st

N^o 4001

Approving, for in-
mediate execution, of the
estimate amounting to Rs 225
for erecting a wooden Pent
roof in the outer veranda
in front of the guard room
Artillery Barracks Fort
St. George.

N^o 3816-23rd December
W. H. O. S.

No 601-602

N^o 3816
Communicated to the Department

Engineers & Sanitary Administration

and guidance

The cost of the work will be met

23rd Decr 1863

From the Quarter Master General

Accounts General & Quarter Master General

Contractor & Master of Works of Fort St. George