

(1) Number of pages 6

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 3820	Press ~~Mis.~~
<i>20-9-50</i>	
Dated 24-12-1853.	

Not to be folded or roughly handled

let
7-9-50

*Proceedings of the Madras Government, Public Works Department,
24th December 1863.*

No. 609. Read the following Proceedings of the Madras Government in the Revenue
Department:—

Approving for entry in the Budget of 1864-65 the Estimate of
Rupees 8,250 for new buildings for Sub-Magistrates' Cut-
cherries, &c., at Kytar, Verduputty and Velatikolum in } (Here enter 18th December 1863, No. 2,331.)
Tinnevely District

No. 610. ORDER THEREON, 24th December 1863, No. 3,820.
Communicated to the Superintending Engineer, 8th Division, for information and guidance.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 8th Division.

„ Accountant General.

„ Controller and Auditor of Public Works Accounts.

Erd. S. T. Augustin.

District Simevelly

Work Constructing Sub Magistrates Quarters, subsidiary jail and Police Station proposed to be built at Kayathur, Perodhoorputty and Palathur.

Quantity

Description of work.

Rate amount of each part

331 1/2	bricks in Chumam	at 3 8	1155 7
51 15/16	D ^o Terrace floor work	do at 4	207 14
637 5/16	Sqr feet Plastering 3 Coats	at 2 8	159 6
44 14/4	D ^o Pointing	at .. 8	22 1
1175 7/8	D ^o Flooring with brick jelly in Chumam		
	3" thick and flat tiles 7 1/2" square		
	4 1/4" thick above	at 5	58 12
205 7/16	6" feet Wrought wood	at 2 8	512 11
6	Pairs of Doors each 3 x 6 1/2 with frames, hooks, hinges, iron bars 1/2" Complete	at 30	180
4	Pairs of Panelled Doors with frames, hooks, hinges, bolts 1/2" Complete	at 23	92
5	Pairs of Panelled Windows each 3 x 4 with frames, hooks, hinges, bolts, iron bars 1/2" Complete	at 20	100
9	Centilators (oval size) each 2 x 3/4 with frames, iron bars, shutters, rope 1/2" Complete	at 5	45
	Excavating foundation, raising floor & sundries		216 13

Total of Estimate Rupees 2750

Amount of Estimate for 2 other houses 5502

43 Engineers Office

D^o Madras

4 October 1863

J. H. M. S. S.

Captain R.E.

Superintendent Engineer 8 Division

I. K. S. S.
Collector

*Proceedings of the Madras Government, Revenue Department,
18th December 1863.*

No. 331. Read the following letter from Captain F. J. MOBERLY, R. E., Superintending Engineer, 8th Division, to Colonel C. A. ORR, R. E., Secretary to Government, Public Works Department, dated Madras, 24th November 1863, No. 1,276 :—

- Sir,
1. I have the honor to forward for sanction and entry in the Budget for 1864-65, a Plan and an Estimate of Rupees 8,250 for constructing new buildings for Sub-Magistrates' Cutcheries, subsidiary Jails and Police stations at Kytar, Verduputty and Velatikolum in the District of Tinnevely, duly countersigned by the Collector.
 2. Mr. Silver states that the Superintendent of Police mentioned to him that the accommodation allowed in the Plan for Police and prisoners is sufficient.

Referred to the Revenue Department.

Chepauk,
1st December 1863.

(Signed) C. A. ORR, Colonel, R. E.,
Secretary to Government, P. W. D.

No. 332.

ORDER THEREON, 18th December 1863, No. 2,331.

Approved.
(True Extract.)

[Signature]
Secretary to Government.

To the Board of Revenue.
" Department Public Works.

Exd. S. T. Augustin.

*Indorse in a letter from the
Superintending Engineer, to the
Secretary to Government, P. W. D.
dated 24th November 1863. J.
1276. P.W.D. 332.
407/8 4922/63.
Ca. 29031/63.
Abstract Estimate. C. A. Orr.
District Engineer.
Constructing Sub Magistrates
Cutchery subsidiary Jails
& Police Stations at Kytar,
Verduduputty & Velatikolum.*

Wm. H. B. Smith
Asst. Sec. of War
Dec 23 1863

Pro. R. Smith
Dec. 23 1863

Wm. H. B. Smith
Dec. 23 1863

Wm. H. B. Smith
Dec. 23 1863

Wm. H. B. Smith

Dec 23 1863

Communicated to the

Adj. Gen. S. D. Smith for
information & signature.

Wm. H. B. Smith

Dec 23 1863

Dec 23 1863