

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 133	Press
270-271	Mis.
Dated 15-1-	1866.

Not to be folded or roughly handled

END

*Proceedings of the Madras Government, Public Works Department,
15th January 1864.*

No. 270. Read the following letter from Captain E. A. FOORD, R. E., Superintending Engineer, 6th Division, to Colonel C. A. ORR, R. E., Secretary to Government, Public Works Department, dated Tanjore, 22nd December 1863, No. 1,414 :—

SIR,

With reference to my letter No. 620 of the 16th September last, I have the honor to forward for sanction and entry in the Budget of 1864-65, the revised Estimate amounting to Rupees 10,420 for constructing the road from the north bank of the Coleroon river to Woodiarpolliem in lieu of one of the same amount sanctioned by Government in November 1857. The full amount of the Estimate has been entered in the Budget for expenditure on this work in the ensuing year. The Estimate has been carefully revised by Supervisor Balasoondara Mudali.

No. 271. ORDER THEREON, 15th January 1864, No. 133.

1. The Government sanction for entry in the Budget of 1864-65, the revised Estimate of Rupees 10,420 submitted with this letter for a new road from the north bank of the Coleroon river to Woodiarpolliem:

2. It is observed that this order cancels the sanction accorded in Minutes of Consultation No. 2,148, dated 23rd November 1857, to an Estimate of corresponding amount for the same work.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 6th Division.
„ Controller and Auditor of Public Works Accounts.
„ Accountant General.

Exd. S. T. Augustin.

Work Constructing the Road from Combacorum to
 Kodiarpollum between North bank of the Col-
 room River and Kodiarpollum Length 9 Miles
 and 955 yards.

Quantity	Description of work	Rate	Amount	Amount of each part
14212½	Cubic yards	@	1 - 888 4 6	
49660	do	@	9 2327 13 -	
11581½	do	@	10 603 3 3	3819 4 9
	<u>Installing</u>			
123 46	Cubic yds	@	3 - 23¼ 14 -	
4360	do	@	6 - 1635 - -	3949 14 -
	<u>Clearing Jungles</u>			
203540	or 31 Cawney 80 Sonta & 20 yds	15 -	477 - 9	477 - 9
	<u>Road Tunnels.</u>			
6	at	200 -	1200 - -	
8	at	100 -	800 - -	2000 - -
	<u>Sundries &c</u>			173 12 6
	<u>Total Rupees</u>			10420 - -

Camp Madanacochy (signed) 16th December 1863. B. Balasundramudaly
 Supervisor &c
 In charge of 3rd Rang

Edwyl Captain R.E.
 Supg Engineer &c

Enclosure in a letter
from the Deputy Comm
An On Jan 14/65 dated
22nd December 1863
5418/63

Consider

N^o 133.

4x
5x

The Government

Sanction for entry in the Budget
of 1864/65 the revised Estimate of
Pt 11420 submitted with this letter
for a new road from the north
bank of the Coleroon river to Noddian
- pollicur -

2. It is observed that this
order cancels the sanction re-
- corded in mins of Govt N^o 2148
dated 23rd Nov^r 1857 to an Estimate
of corresponding amount for the
same work -

To The Sup^y. Engr^r 652.5
- Controller & Auditor of P.W. Works
- Accountant General -
Chapman &
15th Jan^y 1865
15th Jan^y 1865
15th Jan^y 1865

No 23rd November 1863
26th Sept 1863 587 588

P.W. 1863
No. of G.O. for 1863
from

The Supr. Engineer
to Do.

To
The Secretary to Govt.
P.W.D.

Dated 22nd Dec 1863
Recd 20

No. 1414

Enclosure one

No. 133-15th January

Forwarding for sanc-
tion and entry in the
Budget an Estimate
for the Road from
Leombacum to
Woodharpollin

With an Order

No. 270. 271

2, 8th Jan 1864. No. 121