

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No.	3027	Press
		Mis.
387-389.		
Dated	21-10-1864.	

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
21st October 1864.*

Read the following letters :—

No. 387. From Lieutenant-Colonel G. W. WALKER, R. E., Superintending Engineer, 7th Division, to Colonel C. A. ORR, R. E., Secretary to Government, Department Public Works, dated Luckady, 28th September 1864, No. 128.

SIR,

I have the honor to forward, for the sanction of Government, plan and estimate of a Police Station, proposed to be built at Ootacamund, at an estimated cost of Rupees 4,600, to be defrayed from the Budget allotment for the new Police works of the current year, in Coimbatore District.

Enclosures 2,

Referred to the Judicial Department.

CHEPAUK,
10th October 1864.

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government, P.W.D.

No. 388. Memorandum from the Chief Secretary to Government, Judicial Department ;—
(Here enter 14th October 1864, No. 530.)

No. 389. ORDER THEREON, 21st October 1864, No. 3,027.

1. The Governor in Council sanctions the estimate submitted by the Superintending Engineer, 7th Division, amounting to Rupees 4,600, for constructing a Hospital for the use of the Police at Ootacamund.

2. The cost of the work will be met from the source proposed by Colonel Walker.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 7th Division.

„ Accountant General.

„ Controller of Public Works Accounts.

„ Judicial Department.

Ed. T. O'Connor.

Judicial

New York

Estimated 11th of 1864 5

Melgherry Range
Colinbatu District

3

Work. Constructing a Hospital with out officers for the use
of the Police at Cotacamund

Description of Charges	Measurements			Contents
	L	B	H	
Hospital				
Foundation to walls and pillars including that of the intermediate basement	269.	26	3.	2017 6
Basement to D ^o including that of the intermediate basement between them	271.	2.	2.	1084 1/2
Left roughstone in Chunnam				3101 6
Principal side and End walls above	121.	16	14.	2541 "
Principal roof walls above	16.	16	14.	336 "
Verandah side and End walls above	21.	16	7 1/2	236 "
D ^o roof	16.	16	7 1/2	180 "
Principal Gable end	19.	16	3 1/2	90 3
Verandah D ^o	38.	16	3 1/2	185 3/4
Total				3568 6
Secret for openings left back in brick				511 6
Carving with Bricks in Chunnam	78.	7 1/2	"	305 1/2
Common boarded flooring with joists planks &c. Complete	40.	16.	"	585 "
Roofing with trunks rafters Bamboos reapers	47.	50.	"	640 "
Bamboos mats Common tiles &c.	"	"	"	2350 "
White washing and pointing with Chunnam	"	"	"	5117 "
Masonry chimney with shaft &c.	"	"	"	1
Panel doors Complete	7.	4.	"	3
D ^o	6.	3.	"	2
D ^o	5.	3 1/2	"	2
Glazed windows	36	26	"	3
D ^o	"	"	"	47 1/2
Wooden shelf for surgery and store room	"	"	"	2
Masonry Ventilators over the ridge	12.	16	7 1/2	135 "
12 Verandah Pillars above	7.	3 1/2	7 1/2	33 3
1 step including foundation	7.	2	1 1/2	239 3
Door and window frame left back in Chunnam	159 6	16	1	407 6

Abstract of Estimate No 15 of 1864-5

Carthwork for Excavating foundation & filling in
 Foundation of Pillars including that of the intermediate
 basement between them
 Basement to 6 Pillars including the intermediate basement
 Left rough stone in Chunnam
 Whitewashing
 Roofing with Couple rafters Bamboo reapers common tiles
 Paring with brick in Chunnam
 Carthwork for Excavating foundation and filling in
 Cope room
 Junction side and end walls
 Basement to do
 Side and end walls above
 Gable Ends

Carthwork for Excavating foundation & filling in
 Foundation of Pillars including that of the intermediate
 basement between them
 Basement to 6 Pillars including the intermediate basement
 Left rough stone in Chunnam
 Whitewashing
 Roofing with Couple rafters Bamboo reapers common tiles
 Paring with brick in Chunnam
 Masonry Jalousy
 Windows
 Bathing door
 Carthwork for Excavating foundation & filling in
 Foundation of Pillars including that of the intermediate
 basement between them
 Basement to 6 Pillars including the intermediate basement
 Left rough stone in Chunnam
 Side and end walls
 Gable Ends

Whitewashing to Screen wall
 And Plastering
 Brick in Chunnam to Screen and a line
 Flooring with jelly in mud
 Roofing with Couple rafters Bamboo reapers common tiles
 Glazed Bulb Eye
 Bathing Door
 Privy seats
 Carthwork for Excavating foundation & filling in

38	26	3	285
39	2	16	147
20	12		240
19	6	3	68
			15
42	26	3	313
42	2	16	147
42	16	46	442
22	16	10	61
			533
15	6	17	263
9	6	7	71
			2
3	6	26	1
6		3	17
38	26	26	2170
21	6	26	1234
38	3	6	38
			409
38	16	6	342
22	16	10	60
			403
			36
			372
			258
			536
21	6	6	193
7	6		56
13	6		239
2	16		1
6	3		
			216

Quantity	Particulars	Rate	Amount	Amount of each part
4354	Left Rough stone in Chunnam	20	8708	
3909	Left Brick in mud	15	5863	
702	Left Brick in Chunnam	26	1829	
724	Left Paring with brick in Chunnam	12	8688	
640	Common Flooring with first plank	45	2880	
3083	Do Roofing with trunks rafters reapers	50	15415	
5117	Bamboo reapers common tiles	2	10234	
536	Do whitewashing and pointing with Chunnam	2	1072	
1338	Do And Plastering	2	2676	
564	Do Whitewashing	8	4512	
47	Do Flooring with jelly in mud	2	94	
1	Left wooden Shelf	3	3	
1	Masonry Chimney	40	40	
1	Do Jalousy	10	10	
2	Do Ventilators	6	12	
3	Panel Doors	30	90	
2	Do	20	40	
2	Glazed windows	22	44	
3	Do	10	30	
2	Do	10	20	
2	Bathing Doors	18	36	
1	Glazed Bulb Eye	4	4	
165	Privy seats	10	1650	
	Left Carthwork	4	4	
			416	
			419615	
			403	
			403	
			400	

Handwritten at 10/100 Cents
 Gross Total

Executive Engineers Office
 Secunderabad 10th August 1864
 Assistant Engineer

Specification
 Amount of Estimate Rupees 4600.
 The Hospital proposed to be built is to be raised on a basement 2ft in height above foundations which are to be sunk 3ft, the principal walls and verandah pillars to be 14 & 7 1/2 ft high respectively. The building is to contain 4 rooms

Wunderlich
Superior

I have the honor to be
Sir,
Your most Obedt Servant.
J. Walker Lieut Col
Superintendent Niagara
70.

[illegible]

Referred to the
Judicial Department.

Chas. R. E.

Secy to Govt. P. W. D.

Chas. R. E.
12 Oct 64

Y. 87.

727 1864. 22
Judicial Dept. Oct 22

The Chief Engineer
7th Division

The Secretary to Government

D. M.

W. L. 4 89/64

Dated 28th September

Received 6 Oct 64
Here 11 Oct 64

With enclosure

11/28

Enclosure

No 2083

Forwards Plan and Estimate
for the construction of
Government, for Police

Hospital at Ootacamund
and states that the cost
viz. Rs 4600 may be defrayed
from the Budget allocation
for new Police Building

218 3027-218 Oct 1864

N. 387

12 Oct 64

Judicial DEPARTMENT.

No. 530

MEMORANDUM.

From the Inspecting Engineer
Division dated 28th September
1864 No 128

The Chief Secretary has the honor to
return the letter noted in the margin, together
with the Plan and Estimate which accompanied
it for the construction of a Police Hospital
at Ootacamund
and to inform Colonel Orr that he sees no
objection to the Plan.

Fort St. George,

14 October 1864.

C. J. Curthrust
Chief Secretary.

The Secretary to Government,
Public Works Department.

M. B. King

one room 30'x16', one 16'x10', one 12'x8' and one 10'x8' having
 rear and front an open verandah 8ft wide - The
 sides with two outoffices, viz a 12'x8' and a 10'x8'

To H 1864 Sept
 'Pro. off' for Oct
 No 4489
 From
 The Chief Secretary
 to Government
 Ind. Dept.
 Dated 14th October 1864
 Recd 15th October 1864
 No 530
 B.

Approving the
 Estimate of Rs 4600 for
 constructing a Police Hos-
 pital at Colacamund,
 Coimbatore Dist.

No 388

No 3027-21st Oct/64

No 3027
 of the Madras Government
 Under date the 21st October 1864
 the
 Send the following

Engineer J. D.
 Plan and Esti-
 mation of Port for
 Colacamund and
 with Papers 4600
 from the Budget allst
 id Buildings.
 Secy to Govt
 Ind. Dept
 of the Estimate
 constructing a Police
 Hospital at Colacamund.

(Here enter 28th September 1864
 No 128)

(Here enter 14th October 1864
 No 530)

The Governor
 in Council permits
 the Estimate submitted
 by the Superintending
 Engineer of Division
 amounting to Rs 4,600
 for constructing a
 Hospital for the use
 of the Police at
 Colacamund

D
 W

The cost of the
work will be met from
the source proposed
by Colonel No.

L.H.

Supr. Engr. 7th Div ✓
" Scott Engr ✓
" Controller ✓
" Judicial Secy ✓

Sept 22 - October

4071864 Dept
Pro: of Govt for O.C.

No. 0027
Pro: of Government
29/21 Oct/64

Approved
19/10/64

Estimate of Rs.
4600 for constructing
a Hospital for the
use of the Police at Oota
Command. Coimbatore
District sanctioned.

No. 007/009