

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works **DEPARTMENT.**

G.O. No. 3370	Press ~~Mis.~~
488-489	
Dated 24-11-18	64.

Not to be folded or roughly handled

16

*Proceedings of the Madras Government, Public Works Department,
24th November 1864.*

No. 488. Read the following Proceedings of the Madras Government in the Revenue Department:—

Approving of the estimate of Rupees 12,100 for constructing } (Here enter 17th November 1864, No. 2,111.)
a Taluq Cutcherry at Adoni, Bellary District.

No. 489 . ORDER THEREON, 24th November 1864, No. 3,370.

1. Communicated to the Superintending Engineer, 3rd Division.
2. The work should not be proceeded with until funds are specially provided for it by Government.

(True Extract)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 3rd Division.

„ Accountant General.

„ Controller of Public Works Accounts.

Exd. S. T. Augustin.

Abstract Estimate for constructing a Taluk Kutcherry at Adoni Bellary District

96

Quantity	Description of work	Rate	Amount	Total
24205	cubic feet Stone in mud	1	1325 5	
6830	Do Burnt Brick in chumam	3	6149 1	
562 1/2	Do Flat Arch work	4	140 10	
718 1/2	Do Circular arch work with centring	5	224 8 6	
670	Quare feet bordon or moulding work	4	167 8	
144	Sq yds Rustic work for Quoins	8	72	
256	Squares Plastering with 2 coats of chumam	3	156 10 16	
55 2/3	Do Flooring with stone slabs	12	8	668
15	Do Graveling in courtyard	28	2	8
230	Quare feet Stone flags between Pillars and Steps	5	4	75 10 8
74	Do Stone Slabs	6	27	12
47 1/3	Squares Terracing with 13 Inches square Bricks on Captain Falloch's Plan including wood work per square	43	2055	64
18 3/10	Squares Verandah Roofing with Palmyrah Rafters, Risers, Nails, Flat Paints and chumam borders &c	30	542	11 2
180	Running feet Prefummers	5	56	4
1	Circular Entrance Gate 6' x 9'			90
8	Pairs of Batten Doors 3 1/2' x 6 1/2'	20	160	
5	Do Do 4' x 7'	25	125	
2	Iron Barred Doors to Treasury 3 1/2' x 6'	35	70	
12	Batten Windows 3' x 4'	14	168	
14	Do Iron Barred windows 3' x 4'	18	252	
6	Iron Barred Allic windows with weather board 3' x 1 1/2'	10	60	
2	Do Do Do 3' x 2'	12	24	
567	Square feet Iron Railings	1	8	550 8
72	Do Wooden Do	39	28	1 3
4	Do Do Barred Doors	8	32	
20 1/2	Squares Green paint to Doors and Windows &c	4	82	
36	Do Mould for joints	3	2	112 5
1	Trap Door			20
1	Ladder to Roof			10
	Carried forward			9953 5 11

Quantity	Description of work	Rate	Amount	Total
	<u>Brought forward</u>		9983 5 "	
A Well 6 feet in diameter	" " "	70 "	" "	" "
470 cub yds of excavating foundation and filling in Basements	" 2 "	58 12 "	" "	" "
			10112 1 "	
Sundries and Superintendence	" "	1007 14 1	" "	11120 " "

	<u>Prany for Kutcherry servants</u>			
826 1/2 cub ft stone in mud	" 1 "	57 10 8	" "	" "
132 " " Brunt Brick in chumam	" 3 6	28 14 "	" "	" "
11 3/5 Squares Pointing	1 8 "	16 10 10	" "	" "
2 18/25 " " Roofing with Palmyrah Coupler 78 "	30 " "	81 9 7	" "	" "
1 1/2 " " Flooring with Brick jelly in chumam	5 " "	7 8 "	" "	" "
1 Turn Pike	" " "	3 " "	" "	" "
20 cub yds Excavating foundations	" 2 "	2 8 "	" "	" "
		191 12 11	" "	" "
Sundries	" " "	18 3 1	" "	210 " "

	<u>Open Latrine for Prisoners</u>			
911 cub feet stone in mud	" 1 "	58 15 "	" "	" "
186 1/2 " " Brick in chumam	" 3 6	40 11 10	" "	" "
14 21/25 Squares Pointing	1 8 "	22 4 1	" "	" "
2 4/25 " " Flooring with Brick & jelly 78 "	5 " "	10 12 9	" "	" "
2 " " Turn Pike	3 " "	6 " "	" "	" "
20 cub yds Excavating foundation	" 2 "	2 8 "	" "	" "
		139 3 8	" "	" "
Sundries	" " "	10 12 4	" "	150 " "

	<u>Shed for Ryots and others</u>			
816 cub ft stone in mud	" 1 "	57 " "	" "	" "
253 1/10 " " Brick in chumam	" 3 6	55 7 " "	" "	" "
7 13/50 Squares Plastering with 2 coats of khamam	3 15 6	28 13 " "	" "	" "
1 1/10 " " Pointing Basement	1 8 "	1 10 4	" "	" "
4 1/25 " " Flooring with Stone Slabs	12 8 "	55 8 "	" "	" "
82 Cub ft Stone Slabs over retaining walls	" 3 "	15 6 "	" "	" "
<u>brought forward</u>		207 13 3 11480 " "		

Quantity	Description of work	Rate	Amount	Total
	<u>Brought forward</u>		207 13 3 11480 " "	36
40 Squares Stone Slabs 1 1/2 x 1 1/2 x 1 1/4	" 6 " "	15 " "	" "	" "
9 3/5 " " Roofing with Palmyrah Rafters, Reapers, Nails, Flat and Pantiles & khamam borders	30 " "	288 " "	" "	" "
		78 " per square	" "	" "

44 cub yds Earthwork excavating foundation and filling in Basement	" 2 "	5 8 "	" "	" "
140 Running feet Preferrers and ridge poles	" 5 "	43 12 "	" "	" "
		560 1 3	" "	" "

Sundries and Superintendence 78 "	59 14 9	620 " "
-----------------------------------	---------	---------

Total Estimate Rupees 12100 " "

Buddapah
Supdy Engineer's Office
1st November 1874.

Quarry

Leut. Col. R.E.
Supdy. Engineer
3rd Division

*Proceedings of the Madras Government, Revenue Department,
17th November 1864.*

No. 214. Read the following letter from Lieutenant-Colonel E. HEMERY, R. E., Superintending Engineer, 3rd Division, to Colonel C. A. ORR, R. E., Secretary to Government, Public Works Department, dated Cuddapah, 1st November 1864, No. 129:—

Sir,
1. With reference to a note at the foot of letter No. 2,674, dated 14th September last, from the Deputy Secretary to Government, Fort Saint George, Public Works Department, to the Secretary to the Government of India, Public Works Department, I have the honor

1 Plan.
1 Estimate.
1 Specification.

herewith to forward a Plan and an Estimate amounting to Rupees 12,100 for a Talook Cutcherry at Adoni, according to the last Standard Plan sanctioned by Government, and approved of by the Board of Revenue, and by the Inspector General of Police.

2 The Estimate was, in the first instance, prepared by Major Flint, when in charge of the Bellary Range, the rates have been carefully revised by Mr. Clardge, Supervisor now in charge of that range, and again in my Office; and although the amount required is large, I am confident that the building could not be constructed at Adoni for a smaller sum, as all the iron and wood work will have to be sent from Bellary, a distance of 43 miles.

Referred to the Revenue Department.

CHEPAUK,
8th November 1864.

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government, P. W. D.

No 215

ORDER THEREON, 17th November, 1864, No. 2,111.

Miscellaneous.

Approved.

(True Extract.)

Charles A. Orr
Secretary to Government.

To the Public Works Department,
the Board of Revenue.

Exd. S. T. Augustin.

*Abstract
Estimate for building a
Talook Cutcherry at Adoni
in the Bellary District
Cannara
17/11/64*

*22/11/64
24/11/64
Rev: 2926/64*

