M.R.O. 1—77,906—8-6-37.

(1) Number of pages.....

(2) Date of repair.....

(3) Initials of the Referencer.....

MADRAS RECORD OFFICE.

Government of Madras.

public works. **DEPARTMENT.**

G.O. No. 47. Press ~~Mis.~~

99-100

Dated 7-1- 1864.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 7th January 1864.

No. 99. Read the following Proceedings of the Madras Government in the Military Department:—

Approving of the Estimate of Rupees 780 for constructing a masonry open drain and a tunnel near the Horse Artillery Lines in the Recruit Depôt at Saint Thomas' Mount, Madras District. (Here enter 22nd December 1863, No. 4,078.)

No. 100. ORDER THEREON, 7th January 1864, No. 47.

1. Communicated to the Superintending Engineer, 4th Division, for information and guidance.

2. The cost* of the work will be met from the current year's Reserve.

* Rupees 780.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 4th Division.
„ Accountant General.
„ Controller and Auditor of Public Works Accounts.

Exd. S. T. Augustin.

BUILDINGS

ABSTRACT of Estimate No. of 186 -6

DISTRICT

WORK Constructing a masonry Open Drain and a Tunnel of 1 Vent near the Horse Artillery Line in Recruit Depot at the Mount.

Quantities.	Description of Work.	Rate. Rs.	A.	P.	Amount. Rupees.	Amount. of each part. Rupees.
	Open Drain.					
44	Cc yds of Brick in chunam @ Cc yd	3	8	"	347	
26	Sqs of Plastering with Do @ Sq	2	4	"	58	
8	Do Do asphalte	22	"	"	176	
118	Cc yds of Earth work @ Cc yd	"	2	"	15	
						596
	Tunnel of 1 Vent.					
17	Cc yds of Brick work in chunam @ Cc yd	3	8	"	59	
7	Do Arch work in Do Do	1	12	"	33	
3	Sqs of Plastering with Do @ Sq	2	4	"	7	
1	Do Do with asphalte Do	22	"	"	22	
26	Cc yds of Earth work @ Cc yd	"	2	"	3	
						124
						720
	Sundries &c	"	"	"		60
	Total Estimate Rupees					780

Sup[d] Eng[r] Office 4[th] Division
Madras
9 December 1863.

Lieut Col[l] R.E.
Sup[g] Engineer 4[th] Division

Quantities.	Description of Work.	Rate.			Amount.	Amount. of each part.
		Rs.	A.	P.	Rupees.	Rupees.

Enclosure
In a Letter from
Superintending Engineer
4th Division
dated 9th December 1863
No 3919

To

The Secretary to Govt
P. W. Dept

Dated 9th December 1863
Received
the 22nd December 1863
No 3919

Abstract Estimate for Constructing Masonry Open Drain and a Tunnel of 17 Feet Head for the Horse Artillery Lines in the Recruit Depôt at the Station in the District of Madras Amounting to—

Rupees 780—

MILITARY DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following letter:—

From the Superintending Engineer, 4th Division, Madras, 9th December 1863, No. 3919; to the Secretary to Government, Public Works Department.

I have the honor to forward, for the early sanction of Government, Sketch and Estimate amounting to Rupees 780, for constructing a masonry open Drain of exactly the same character as the existing Drains at the Station, and a Tunnel near the Horse Artillery Lines in the Recruit Depôt at Saint Thomas' Mount.

Enclosures.
1 *Specification.*
1 *Sketch.*
1 *Abstract Estimate.*

2. The work is represented to be necessary for the health of the inhabitants of the family Lines, and as it has been approved of by His Excellency the Commander-in-Chief and the Major General Commanding the Division, I request that the Estimate may be authorized for execution from the Reserve Fund of the current official year.

Referred to the Military Department.

(Signed) C. A. ORR, Colonel, R. E.,
Secretary to Government, P. W. D.

11th *December* 1863.

ORDER, No. 4078, 22*nd December* 1863.

Approved.

(True Extract.)

Deputy Secretary to Government.

To the Pub. Works Dept., with three enclosures. 420 Spare Copies.
„ Quarter Master General.

Exd. T. Stubbs.

Dublin 1780