

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works **DEPARTMENT.**

G.O. No. 49	Press
183-104	~~Mis.~~
Dated 7-1-	1864.

Not to be folded or roughly handled

✓

17

*Proceedings of the Madras Government, Public Works Department,
7th January 1864.*

No. 103. Read the following Proceedings of the Madras Government in the Military Department:—

Approving of the Estimate of Rupees 360 for constructing
a Bath-room to the Hospital Serjeant's Quarters and one
to the Matron's Quarters at the Garrison Hospital, Saint
Thomas' Mount, Madras District. } (Here enter 23rd December 1863, No. 4,085.)

No. 104. ORDER THEREON, 7th January 1864, No. 49.

1. Communicated to the Superintending Engineer, 4th Division, for information and guidance.

• Rupees 360.

2. The cost* of the work will be met from the current year's Reserve.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 4th Division.

„ Accountant General.

„ Controller and Auditor of Public Works Accounts.

BUILDINGS

ABSTRACT of Estimate No.

of 186 -6

(New Work)

57

DISTRICT Madras

WORK Constructing a Bath room to the Hospital Sergeants Quarters and one to the Quarters at the Garrison Hospital St. Thomas Mount.

Quantities.	Description of Work.	Rate.			Amount.	Amount. of each part.
		Rs.	A.	P.	Rupees	Rupees.
265	62 ft. of Brick chumnam 7/2 be ft	"	2	1	34	
32	D ^o of arch work in D ^o D ^o	"	3	6	7	
522	Spff of Plastering with 2 coats 7/2 be ft	2	4	"	12	
100	D ^o of with 8 Square tiles over	"	"	"	"	
	2 layers bricks 7/2 Square	8	8	"	9	
162 1/2	D ^o of Bengal roofing on Palmarah	"	"	"	"	
	rafters complete 7/2 Square	22	"	"	36	
1	Teakwood Butten Door 1 x 6 - com					
	plete	21	"	"	21	
1	Teakwood Panel Door 1 x 7 complete	28	"	"	28	
1	D ^o Venetian window - 1 x 5 - D ^o	24	"	"	24	
63 3/4	62 ft of breaking out masonry	"	"	4	1	
	Excavating foundation and	"	"	"	"	
	Sandries	"	"	"	8	
	Total for one				180	
	Total for Two	"	"	"		360

Sup^d Engr^s office to the Division
Madras
1862-

Sup^d Engr^s 4th Division
Lieut. Col. R. E.

Quantities.	Description of Work.	Rate.	Amount.
-------------	----------------------	-------	---------

Enclosure
 In. a/c 5391
 From 524/3
 The Sup^r Engineer
 4th Division.

To
 The Secretary to Govt.
 G. P. W.

Dated 11-

Received

No 3996

Abstract Estimate for
 Constructing a Bath-room to
 the Hospital Serjeants Quarters
 and one to the Matrons Quarters
 at the Garrison Hospital St.
 Thomas Mount in the Dist^t
 of Madras Amounting to
 Rupees. 360.

In No 5336 of 1863.

MILITARY DEPARTMENT.
 PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following papers:—
 From the Superintending Engineer, 4th Division, Madras, 11th December 1863, No. 3996; to the
 Secretary to Government, Public Works Department.

I have the honor to submit for the orders of Government, an Estimate amounting to Rupees 360, for constructing a Bath-room to the Hospital Serjeant's Quarters, and one to the Matron's Quarters at the Garrison Hospital Saint Thomas' Mount.

Enclosure.
 1 Estimate.

2. The Estimate has been prepared in communication with the Garrison Surgeon, and approved of by His Excellency the Commander-in-Chief, and the Officer Commanding the Mount; and I recommend that sanction be given for its execution this year from the Reserve Fund.

Referred to the Military Department

(Signed) C. A. ORR, Colonel, R. E.,
 Secretary to Government, P. W. D.

15th December 1863.

Order, No. 4085, 23rd December 1863.

Approved.
 (True Extract.)

Deputy Secretary to Government.

To the Public Works Dept., with an Estimate. 420. 6/10. 1/10.
 " Quarter Master General.

Frd. J. E. Cashart.

