

(1) Number of pages_____

(2) Date of repair_____

(3) Initials of the Referencer_____

MADRAS RECORD OFFICE.

Government of Madras.

DEPARTMENT.

G.O. No.	627	Press Mis.
Dated	18	

Not to be folded or roughly handled

16

*Proceedings of the Madras Government, Public Works Department,
3rd March 1864.*

No. 63. Read the following letter from Colonel A. J. M. BOILEAU, R. E., Superintending Engineer, 4th Division, to Colonel C. A. ORR, R. E., Secretary to Government, Public Works Department, dated Madras, 27th February 1864, No. 5,343 :—

SIR,

1 Plan.
1 Abstract Estimate.

1. With reference to the Proceedings of Government No. 3,513, dated 30th November 1863, I have the honor to submit for sanction Plan and Estimate amounting to Rupees

7,370 for excavating new Salt Channels at Kattur in the Madras District.

2. The project having been already approved of by the Board of Revenue and the Acting Collector, I have not thought it necessary to refer to them again on the subject. The full amount of the Estimate I have entered in Statement No. III furnished under the Orders of Government No. 3,681, dated 14th December 1863, as Mr. Executive Engineer Kennedy reports that the whole sum will be expended by the 30th April next.

No. 64. ORDER THEREON, 3rd March 1864, No. 637.

The Estimate submitted with this letter, amounting to Rupees 7,370, is sanctioned for immediate execution from the Reserve Fund.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 4th Division.

„ Accountant General.

„ Controller and Auditor of Public Works Accounts.

„ Revenue Department.

Exd. S. T. Augustin.

Salt Channel

New Work

Detailed Estimate N^o of 1863/64District Madras, Talug Ponnary, Village Katoor, ³⁶
Work. - Excavating Salt Channels at Katoor.Vide Memo of Super^r Engineer H^o Div^o N^o 2920 Dtd 15th October 1863

Particulars of Work	Measurement				Cubical Contents
	Length	Breadth	Depth		
	ft	ft	ft	ft	
Excavating Channel - - - - -	4500	45	3	-	607500 cft
or Earthwork Cubic yds - - -					<u>22500</u>
Do - - - - - Do - - - - -	6900	23	4	-	634800 cft
Do - - - - - Do - - - - -	1500	24	4	-	162000 cft
Total Cubic feet					796800
or Earthwork cubic yds					<u>29511 1/3</u>
Making embankment to separate Lagoon from back water - - - - -	825	42	3	-	103950 cft
or Earthwork cubic yds					<u>3850</u>

C. S. Canal Office
Adyar
7th January 1864R. Kennedy
Special Engr^r

New work

Salt Channel

Abstract Estimate No of 1863/64

District Madras, Taluq Ponnary, Village Katoor.

Work.- Excavating Salt Channels at Katoor.-

Vide Memo of Super^r Engineer & Div^r No 2920 Dated 15th October 1863.

Quantities	Description of Charges	Rate	Amount	Total
23500	Cubic yds ² Earth work for excavating Channel (working in water)	" 2 1/4	3281	
29511	do - do - for excavating channel working in mud and water including baling and putting platforms in section	" 1 10	3381	
5850	Cubic yds ² Earth work for making embankments to separate Lagoon from backwater, carried 80 yards	" 1 6	361	
	Superintendence and Sundries at about 5 per cent	" "	347	
				Total Estimate Rs - 7370.

C. C. Canal Office
Adyar
7 January 1864
G. J. H.

R. Kennedy
Special Executive Eng^r

Est 1864 L. 11

est 637

The Estimate submitted
with this letter amounting to Rs.
7370 is sanctioned for immediate
execution from the ~~fund~~
~~and for it in G.O. No~~

[Signature]

[Signature]

[Signature]

[Signature]

Chepauko
3rd March/64

[Signature]

Supd. 4th March
Recd. 4th March

Recd. 4th March

Cont. & Under Recd.

Recd. 4th March

282

of

Mr. Kennedy

Special Officer

to

The Deputy Engineer

at

Estimate
No. 2

9377 862/64

Estimated and abstract

for account of

Amount of Estimate Rs. 7370

Amount of estimate Rs 1370.

1864
To the Secy to Govt
The Public Works Dept
No. 100

To the Secy to Govt
9th Feb 64

Dated 23 February
Recd 29 1864
82. No 5343.

Submits for sanction
Plan & Estimate
amounting to Rs 1370
for excavating the
salt channels at
Kattur in the Madras
District.

1864

No 637-3rd March 64-