

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No.	649	Press ~~Mis.~~
Dated	4	18 64

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
4th March 1864.*

No. 87. Read the following letter from Lieutenant-Colonel G. W. WALKER, R. E.,
Superintending Engineer, 7th Division, to Colonel C. A. ORR, R. E., Secretary
to Government, Department Public Works, dated Searady, 17th February 1864,
No. 336 :—

SIR,

I have the honor to submit herewith the Plan and Estimate for
a market shed at Coonoor, called for in your Memorandum No. 93 of
18th December, and entered as Item No. 33 of the Coimbatore Dis-
trict Budget for 1864-65.

Two Enclosures.

* Rupees 2,000.

No. 88. ORDER THEREON, 4th March 1864, No. 649.

1. The Governor in Council sanctions the Plan and Estimate amounting to Rupees 2,000
for a market shed at Coonoor.

2. As no provision has been made for the work in the Budget for 1864-65, the Superin-
tending Engineer will be requested to submit an application for funds after the 1st May next.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 7th Division.

„ Controller and Auditor of Public Works Accounts.

„ Accountant General.

Revised Detailed Estimate No 32 of 1863/4
 Nilgerry Range
 Coimbatore District

Work. Constructing a Market shed at Coonoor called for
 in Pro-Memo. Govt No 2392 of 21st Aug 63

Particulars of Work	Length	Breadth	Height	Contents
Foundation to 26 Side and End Pillars	65	2.6	2.6	406.3
Basement to 26 do do do	52	2.6	9	78
26 Side and End Pillars above	39	1.6	9	526.6
Total cubic feet of Brick in Churnis				1010.9
Foundation to the Intermediate Walls				
between Pillars	165	1.9	2.6	721.02
Total cubic feet				721.10 1/2
Do do yards of rough stone in mud				26.53
Intermediate walls between Pillars above	106	9	9	715.6
Do do do do do	38.8	9	4.6	130.6
Basement to the Intermediate walls				
between Pillars	178	1.8	9	105.10 1/2
Total cubic feet of Brick in mud				1012.10 1/2
Total square feet of Flooring with jelly				
in mud	100	12		1200
Do of Whitewashing				3801
Do of Roofing with rafters. Purlins				
Trusses. Summers. Ridge Poles complete	106	22		2332
Cubic feet of Granite stone in mud				
for edging to entrance of the shed	38.9	1	38 3/4	
Cubic yards of Earth Work for				
excavating. Foundations and				62.8
filling in				

Abstract Estimate No. 32 of 1863/4

Quantity	Particulars of Charges	Price	Rate	Amount	Total
10129	Total cubic feet of Brick in Chimney	27			
2657	Total cubic yards of rough stone in mud	2			
101214	Total cubic feet Brick in mud	19			
1200	Total square feet of Flooring with jelly in mud	4			
8801	D ^o of Whitewashing				
2332	D ^o of Roofing with Rafters				
1011	Peepers. Trusses. Summers	50			
82	Ridge Pole. D ^o complete				
383	Cubic feet of granite stone in mud for edges to entrance of the shed				
623	Cubic yards of Earth Work for excavating foundations and filling in				
	Total				

Sundries and contingencies about 18193.
Total of Estimate Rupees 18013.

2000

Executive Engineer's Office

At Coimbatore

28th November 1864

W. M. M. Major

Executive Engineer

Specification

Amount of Estimate Rupees 2000

The building is to be raised on a basement $\frac{3}{4}$ foot in height above foundations which are to be sunk 2 $\frac{1}{2}$ feet. The Pillars and the intermediate walls

between them are to be 9 feet high except the walls between the Front Pillars which are to be raised ^{commensurate} 4 $\frac{1}{2}$ feet high for the allowance of light in the building. The building is to contain one room 100 feet long by 12 feet broad with a pent roof ~~over~~ over it which consists of Rafters Peepers Pantiles. Trusses. Summers &c complete

W. M. M. Major
Executive Engineer

W. M. M. Major
Sup. Eng. 7, Du

W. M. M. Major
Collector

10/10/10

Supp. Cuzco y D^a

