

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No.	662	Press
		Mis.
Dated	23	18 66.

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
5th March 1864.*

111. Read the following Memorandum from A. J. ARBUTHNOT, Esq., Chief Secretary to Government (Judicial Department), to the Secretary to Government, Department Public Works, (with a letter and two enclosures), dated Fort Saint George, 25th February 1864, No. 94:—

The Chief Secretary has the honor to transmit to the Secretary to Government, Department of Public Works, the enclosed letter* from the Inspector General of Police, from which it appears that the Plan of the projected Police Station House at Wellington is well adapted for the purpose.

from Lieutenant-Colonel J. TEMPLE, Acting Assistant Inspector General of M. Police, to A. J. ARBUTHNOT, Esq., Chief Secretary to Government, Fort Saint George, dated Madras, 19th February 1864, No. 353.

SIR,

1. I have the honor, in the absence of the Inspector General, to return the Plan and Estimate for enlarging the Police Station House at Wellington received with Government Order 156, dated 8th February 1864.

2. The alterations proposed are very necessary and appear judiciously arranged. The Plan has been countersigned by the Inspector General.

112. ORDER THEREON, 5th March 1864, No. 662.

1. The Governor in Council sanctions the Estimate submitted with the letter from the Superintending Engineer, 7th Division, No. 232, dated 21st November 1863, for alterations and additions to the Police Station House at Wellington.

2. Funds have been provided for the work in G. O. No. 297, dated 23th January 1864.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 7th Division.

- „ Accountant General.
- „ Controller and Auditor of Public Works Accounts.
- „ Judicial Department.

No. 4.

Detailed Estimate No. 25 of 1883

Mildmay Range 3

Coimbatore District

Work - Making certain alterations and additions to the
Police Station House at Wellington

Particulars of Work	Length	Breadth	Height	Content
Foundation to Side & End additional wall	38'-0"	2'-6"	3'-0"	285'-0"
Do. to 2 Partition walls	16'-6"	1'-9"	2'-0"	579'-0"
Total Cubic feet				342'-9"
Do. Do. Yard of rough stone in hand				12'- ²⁵ / ₈
Foundation to 2 Steps	8'-0"	1'-9"	1'-0"	14'-0"
2 Steps above	8'-0"	1'-0"	6'-0"	4'-0"
Door & Window frames	30'-0"	1'-6"	1'-3"	150'-0"
Total Cubic feet of Brick in Churnam				188'-0"
Basement to Side & End walls	38'-0"	2'-0"	1'-0"	76'-0"
Do. to Partition wall	16'-6"	1'-6"	1'-0"	25'-1 ¹ / ₂
Side & End wall above including Parapet	51'-6"	1'-6"	13'-3"	1023'-6 ³ / ₄
Partition Do. Do.	17'-6"	1'-9"	11'-1"	145'-5 ⁵ / ₈
Total				1270'-1 ⁷ / ₈
Deduct for Openings				282'-1 ⁷ / ₈
Total Cubic feet of Brick in hand				942'-0"
Do. Square feet Boarded flooring with joints, Planks &c. Complete	27'-9"	10'-0"		277'-6"
Square feet of Plastering with Churnam				1599'-0"
Do. Ceiling the 2 Back up Rooms with joints, Planks &c. Complete	15'-0"	12'-0"		180'-0"
2 Pair Battens Doors	7'-0"	4'-0"		"
1 Do. Do.	7'-0"	2'-6"		"

2	Glazed Windows Complete	4	4		
	Pulling down the Verandah Roofing				
	Masonry work &c & cleaning the spot				
	4 sq. feet of Terracing with joints Brick on Edge &c Complete	28	6	10	285
	Repairing the side Eue of the Verandah Roof over Terrace				
	Total running feet of Cornice work in Chumam				54 1/2
	Removing the Iron Bars of Lock up and making a doorway				
	Cubic yds of Earthwork for excavating foundations & filling in				

Abstract Estimate No. 25 of 1883

Quantity	Description of Charges	Price	Rate	Amount	Total
12 3/8	Cubic yds of Rough Stone in hand	2	25	6	
168	Do. feet of Brick in Chumam	26	43	11	
942	Do. Do. Do. in hand	18	17	7	
277 1/2	Square Do. of Boarded Flooring with joints Planks &c Complete	96	266	6	
1599	Do. of Plastering with Chumam	6	95	15	
180	Do. Ceiling the 2 Lock up Rooms with joints, Planks, &c Complete	50	90		
2	Fair Bathing Doors	40	80		
1	Do. Do. Do.	20	20		
2	Glazed Windows	20	40		
	Pulling down the Verandah Masonry work &c & cleaning the spot				74
	Carried over				

	Brought forward				853	3
285	4 sq. feet of Terracing with joints Brick on Edge &c Complete	70	199	8		
	Repairing the side Eue of the Verandah Roof over Terrace			5	6	
54 1/2	Running feet of Cornice work in Chumam	8	27	4		
	Removing the Iron Bars of Lock up and making a doorway			6		
17 1/2	Cubic yds of Earthwork for excavating foundations & filling in	2	2	3		
						1093 8

Lundries & Contingencies about 10 1/2 Cent 106 8

Total Estimate Rupees 1200

Executive Engineer's Office
P.O. Secunderabad
1st November 1883

Major
Executive Engineer

Specification

Amount of Estimate Rupees 1200

The addition room to the Police Station House is to be raised on a basement of 1 foot in height above foundations which are to be sunk 3 feet. The walls are 10 3/4 feet high under the Terrace roof.

The Room is to contain 2 Apartments
1. Do. 20 1/2 feet long by 10 feet broad
1. Do. 10 do do by 10 do do

Amthor Lieut Col. Major
Sup. Engr. J. D. Executive Engineer

As per order of the Government

General Department
No 353

Chief Office of the Insp^l Genl
of Madras Police
Madras 19th February 1864

From
Lieut Colonel Temple
Ag^t Insp^l General
of M Police
To,
A. J. Arbutnot Esqre
Chief Secretary to Government
Fort Saint George

Sir,
I have the honor in the absence
of the Inspector General to return the
Plan and Estimate for enlarging
Police Station House at Wellington.
received with Government Order No
156 dated 8th February 1864.

2. The alterations proposed are
very necessary and appear
judiciously arranged. The Plan has
been countersigned by the Inspector
General.

I have the honor to be,
Sir,

Your Most Obed^t Serv^t.
Lieut Col
Ag^t Insp^l Genl of M Police

C. P. W.

For side
by the
Inspector General
of Madras Police
at Wellington
Madras 19th Feb 1864

No. 353 of 1863.

14/4/64

14/4/64

14/4

14/4

