M R O. 1—77,006—8-6-37.

(1) Number of pages _____

(2) Date of repair 13-5-2

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 3453 Press / ~~Mis.~~

40-41

Dated 2-12- 1864.

Not to be folded or roughly handled

23.10.42

Proceedings of the Madras Government, Public Works Department, 2nd December 1864.

No. 40. Read the following Proceedings of the Madras Government in the Military Department :—

Approving, for entry in the Budget of 1865-66, of the estimate of Rupees 8,840 for levelling the Ramparts of the Fort at Kurnool, within the Military limits. } (Here enter 24th November 1864, No. 4,190.)

No. 41. ORDER THEREON, 2nd December 1864, No. 3,453.

Communicated to the Superintending Engineer, 3rd Division, for information and guidance.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 3rd Division.
" Accountant General.
" Controller of Public Works Accounts.

Exd. T. O'Connor,

Ja Thompsons

3

Boston Feb 18 1771

24 1771 Mch

Sir I

Estimate of the Probable expense for Demolishing the Ruined Rampart and Glacis of Runnool Fort

Remarks	Name of Items	Measurement: Length	Breadth	Depth	Sup. Ft.	Cub. Ft.	Description of Works	Rate	Rs	Amount of Each Item	Amount of Each work
		1040	18	2.62	-	490464.0	A 5.24 ÷ 2				
		1040	42	10.14	-	442915.20	B 20.28 ÷ 2				
		1040	25	8.625	-	224250.00	C 17.25 ÷ 2				
		1040	8	1.1050	-	9193.60	D 2.21 ÷ 2				
		110	22	10.00	-	24200.00	E 20.00 ÷ 2				
		1040	48	10.00	-	468000.00	F 20.00 ÷ 2				
Remarks	Cutting & Levelling				Total	1217603.20	= 45096½ Cubic Yds. Cutting & Levelling	1	-	45096	7516 1 4
		347					Running Yards of Ruined Rampart	1	8	347	520 8 -
							Superintendence & Sundries at about	10	-	7½	803 6 8
										Total Rupees	8840 - -

Runnool
1st Range Office
October 1861

C. Mumm

Sub Engr. Engineer
3d Divn

H. Birch

James Flint Major
1st Assistt Engineer in Charge of
Runnool Range.

851.

MILITARY DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following paper :—

From the Superintending Engineer, 3d Division, Cuddapah, 1st November 1864, No. 130, to the Secretary to Government, Public Works Department.

I have the honor herewith to forward, for sanction and entry in the Budget of 1865-66, Plans and an Estimate amounting to Rupees 8,840, for levelling the Ramparts of the Fort of Kurnool, within the Military limits.

3 *Enclosures.*
1 *Estimate.*
1 *Plan.*
1 *Section of do.*

2. This work was entered in the List of Original works to be included in the Budget of 1864-65, forwarded to Government by the Quarter Master General with his letter, No. $\frac{201}{707}$, dated 2nd September 1863; but knowing that funds were not available this official year, I did not submit the Estimate for sanction at an earlier date.

3. The Plans and the Estimate have been approved of by His Excellency the Commander-in-Chief.

Referred to the Military Department.

(Signed) C. A. ORR, Colonel, R. E.,
Secy. to Govt., P. W. D.

4th November 1864.

ORDER, No. 4190, *24th November* 1864.

Approved for entry in the Budget for 1865-66.

(True Extract.)

Under Secretary to Government.

To the Pub. Works Dept., with 3 enclosures.
„ Quarter Master General.

Exd. R. Stephenson.

C.W. 1864 Dublin
Office of Public Works
No 5117
Proposal
in the Military Department

Dated 24th Nov 1864
Recd 28th Nov 1864

No 4190

£3

C.O. 3588/65

Approving of the
Entry in the Budget of 1865/66,
of the Estimate of £8840 for
levelling the Ramparts of
the Fort at Hunmore, within
the Military limits.

No 3453 - 2nd December
1864
With an order.

Commissariat Office Kilkenny 22nd Dec 1864

Sir

I am directed by the Commissariat General to request you will inform them whether the Ramparts and Traverses of the Fort at Hunmore, Co Galway, are within the Military Reserve, and if not, what Rent will be required for the same.

I am Sir
Your Obt Servt
[illegible]
Commissariat Clerk

To
The Secretary
Board of Public Works
Dublin

No 4190 61