M.R.O. 1—77,006—8-6-37.

(1) Number of pages_____

(2) Date of repair_____

(3) Initials of the Referencer_____

MADRAS RECORD OFFICE.

Government of Madras.

public works DEPARTMENT.

G.O. No. 1154. Press Mis.

532-533

Dated 22-6 1864.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 22nd April 1864.

No. 532. Read the following Proceedings of the Madras Government in the Military Department :—

Approving of the Estimate for altering the Lightning Conductor of the Powder Magazine at Palamcottah, Tinnevelly District. } (Here enter 16th April 1864, No. 1,293.)

No. 533. ORDER THEREON, 22nd April 1864, No. 1,154.

1. Communicated to the Superintending Engineer, 8th Division.

2. Application should hereafter be made for a grant from the Reserve of 1864-65 to admit of the execution of the work.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 8th Division.
„ Controller and Auditor of Public Works Accounts.
„ Accountant General.

Exd. S. T. Augustin.

Public — Abstract Estimate &c of — New work

District Tinnevelly

Work, Making new Lightening rods to Powder Magazine at Palamcottah

Quantities	Description of work	Rate			Amount	Amount of each
		Rs	A	P		
400	1 foot of 1 inch Circular brass = 1386 lb	"	12	"	1038-12-0	
135	Running feet of flat brass 1 x 1/2 Connecting windows & Door with upright Conductors. 810 Cubic Inches = 245 lb	"	12	"	183-12-0	
100	lb weight of Castings	"	14	"	87-8-0	
240	1 foot of Iron chain	"	4	"	60-0-0	
	Sundries					130--
	Total Rupees					1500--
	Deduct 555 Cubic Inches = 168 lb of brass now under Cable from the Lightening Conductors	"	12	"	126----	126---
	Remainder requiring Sanction					1374--

Tinnevelly 1st Range Office
11th March 1864

Duston Major
Asst. Engr 1st Range Tin

F. Needham Captain RE
Superintending Engineer 8th Div.

Enclosure in a letter from the Supg Engineer 8th Dn dated 26th March 1864 No 2166 To the Secy to Government P W D

No 5
1864

P W 1699/64

P W 1420/64

M. D. No 1746 of 1864

Estimate for constructing a Lightning Conductor to the Powder Magazine in the Fort at Palamcottah.

MILITARY DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following papers:—

From the Superintending Engineer 8th Division, Palamcottah, 26th March 1864, *No.* 2166; *to the Secretary to Government, Department Public Works.*

Enclosures 3.
2 Plans.
1 Estimate.

1. I have the honor to enclose an Estimate for altering the Lightning Conductor of the Powder Magazine at this Station.

2. The amount entered for the Brass Rods is merely from guess, they must be supplied from Madras or even procured from England, and it is difficult to say what the cost of conveyance by sea to Tuticorin will be, as it must depend on the season.

Referred to the Military Department, with reference to the orders in that Department, No. 4090, dated 23rd December 1863.

(Signed) C. A. ORR, Colonel, R. E.,
Secretary to Government, P. W. D.

5th April 1864.

ORDER, No. 1293, 16*th April* 1864.

The execution of the work is approved.

(True Extract.)

Deputy Secretary to Government.

To the Public Works Dept., with 3 enclosures & 20 spare Copies.
„ Quarter Master General.
„ Inspr. Genl. of Ordnance, for information.

Sxd. W. Regel.

No. 1804 Dated
Proo of ...
No. 699.
Pro. of Govt. in the
Mily. Departt.
Dated 16 } Apr
Received 19 }
No. 179

Approving of the Estimate for altering the Lightning Conductor of the Powder magazine at Palamcottah, formerly ...

No 1154 - 22nd April

With an Order

No. 1154.

No. 532.

1 Communicated to the Supg. Engineer 8th Division —

2 — Application should hereafter be made for a grant from the Reserve of ~~the~~ 1864/65 — to admit of the execution of the work —

To The Supt. S. Dn. with 1 Report
Controller Auditor of
Acct. General — P. 4 docts.
Docts. 23rd April
Chepauk 2nd April /64 } ...