M.R.O. 1—77,006—8-6-31.

(1) Number of pages 8

(2) Date of repair 23-9-42

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

PUBLIC WORKS DEPARTMENT.

G.O. No. 1195 Press Mis. 613-614

Dated 26-6- 1866.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 26th April 1864.

No. 613. Read the following letter from Captain J. BEAN, R. E., Officiating Superintending Engineer, 6th Division, to Colonel C. A. ORR, R. E., Secretary to Government, Public Works Department, dated Tanjore, 19th April 1864, No. 2,472 :—

SIR,

1. I have the honor to enclose an Estimate amounting to Rupees 1,030 with a Plan for re-building the Kurpur Sluice in Combaconum Táluq, Tanjore District, and to request that Government will sanction the same as a minor new work from the balance in the Tanjore District unallotted for this head still unappropriated. The local authorities are not competent to sanction the Estimate as it amounts to more than 500 Rupees.

1 Estimate.
1 Plan.
1 Survey.

2. The sluice is at the head of a channel branching from the Cauvery river in Combaconum Táluq, and was destroyed at the time of a large breach occurring in the river bank during the last monsoon. The average revenue from the channel for the last five years amounts to Rupees 7,419-10-0, the Collector approves of the work, and as the channel irrigates 1,224 Acres, I beg early sanction for the Estimate in order that the present building season may be taken advantage of.

No. 614. ORDER THEREON, 26th April 1864, No. 1,195.

The Governor in Council sanctions the Estimate of Rupees 1,030 submitted with this letter for altering the head of and building a new head sluice for the Kurpur channel in Tanjore. The expenditure on the work in the current year will, if funds are available, be charged as proposed to the unallotted balance under the head "Minor New Works."

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R E.,
Secretary to Government.

To the Superintending Engineer, 6th Division, with 1 D. Estimate and 1 Survey.
" Controller and Auditor of Public Works Accounts.
" Accountant General.

Exd. S. T. Augustin.

Irrigation Canal

Abstract Estimate No. of 1863/64

Tanjore District

Koumbacounum Taluq

Work ——— Reconstructing Head Sluices and altering the Head of the Kurpoor Channel in the left bank of the Cauvery.

Quantities	Descriptions of Works	Rate	Amount	Amount of each part.
1,832	Cubic feet of Brick in Chunam ——— Cft.	" 2 "	60 1/4 " "	
1991	Sft. feet of Plastering ——— per Sqr.	2 " "	39 14 "	
6	Cross Stones ——— each	3 12 "	22 8 "	
	Excavating foundation & filling ———	" " "	80 " "	
	Baling ———	" " "	50 " "	
	Scaffolding and Centering ———	" " "	20 " "	
	Sundries and Contingencies ———	" " "	7 9 10 "	
	Total for Sluices			896 " "
	Excavating Channel			
2717 5/8	Cubic Cyds. of Earth work ——— Cyds.	" " 9	127 6 2	
	Sundries and Contingencies ———	" " "	6 9 10	
	Total for Channel	" " "	" " "	134 " "
	Total Estimate Rupees			1,030 " "

Supt. Engr. Office 6th Divn.
——— Tanjore ———
15th April 1864.

J Blunn Captain R.E.
Offg. Superintg. Engineer 6th Division

W. M. Smith
Collector

Mitchell/64

The Governor in Council
recommends the Estimate of £2,1930
submitted with this letter for
the rebuilding of the head of canal buildings
obtained the head sluices for the
new head sluices for Tarjie -
Kanpur Channel in Tarjie -
The expenditure on the work in
the Current year until, if
funds are available, be charged
to Surplus collected balance
as per Margin head "Plain New
under the head "Plain New
Works"

[illegible]

[illegible]
Secretary to Govt. of India
Public Works Department
Simla

DW 1564 Default

From Supt. Engineer April
No 1787

The Supt. Engineer
&c. &c.

To

The Secretary to Govt
PWD

Dated 19th April 1864
Rec'd 22

No. 2472

Enclosures 3

No. 1195 - 26th April/64

Forwarding for sanction
an Estimate of Rs 1030
for rebuilding the
Thurpur sluice in
Combaconum Taluq.

William Oder

No. 613. 614