M.R.O. 1—77,006—8-5-37.

(1) Number of pages 6

(2) Date of repair 28-2-42

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 1283 Press Mis-
81-82
Dated 6-3-82 1864.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 4th May 1864.

No. 81. Read the following Proceedings of the Madras Government in the Military Department:—

Approving of the Estimate of Rupees 510 for gravelling the Hospital paths of her Majesty's 102nd Regiment at Cannanore, Malabar District. } (Here enter 25th April 1864, No. 1,383.)

No. 82. ORDER THEREON, 4th May 1864, No. 1,283.

1. Communicated to the Superintending Engineer, 7th Division.
2. The cost of the work, viz., Rupees 510, will be met from the Reserve Fund.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 7th Division.
" Accountant General.
" Controller and Auditor of Public Works Accounts.

Exd. S. T. Augustin.

Malabar District

Estimate of the probable expense of Gravelling the Walks in the European Hospital at Cannanore

Gravelling Walks in the European Hospital Cannanore

Measurements Length	Breadth	Depth	Cubic Yards	Particulars of Works	Rate	Amount of each Article	Explanation of the Necessity of works &c.
yds	yds	yds					
104	3	1/6	52	Gravelling walks on Sea face			
154	2/3	1/6	61	___ Do ___ on North side			
148	2/3	1/6	59	___ Do ___ on South side			
84	6	1/6	84	Main walks from Main ward to Convalescent Shed			
90	8	1/4	120	Walks across Main ward in front from North to South			
12	8	1/6	16	" Apothecary Office and Surgery			
35	8	1/6	46	From rear of Main ward to detached ward			
62	8	1/6	82	From End of Female ward to Gate on Entrance of hospital			
			533	Total Cubic Yards of Gravelling walks beaten	1/4	1 Rupee	466 6
				Sundries and Superintendence about	10	1 Cent	43 10
				Total Estimate Rupees			510

Cannanore
4th April 1864

J. W. Beaufoy Colonel
Commanding Malabar Sub Division

James Sertue Captain
Executive Engineer
Malabar

38

MILITARY DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following papers:—

Memorandum from the Quarter Master General, Fort Saint George, 16th April 1864, No. 3995; to the Secretary to Government, Military Department.

(Forwarded to Government with the approval of His Excellency the Commander-in-Chief.

From the Officer Commanding Malabar and Canara, Cannanore, 5th April 1864, No. 128; to the Quarter Master General, Madras.

I have the honor to submit for the sanction of His Excellency the Commander-in-Chief, an Estimate* for gravelling the Hospital paths of Her Majesty's 102nd Regiment, which the Officer in Medical charge has requested may be completed before the monsoon, on Sanitary grounds, and I therefore suggest the speedy prosecution of the work.

* *Amounting to Rupees* 510.

ORDER, No. 1383, *25th April* 1864.

Approved and communicated to Department Public Works.

(True Extract.)

Deputy Secretary to Government.

To the Quarter Master General.
„ Public Works Dept., with an estimate. *for 20 spare Copies*

Exd. W. Regel.

1864 Depte
Pro: of Govt for Hay
No 1881

Pro: of Govt in the
Mily. Depte
Dated 25th Ult.
Recd 28th Ult.
No 1882
&
No 1283 - 4th May 1864 -

Approving of the
Estimate of £70 for gra-
velling the Hospital paths
of Her Majesty's 102nd Regiment
at Cannanore, Malabar &c.

Wm Hamilton Dodds

No 1283.

Commanding Officer Royal Engineer Corps
The Cost of the work Estimated in Engr Officer's No
will be met from the Revenue Dept.

No 81. 82

To the Depty Secy to Govt
Accountant Genl
Controller Mils & Ordnance

Dated Fort St. George
the 4th May 1864

By Order
Wm Hamilton Dodds
Secy to Govt

Ld No 1950 of 64

Ley Pr 443