M.R.O. 1—77,006—8-6-37.

(1) Number of pages_____

(2) Date of repair_____

(3) Initials of the Referencer_____

MADRAS RECORD OFFICE.

Government of Madras.

Public DEPARTMENT.

G.O. No. 144 P — Press / Mis.

Dated 18-5- 1864.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 18th May 1864.

No. 421. Read the following Proceedings of the Madras Government in the Military Department :—

Approving of the Estimate of Rupees 2,724 for enclosing the Soldiers' Garden at Wellington, Coimbatore District. } (Here enter 12th May 1864, No. 1,615.)

No. 422. ORDER THEREON, 18th May 1864, No. 1,448.

1. Communicated to the Superintending Engineer, 7th Division, for information and guidance.

2. The cost of the work, viz., Rupees 2,724, will be met from the Reserve under "Military."

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 7th Division.
" Accountant General.
" Controller and Auditor of Public Works Accounts.

Exd. S. T. Augustin.

Detailed Estimate No 43 of 1863-4

Nuiggerry Range
Commissariat District.

Work. Building a Mud wall around the Soldiers Garden with gates and wooden paling on either side of the Barracks at Wellington

Measurements			Contents	Particulars	Rate	Amount	Amount of each part
L	B	D					
374	2	1	6348	Foundation walls			
374	2	8½	9440	Mud walls above			
			25785				
			955⅔	Cubic Yards Mud work in Brick or Stone	40	634 13	
374	2	¼	155⅔	Cubic Yards Brick in chunam top Small			
240	1"	"	"	Cubic feet of teakwood paling including	3 8	840	
"	"	"	"	the cost of nails			
"	"	"	3	Gate with wooden frames posts	100	300	
"	"	"	"	iron bars &c complete			
"	"	"	252⅔	Cubic Yards Earthwork for Excavating	" 2	44 1 6	
"	"	"	"	foundations &c			2574 15
				Sundries @ 5 per Cent			129 1 "
				Total			2724 " "

Calcd and measd
17th Nov. 1864

Conductor

Supdg

Lt Holder
Engr

Lt Holder
do

Specification

Summary of Estimate 2724 Bo

The proposed mud wall around the Soldiers Garden to be 4 ft high above foundations which is to be 1 ft deep the wall is to be provided with a Brick in chunam head, 3 Gates with wooden frames Posts Iron bars &c and teakwood paling on either side of the Barracks

Wm B Thompson Lieut Col
Comms Wellington

W Clauson Capt
Executive Engineer

W Clauson Capt
Executive Engineer

MILITARY DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following paper :—

Proceedings of the Madras Government, Public Works Department.

Referring the Estimate for enclosing the Soldiers' Garden at Wellington. } Here enter 29th April 1864, No. 1237.

ORDER, No. 1615, 12*th May* 1864.

The Plan and Estimate for the wall to enclose the Soldiers' Garden at Wellington, are approved for execution.

(True Extract.)

Deputy Secretary to Government.

To the Public Works Department, with 3 enclosures. *& 20 spare Copies*

" *Quarter Master General.*

Lt. G. Rodrigues.

No 1148

Communicated to the Supt Engineer T.S. Division for information & guidance.

The cost of the work Vizt Rs 2724 will be met from the Reserve under "Relief".

To The Supt Engineer T. D. with 1 Letter
" Acct General
" Controller Auditor of P.W. accts

Chepauk 18th May 1861

Dated 19th May

No 1148 Dated 18th May 1861.

From Lt Col Orlebar Supt Engineer T.S.

To The Secretary to Govt with Letter

Dated 13th May 1861

Received 18th May 1861

No 2138.

Estimate of Rs 2724 for enclosing the Sluices, Sarkhi at Pallavaram, Chingleput District.

Lt Col Orlebar