M.R.O. 1—77,006—8-6-31.

(1) Number of pages_____

(2) Date of repair_____

(3) Initials of the Referencer_____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 1466 Press / Mis.

Dated 20-5-32 1832.

Not to be folded or roughly handled

15

Proceedings of the Madras Government, Public Works Department, 20th May 1864.

No. 457. Read the following Proceedings of the Madras Government in the Military Department :—

Approving of the Estimate of Rupees 130 for converting one end of the Cook-room of the old Dragoon Hospital at Bangalore into a Store-room. (Here enter 11th May 1864, No. 1,603.)

ORDER THEREON, 20th May 1864, No. 1,466.

No. 458.

1. Communicated to the Superintending Engineer, 5th Division.
2. The cost of the work will be defrayed from the source proposed by Captain Gahagan.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 5th Division, with specification report.
" Accountant General.
" Controller and Auditor of Public Works Accounts.

Exd. S. T. Augustin.

Harried down 6212

Fabrication of the Buildings &c &c. 1863.

Estimate of the Probable Cost of adapting one End of Cook Room of Old Dragoon Hospital at Bangalore as Hospital Store Room prepared agreeably to the Order from the Deputy Assistant Quarter Master General Mysore Division No. 25. dated 3d March 1863.

Measurement				Nature of Work	Cost			
							Amount	Cost of Work
1	13¼	2½	2½	78 3/16	Excavating for wall			
1	7½	2½	2½	24	do do do			
Total				98 3/16	Excavating for foundation	0	01	8 2
Total				98 3/16	Foundation stone in Lime	0	10	5 2
1	13¾	1¾	1¼	30 1/16	Basement to Partition wall			
1	7¾	1¾	1½	12 3/8	do do do do			
Total				48 7/16	Basement for walls with Stone	0	2	6 10
					in Chunnam			
1	14	1¼	1¼	245	Walls above			
1	14	1¼	2⅓	40 2/3	Gables Ends &c do			
5		1¼	12	75	Walls above for Cooking Place			
3		1⅓	3	11¼	do do chimney			
Total				371	Walls with Brick Chimney	0	22	80 6
1	14	0	14	392	Plastering to walls			
1	14	0	2⅓	65⅓	do do Gables			
5		0	12	120	do do Cooking Place			
					Carried over			6212

Measurements

No.	L	B	D	Cont.	Remarks
2	3	3	18		
"	"	"	50		
Flat				64.53	
Total				3731	
"	15 3/5	"	"	"	
1	3 1/2	"	1/2		

Date Amount Rs. As. Ps.

Brought over

Plastering all Chunam

Plastering where required

Plastering two Coats Lime Mortar

Whitewashing the same with two Coats

Packing down the flooring and the wall

Running feet of stone sills

One Pair of Teak wood Panelled door with frame and Iron work and fastening including putty and fixing &c. Complete

Sundries at 5.12 per Cent

Total Amount of Estimate Rupees

Rupees one hundred and thirty

Ex. Engr. Office Bangalore

Jno. Grandidier Captain &c

J. Colgan Asst. Engr.

Comp. Bills 3-4-

No 457. 458.

No 2137.

No 1166

Dated 11th May 1864

Rec'd 11th May

Ans.

Estimate of Approving of the
-ing me the 180 for convert.
of the old Lazaretto Hospital
at Bayabac into a Sick Room
etc. 1166 - 20th May 1864

Writs in Order

etc 1166

1. Communicated to the Superintending Engineer
5th Division.
2. The cost of the works will be defrayed from
the source proposed by Captain Gahagan.

To The Supg Engr 5th Dn with Specifn & Plan
" Accountt General
" Controller & Audr of Wks Accounts

Letter No 20th May 1864

Rec'd 21st May

X 87