M.R.O. 1—77,005—8-6-37.

(1) Number of pages 2

(2) Date of repair 2-6-

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 1580 Press ~~Mis.~~

684-686

Dated 31-5- 1864.

Not to be folded or roughly handled

40

Proceedings of the Madras Government, Public Works Department, 31st May 1864.

Read the following papers :—

No. 684. From Lieutenant-Colonel O. W. S. CHAMBERS, R. E., Superintending Engineer, 1st Division, to Colonel C. A. ORR, R. E., Secretary to Government, Department Public Works, dated Waltair, 11th May 1864, No. 114.

SIR,

2 Plans.
2 Estimates.
1 Specification.
1 Copy of Civil Judge's letter No. 8, of 5th January 1863.
1 Do. of Deputy Registrar's letter of 10th March 1864.

* Rs. 3,710.
„ 3,820.
„ 3,680.
„ 3,760.
These sums include the cost of out-houses.

1. In forwarding for the orders of Government the enclosed Plan and Estimates* of the cost of constructing certain Court Houses in the Vizagapatam District, I beg to accompany them with a letter from the Civil and Session Judge to the High Court in which the necessity of these buildings is set forth.

2. The High Court approved of Mr. Collett's proposal to build four Moonsiffs' Court Houses in this District, and directed him to apply to this Department for Plans, &c.

3. The enclosed Plan and Estimates were consequently prepared and were sent to Madras, whence they have been returned approved of by the Judges of the High Court who have proposed an unimportant modification of the position of one of the party walls of one of the side rooms of the building, which on being carried out, which it is purposed to be, will involve no alteration in quantities or rates.

Deputy Registrar 10th March 1864.

4. Mr. Collett has further desired that each Court House should be provided with a tiled shed to afford shelter to the bullock coaches and palanquins made use of by the Moonsiff and his suitors, and with a latrine ; a plan of these buildings and a subsidiary Estimate have accordingly been attached to the original design.

At a cost of 250 Rupees for both buildings.

Referred to the Judicial Department. In the event of the Plans being approved of, the undersigned requests that he may be informed whether it is indispensably necessary that the works should be carried out during the current year. Nearly 2½ lacs of the Reserve have been already appropriated and provision has yet to be made for works which were expected to be, but not completed on the 30th April last.

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government, P. W. D.

21st May 1864.

No. 685. Memorandum from A. J. ARBUTHNOT, Esq., Chief Secretary to Government, Judicial Department, to Colonel C. A. ORR, R. E., Secretary to Government, Public Works Department, dated Fort Saint George, 23rd May 1864, No. 267.

1. The Chief Secretary has the honor to inform Colonel Orr that he sees no objection to the Plan submitted by Lieutenant-Colonel Chambers with his letter of the 11th instant (herewith returned), for the erection of District Moonsiffs' Court Houses in the Vizagapatam District.

2. It is desirable that Court Houses should be built at Bimlipatam and Rajum, if possible, in the current year.

No. 686. ORDER THEREON, 31st May 1864, No. 1,580.

1. The Governor in Council sanctions the undermentioned Estimates submitted by the Superintending Engineer, 1st Division :—

District Moonsiff's Court House		at Yellamunchilly	...	...	Rupees 3,710
Do.	do.	at Bimlipatam	...	...	„ 3,820
Do.	do.	at Vizianagram	...	...	„ 3,680
Do.	do.	at Rajum	...	...	„ 3,760

Proceedings of the Madras Government, Public Works Department,
31st *May* 1864.

2. As it is desirable that the Court Houses at Bimlipatam and Rajum should be built without delay the Governor in Council resolves to place a sum of Rupees 7,580 at the disposal of the Superintending Engineer, 1st Division, from the current year's Reserve,* and to direct that those two works be at once proceeded with.

* Under "Civil Buildings."

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 1st Division.
" Accountant General.
" Controller and Auditor of Public Works Accounts.
" Judicial Department.

Exd. S. T. Augustin.

Judicial — New Works.

Abstract Estimate No 14 of 1863-64.

Vizagapatam District

Work. Constructing a Shed and Privy to the District Moonsiffs Courts at Yellamanchilly, Bimlipatam, Vizianagram and Rajam

Quantity	Description of Charges.	Rate	Amount	Total
8 1/3	Cyds of Rough stone in Chunam	1 12 Cyd	14 9 4	
8.	Do of Brick work in Do	2 8 Do	20 ..	
3.84	Squares of plastering in Do	1 12 Sqr	6 11 6	
3.0	Do of flooring with stone jilly in Chunam	2 8 Sqr	7 8 ..	
1.84	Do of Honey Comb tile work	6 4 Sqr	11 8 ..	
22.4.6	Cft Country wood wrought and put up	1 4 Cft	35 7 6	
4.20	Squares of Roofing with palmyrah Couplis of single tie piece, Beepers, Rails, flat and pan tiles and Chunam borders &c complete	130 Sqr	56 11 2	
	Excavating foundation and filling in Basement		12 ..	
			164 7 6	
	Contingencies 10 per cent		25 8 6	
				190
	Privy			
22	Cyds of Rough stones in Chunam	1 12 Cyd	38 8 ..	
	Carried Over		38 8 ..	190

	Brought over		38 0 190
8 3/4	Grarers of plastering in Chunam	12 Gl	155
	Levelling floor and excavating		33
			57
	Sundries		3 60
	Total for Yellamanchilly		250
	" Kanikapatam		250
	" Veeravasaram		250
	" Rajam		250
	Total Estimate Rupees		1,000

Supt. Engrs Office
Madras
7th May 1864.

Lieut. Colonel Chambers
Superintending Engineer 1st Div

Superintending Engr's
Office, 1st Dn. Vizagapatam,
11th May 1864.

No. 114

From

Lieutenant Colonel Chambers R.E.
Superintending Engineer

To

Colonel C. A. Orr R.E.
Secretary to Government P.W.D.

Encls. 7.
2 Plans
2 Estimates
1 Specification
1 Copy of Civil Judge's letter dated 15th April 1864.
1 Dy. Registrar's letter of 10th March 1864.

Sir,

In forwarding for the orders of Government the enclosed Plans & Estimates of the Cost of Constructing certain Court Houses in the Vizagapatam District, I beg to accompany them with a letter from the Civil Judge to the High Court in which the necessity of these buildings is set forth.

2. The High Court approved of Mr. Collett's proposal to build 4 Moonsiff's Court Houses in this District and directed him to apply to this Department for plans &c.

3.

× Rs. 3710
Rs. 3820
Rs. 3680
Rs. 3760
these sums include the cost of encl. houses.

P.W. 22nd/64

31 May 64 – 1580
Copies sent to Encl. 10 1149.

3. The enclosed plans and Estimates were consequently prepared, and were sent to Madras whence they have been returned, approved of by the Judges of the High Court, who have proposed an immaterial modification of the position of one of the party walls of one of the side rooms of the building, which on being carried out, which it is purposed to be, will involve no alteration in quantities or rates.

Dy. Registrar 1st March 1864

4. Mr. Colbeth has further desired that each Cus[t]om House should be provided with a shed to afford shelter to the Palloch Coaches and Palanquins made use of by the Moonsiff and his suitors, and with a latrine; a plan of these buildings and a subsidiary Estimate have accordingly been attached to the original design.

abt. Rs. 600 for both buildings.

I have the honor to be &c.

Your Most Obedient Hble.

Sd. Chambers Lieut. R.E.

Superintending Engineer 1st Dn.

Rec'd

In No. 1064/54.

31st Jany 80 - 1580

1580

2309
P.W. 228/64

Referred to the Surveyor.

In the event of the Plans being approved of, the undersigned requests that he may be informed whether it is indispensably necessary that the works should be carried out during the Current year. Nearly 2½ Years of the Revenue have been already appropriated and provision has yet to be made for works which were excluded to be but not completed in the Work. & first Class.

Jubilee 18th Feb 1880
Rec'd 20th May
Answ'd 26
Superintending Engineer
Public Works
Presidency Division
Poona

Rec'd 11th
Acknd 12th
Desp. 13th
Rec'd 23rd

Exec. No. 1114
No. 1029. Superintending Engineer
Public Works for the Orders of Government. Recommending Plans & Estimates of the cost of Rebuilding Sessions Court House & Jail at the Rajegaphatra Hill together with a letter from the Civil & Sessions Judge to the High Court, in which he expresses his approval of these buildings in that respect.

dated 13th 1880 - 31st January 1881

Abstract Estimates for Constructing a District Moonsiffs' Court House at the undermentioned Stations in the District of Nagapatam with respective Rates of the Stations.

No 14 of 1863-64.

Quantity	Description of Works.	Ayyalmanchilly Smithystation Rate	Ayyalmanchilly Smithystation Amount	Kiranganum Rate	Kiranganum Amount	Nagore Rate	Nagore Amount
25/27	Cubic Yards of Rough stone work in Chunam per Cubic Yard	1 12 · 460	11	1 8 · 394	68	1 12 · 460	11
1/54	Do Brick work in Chunam per Do	2 4 · 382	08	2 2 · 361	47	2 4 · 382	8 8
11/27	Do Arch Work in Chunam per Do	3 · 25	37	3 · 25	37	3 · 25	37
1/4	Square Flooring with brick on edge in Chunam and Levelling Courses under same and plastering with 2 Coats of Chunam per Sqr.	7 109	193 11 5	6 2 · 164	106	7 2 · 179	14 6
1/2	Do Pillastring with one Coat of Chunam and Whitewashing per Sqr.	1 12 · 145	16	1 8 · 114	· ·	1 8 9	125 2 6
	Also Pillars or Drubns including Capitals, Cornices and plastering with one Coat Chunam and Whitewashing each	7 8 · 105	· ·	6 · · 84	· ·	7 · · 98	· ·
53	Cubic Feet of Teak wood or Country wood wrought and put up per Cubic Foot (including frame boards)	Country 1 4 · 157	15	Teak 3 · · 364	10 6	Country 1 4 · 157	15
3	Teak or Country wood Terraces complete with King post, Braces, Purlins, Principal Rafters	Country 50 · · 150	· ·	Teak 70 · · 210	· ·	Country 50 · · 150	· ·
70	Squares of Roofing with Country wood or Palmyra Rafters, Reepers, Nails, Flat and Pan tiles and Chunam borders pointed and pointed with arsenic complete per Sqr.	12 8 · 570	· ·	15 · · 684	· ·	13 · · 592	12 9
4	Pairs of teak half panelled and half Venetioned Shuttered Doors with frames and iron fixtures complete	50 · · 200	· ·	45 · · 180	· ·	50 · · 200	· ·
11	Do Do Do Do	35 · · 385	· ·	30 · · 330	· ·	35 · · 385	· ·
4	Do of Teak wood Venetian Windows with shutters, frames, and iron fixtures complete	23 · · 92	· ·	20 · · 80	· ·	23 · · 92	· ·
	Carried Over	· ·	2860	101 · ·	2982	3 10 · 4	2845 10 11

Quantity	Description of Works.	Nagore Rate	Nagore Amount
1/2	Cubic Yards of Rough stone work in Chunam per Cubic Yard	1 12 · 460	11
1/54	Do Brick work in Chunam per Do	2 4 · 382	8 8
11/27	Do Arch Work in Chunam per Do	3 · · 25	37
1/4	Square Flooring with brick on edge in Chunam and Levelling Courses under same and plastering with 2 Coats of Chunam per Sqr.	7 2 · 179	14 6
1/2	Do Pillastring with one Coat of Chunam and Whitewashing per Sqr.	1 8 9	125 2 6
	Also Pillars or Drubns including Capitals, Cornices and plastering with one Coat Chunam and Whitewashing each	7 · · 98	· ·
53	Cubic Feet of Teak wood or Country wood wrought and put up per Cubic Foot (including frame boards)	Country 1 4 · 157	15
3	Teak or Country wood Terraces complete with King post, Braces, Purlins, Principal Rafters	Country 50 · · 150	· ·
70	Squares of Roofing with Country wood or Palmyra Rafters, Reepers, Nails, Flat and Pan tiles and Chunam borders pointed and pointed with arsenic complete per Sqr.	13 · · 592	12 9
4	Pairs of teak half panelled and half Venetioned Shuttered Doors with frames and iron fixtures complete	50 · · 200	· ·
11	Do Do Do Do	35 · · 385	· ·
4	Do of Teak wood Venetian Windows with shutters, frames, and iron fixtures complete	23 · · 92	· ·
	Carried Over	· ·	2845 10 11

Judicial Department.

No. 267.

Memorandum.

The Chief Secretary has the honor to inform Colonel Orr that he sees no objection to the plan submitted by Lieut. Colonel Chambers with his letter of the 18th Instant (herewith returned) for the erection of District Courts & Court houses in the Vizagapatam District.

It is desirable that Court houses should be built at Bimlipatam and Rajam, if possible, in the current year

Fort St. George
23d May 1864

G. J. Cumberland
Chief Secretary

To
The Secretary to Government,
Public Works Department.

Vizagapatam Civil
Court 5th January
1863

No 8.

To

C. F. Shannon Esquire
Registrar of the High Court of Judicature
Madras, Appellate Side

Sir

I have the honor to state that there is no Court house for the Munsiff at Bimlipatam and no buildings fit for the purpose can be procured. The Court recently established there is now held in a hired house, the best that could be had, but not adapted to the purpose. I have therefore in communication with the Executive Engineer had a plan and Estimate for a Court house prepared; the Estimate amounts to Rs. 3,569 - - - , Exclusive of the Cost of a Site. I understand from the Collector that a Site might be procured without difficulty.

2. There is also no house for the Munsiff's Court recently established at Rajam. The building temporarily hired is totally unfit for the purpose and none other could be had. It is necessary that a Court house should be at once erected there and I would propose the same plan as that prepared for Bimlipatam. There would be no difficulty about a Site.

3. The Munsiff at Vizianagram was

In 1864 Oct 18th
Ro. to Collector
No. 2382

From the Collector
Copy to Court under
Challan Dated
Dated 28
Received 29 Ditto
No. 2417

Re Returning the
draft of the Court
House in the
Compound of the
Cutcherry at
Bimlipatam &
Requesting that
the Collector
may be requested
to Report
whether the
Site is
Available

Ca 1580 - 31st May 1864

was till recently under the Agent of
pegular Moonsiff's Court has now been
established there: the Court is held in
the hired building formerly used.
From a measured plan of it submitted
to me, I am satisfied that it is not a
proper building for a Court house; the
Moonsiff under the Agent had a very
limited jurisdiction and small
establishment. I am of opinion that
a new Court house must be erected
here; there could be no difficulty
about a Site.

4. The Moonsiff at Ponnerain
reports that his Court house is so
inconvenient that he is obliged to hold
the Court in the Verandah. The
building belongs to Government, but
is, I understand, old and of little value.
Ponnerain is apparently a very
inconvenient Station; it is six
miles off the high road, and so surrounded
by paddy fields as to be difficult of
access. All the public Officers whom
I have consulted agree that it would
be very desirable to transfer the
Moonsiff's Court to Pellamunchily,
a town on the high road and 6 miles
from

from Ponnerain. A Police Station
house has lately been built there, and
a Sub Magistrate's Cutcherry is also
to be erected and the Collector
informs me that there is some
Government ground there, which could
be very conveniently given as a Site
for the Court. I therefore think that
a new Court house should be erected
at Pellamunchily, and the present
building at Ponnerain might be
Sold.

5. I have countersigned and returned
to the Engineer's Department the Plan
and Estimate prepared for the Pimlipalam
Court house. It is indispensable that a Court house
be erected at once both at Pimlipalam
and Rajavi; and I consider it most desirable
that a new Court house should also be erected
as soon as conveniently can be done, at
Vizianagram & Pellamunchily respectively.
I have the honor therefore
to request that if the Chief Justice
and the Honorable the Judges
approve of my proposal, such
communication as may be necessary
may be made to Government

To

Pub. Works Dept. 25

No 1550

Proceedings of the Madras Government

Under date the 21st May 1864

Read the following Letters

From the Superintg Engr 1st Dn

Submits for this orders of Govt the accompanying Plan and Estimates for the cost of constructing certain Court Houses in the Vizagapatam Distt together with a letter from the Civil and Sessions Judge to the High Court in which the necessity of these buildings is set forth.

Chief Secy to Govt Judl Dept

Approving of the Plan Estimate for the erection of Civil Courts Houses in the Vizagapatam Distt, and considering it desirable that these at Bimlipatam & Rajam should be built if possible in the Current year

Read 11th May 64 No 114

Read 23rd May 64 No 267

The Governor in Council sanctions the undermentioned Estimates submitted by the Superintg Engr 1st Dn

Viz

Erection of the Court Houses

Rajam ... Rupees 23,000

Bimlipatam ... Rupees 13,000

Signed Charles Collett

Chief Secy

Certified

Signed Charles Collett

Chief Secy

Certified

Illegible

Asst Writer

To Superintg Engr 1st Dn

Sd/ Illegible

Asst Secy to Govt

District Moonsiffs Court

House at Yellamunchilly —— Rs. 3,710

- Do. at Bimlipatam —— " 3,820

— Do — at Vizianagram —— " 3,680

— Do. at Rajam —— " 3,760

As it is desirable

that the Court Houses

at Bimlipatam and

Rajam should be built

without delay the Governor

in Council resolves to

place a sum of Rs. 7,580

at the disposal of the

Superintg. Pl. Wks. from

the

under "Civil Buildings" the Amount yearly Revenue

and to direct that Notice

two months be at once given

to

The Superintg. Pl. Wks. Specifications & Original Letter

" Accountant

" Comptr.

" Judicial Deptt.

Despr. 1st June.

43

5

P. W. 1864 Deptt

Proc. of Govt. for Aug

No 1580

Proc. of the Ld Govt

Dt 31 May 1864

Estimates amtg
to Rs 14970 for the con-
struction of certain
Court Houses in the
Nagapatam Divn
Sanctioned