

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

public works DEPARTMENT.

G.O. No.	1621.	Press
		Mis.
69-70		
Dated	3-6-	1866.

Not to be folded or roughly handled

1

*Proceedings of the Madras Government, Public Works Department,
3rd June 1864.*

No. 69. Read the following letter from Lieutenant-Colonel J. C. ANDERSON, R. E.,
Superintending Engineer, 2nd Division, to Colonel C. A. ORR, R. E., Secretary to
Government, Department Public Works, dated Masulipatam, 16th May 1864, No. 5:—

SIR,

- 1 Plan of bridge.
- 1 Section.
- 1 Estimate.
- 1 Specification report.

ment, and sanctioned by Government along with those for other masonry works on the same road.

2. There were two Estimates for the Section of Trunk Road No. 6, between the 115th
and the 181st mile, one for the construction* and the other
for masonry† works and both are in course of being worked
out. But it was reported by the late District Engineer,
Nellore, Captain Mullins, in the year 1856, that an additional
expenditure of Rupees 1,05,900 would be required. As only
a small portion of the sum originally sanctioned had then been
expended, the Government returned the supplemental Esti-
mate with a view to a fresh one being submitted if necessary
when the large balance thus remaining in hand should have
been spent.

* Rupees 1,17,113, sanctioned in G. O.
No. 200, dated 2nd May 1854.
† Rupees 84,580, sanctioned in G. O.
No. 1,405, dated 12th August 1856.

G. O. No. 1,698, dated 8th September
1857.

Expenditure up to 30th April 1864:—
Construction, Estimate Rs. 1,02,063 8 4
Masonry works " 60,982 8 5

3. I have accordingly called upon the Range Officers concerned to prepare Estimates for
the completion of the section of the road in question as it stood on the 1st instant inclusive of
all works, with the exception of bridges across the Moonairo, Palairoo and Moosy rivers, which
should not, I think, be estimated for until the completion of the road in other respects, or until
there is a prospect of funds being available for their prosecution.

4. A considerable time must elapse before the revised Estimates can be submitted to Go-
vernment, and as it is desirable that the grant for the current year for masonry works Rs. 24,580
should be expended, I think it inadvisable to detain the Estimate for the Pydairroo bridge until
it can be incorporated with the others.

5. The design which has been prepared by Lieutenant Smith provides for a bridge of seven
arches of 30 feet span, to cost Rupees 16,400 and embanked approaches Rupees 4,600, total
Rupees 21,000.

The original design allowed five arches of 15 feet, but both the rates and the water-way are
a much lower scale than experience shows to be necessary.

6. Lieutenant Smith has allowed a water-way sufficient for the discharge of a quantity of
water with a velocity of 4 $\frac{1}{2}$ per second equal to a fall of 4 $\frac{1}{2}$ inches of rain in 24 hours over the
drainage basin of 60 square miles, which though liberal, is probably not more than sufficient to
dispose of the heavy floods which are liable to occur in the vicinity of Nellore.

7. No further allotment besides that already allowed in the Budget is required for the
proposed work.

No. 70. ORDER THEREON, 3rd June 1864, No. 1,621.

1. The Government sanction the Estimate of Rupees 21,000 submitted with this letter for
a bridge of seven arches of 30 feet span, with embanked approaches, across the Pydairroo river at
the 118th mile of Trunk Road No. 6.

2. The cost of the work will be met from the assignment of Rupees 24,580 in the Budget
for masonry works on the road within the Nellore District.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 2nd Division.

" Controller and Auditor of Public Works Accounts.

" Accountant General.

Exd, S. T. Augustin.

1854, 31-32
1856-1857
1857-62-63

1864, Dep't
of Public Works
June 23rd

The Chief Engineer
2d Division

To the Secy to Govt
D. W. W.

Dated 16 May 1864
Recd. 24

E. L.

Forwarding Estimate and
Plan for Constructing
a Bridge and Embankment
road across the River Tyron
at the 118th Mile of French
Road to be in better or Ditch
amounting to \$21000
and request the sanction
of the same.

A. B. 21- 273rd Fund

With an Order

1864/65

No. 69. 70

C. 28th May 1864 - A. 20th