

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public works. DEPARTMENT.

G.O. No.	1623	Press
		Mis.
73-74.		
Dated	3-6-	1864.

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
3rd June 1864.*

No. 73. Read the following letter from Captain T. E. GAHAGAN, R. E., Acting Superintending Engineer, 5th Division, to Colonel C. A. ORR, R. E., Secretary to Government, Department Public Works, dated Salem, 28th May 1864, No. 204:—

Sir,

1. I have the honor to forward for sanction an Estimate
amounting to Rupees 3,450, for the re-construction of the
Veranam channel head sluice in No. 4 Range, South Arcot,
and to request that a grant to the full amount of the Estimate may be made from the current
year's Reserve.

2. The existing head sluice is reported to be in a dangerous state, from its foundations
having been seriously undermined; and I have therefore authorized the preparation on emergency
of materials for the new work.

No. 74. ORDER THEREON, 3rd June 1864, No. 1,623.

The Estimate of Rupees 3,450 for the re-construction of the Veranam channel head sluice
in the South Arcot District is sanctioned from the Reserve under the head "Agricultural."

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 5th Division, with Specification report.
„ Controller and Auditor of Public Works Accounts.
„ Accountant General.

Exd. S. T. Augustin.

5th Division B.P.W.

New work.

Improvement

Agricultural

Irrigation canal.

Abstract Estimate No.

of 1864. 65.

3

West District

No. 4 Range

Chellambaram Taluq.

Reconstructing a Head sluice ~~the~~ built across
Verrannur Tank surplus channel.

Description of work.	Price	Per.	Amount	Total.
Cubic feet of brick in chumam	2.	84 $\frac{1}{4}$	2310. 8.	
— of arch work in chumam	2.	8.	174. 6.	
Byds of Sateite stone in chumam	6.	20 $\frac{1}{4}$	120. "	
more of Plastering with 2 coats in chumam	2.	5 $\frac{1}{4}$	112. "	
more stone $(6\frac{1}{8} \times 1 \times \frac{3}{4})$	6.	8.	26. "	
— " $(11\frac{1}{2} \times 1 \times \frac{3}{4})$	11.	8.	92. "	
more stone $(6\frac{1}{8} \times 1 \times 1)$	7.	0.	140. "	
do under the face wall $(6\frac{1}{2} \times 1 \times 1)$	7.	0.	84. "	
Old Shutter				
Byds of harth work for excavating foundation &c.	1.	3 Cys.	68. 12.	3127. 10. "
Indies for Contingencies & Temporary dam sea: at 10 ϕ . Cent.				322. 6. "

Total Estimate Rupees 3450. "

Office 5th Div.
16 May 1864

J. E. Gahagan Capt. R.E.
Ag. Sup. Engineer 5th Div.

Charles Reed
Collector

N. 204

Superintg. Engineer's Office
5th Div. Salem 28 May 1864.

From,

The Asst. Superintg. Engineer
5th Division,

To,

The Secretary to Government
D. P. W.

Sir,

Enclosures 3
1 Plan.
1 Abstract
1 Estimate
1 Specification.

I have the honor to forward for consideration an estimate amounting to Rs. 3450 for the reconstruction of the Viranam channel head sluice in N. S. Range, South Arcot, and to request that a grant to the full amount of the estimate may be made from the current year's Reserve.

2. The existing head sluice is reported to be in a dangerous state, from its foundations having been seriously undermined; and I have therefore authorized the preparation on emergency of materials for the new work.

I have the honor to be

Sir,
Your most obedient

T. C. Chakravarti Capt. R.E.
Asst. Superintg. Engineer
5th Div.

Compd. P. D.

25/64

20/7/64

(101)

