M.R.O. 1—11,000—6-6-57.

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

PUBLIC (Misc.) DEPARTMENT.

G.O. No. ( ) Press / Mis.

Dated ( ) 18 .

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department,
10th June 1864.

No. 214. Read the following Proceedings of the Madras Government in the Military Department:—

Approving of the revised Estimate of Rupees 490 for a Store Room and Dooly Shed to be attached to the Pothanoor Rest House near Coimbatore. } (Here enter 4th June 1864, No. 1,912.)

No. 215. ORDER THEREON, 10th June 1864, No. 1,692.

1. Communicated to the Superintending Engineer, 7th Division.
2. The cost of the work will be met from the Reserve under "Military."

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 7th Division.
„ Accountant General.
„ Controller and Auditor of Public Works Accounts.

Exd. S. T. Augustin.

No. [illegible]

Imperial Fund.

Estimate for constructing a Store Room and Cooly Shed to be attached to the Rest House at the Railway Station at Coimbatore.

Coimbatore.

Estimate for a Cooly Shed at Pottanoor.

Taking Name of work.	Measurement. Length.	Breadth.	Depth or Height.	Superficial Contents.	Cubical Contents.	Particulars of work.	Price. Rate. Rs. A. P.	Amount.	Explanation of the necessity of work.	By whom recommended.
						Earth work.				
	129	3½	3.	"	1354½	Cubic feet or 50 cubic yards of excavating Foundation.	" 1 " C.yds.	3 2 "		Quarter Master General.
						Rough stone work.				
	127	2½	3	"	952½	Foundation.				
	106	2	1.	"	212.	Basement				
	21	2	½	"	21.5					
					1185½	Cubic ft or 44 Cubic yards of rough stone in chunam.	3 " " Do.	132 " "		
	106	1½	7	"	1113¾	Walls above.				
	28	1½	2½	"	87½	Two outer gables.				
	14	1½	2½	"	43¾	Two inner. Do.				
					1244½			135 2 "		

				1244¼						135	2
14	1½	1½	"	31½	Two pillars.						
5½	1	½	"	2¾	Steps.						
				1279	Sqft.						
				61.	Deduct for doors and windows.						
				1218							
					laf 5/6 or 45 Cubic yards of Burnt brick in clay.	2	5	3.	6.y2	104	12 3.
90	12	"	1050	"	Sqft 7½ or 10 4/5 Squares of Roofing with Jungle wood, couples, Reepers, nails and yaw ties & chunam borders.	15	"	"	Sq/r	162	" "
3	2½	"	"	"	2. Batten windows with wooden bars.	10	"	"	Each	20	" "
6½	3½	"	"	"	1. Batten Door complete	15	"	"	Do.	15	" "
24	15½	"	372	"	Flooring to Dooly shed.						
14	14	"	196.	"	Do. to Store room.						
27	3	"	81.	"	sloping floor in front of shed.						
			649.	"	Square feet or 6½ Squares of flooring with jilly in chunam 3" thick.	1	8	"	Sq/r.	9	12
119	1	"	119.		Basement.						
93½	7	"	654½	"	Walls.						
12	7	"	84.	"	Two pillars.						
34	2½	"	85.	"	Two Gables.						
			942½	"	Sqr. ft or 9 ½ Squares of Plastering the outside of the Building with chunam.	1	12	"	Do.	16	10 "
					Sundries about 5 Rupees per cent.					26	11 9.
					Total.					490	" "

W. Donough.
Supervisor Coimbatore Ranges.

Coimbatore Range Office
3d May 1864.

MILITARY DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following papers:—

Memorandum from the Quarter Master General, Fort Saint George, 25th May 1864, No. 5218; to the Secretary to Government, Military Department.

Forwarded to Government with the recommendation of the Commander-in-Chief—a Shed for the cover of a few Sick Carts and Doolies, and a Store-room for Tents for the use of Troops moving to the Hills, being much required in connection with the Rest House at Coimbatore.

From the Superintending Engineer 7th Division, Coonoor, 19th May 1864, No. 10; to the Quarter Master General, Fort Saint George.

I have the honor to re-submit the Plan and Estimate* of the Store-room and Dooly Shed to be attached to the Pothanoor Rest House near Coimbatore, revised as requested in your letter No. 2814 of 3rd March.

*Rupees 490.

ORDER, No. 1912, *4th June* 1864.

Approved.

(True Extract.)

Deputy Secretary to Government.

To the Public Works Dept., with Plan and Estimate.
" Quarter Master General.

Ext. T. Stubbs.

20 spare Copies

