M.R.O. I—77,000—8-6-37.

(1) Number of pages 6

(2) Date of repair 30-9-42

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public works DEPARTMENT.

G.O. No. 1706 Press / Mis.

241-242

Dated 11-6 1860

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department,
11th June 1864.

No. 241. Read the following letter from Lieutenant-Colonel E. HEMERY, R. E., Superintending Engineer, 3rd Division, to Colonel C. A. ORR, R. E., Secretary to Government, Public Works Department, dated Camp Guvalcherru, 25th May 1864, No. 20 :—

SIR,

2 Plans.
1 Estimate.
1 Report.

With reference to the Order of Government No. 3,782, dated 21st December 1863, I have the honor herewith to forward for sanction from the Reserve Fund an Estimate amounting to Rupees 2,865 for a road from the Kodur Station on the North-West Railway to the high road from Cuddapah to Madras, a distance of 880 yards.

No. 242. ORDER THEREON, 11th June 1864, No. 1,706.
Sanctioned from the Reserve under "Communications."
(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 3rd Division.
„ Controller and Auditor of Public Works Accounts.
„ Accountant General.
„ Financial Railway Department.
„ Consulting Engineer for Railways.

Exd. S. T. Augustin.

Abstract of Estimate of the proposed Railway Siding at Codnor

Quantities	Description of work		Rate		Amount			Total	
2215 5/9	Cubic yards of Earthwork	"	1	6	207	11	4		
1320	do Metalling	1	"	"	1320	"	"		
440	do Rough Stone	"	6	"	165	"	"		
3535 5	do Sundries	"	"	9	165	11	8		
	Sundries & Superintendence @ 10 p.c.	"	"	"	186	9	"	2345	"
	A Tunnel 8 f. Vent 3 feet 6 span								
81	Cubic yards of Earthwork	"	1	6	2	14	6		
811	Cubic feet Masonry	"	2	6	126	11	6		
207	Sq: feet Pointing in Cement per 100 sq ft	3	"	"	6	"	"		
42 2/3	Cubic yds Rough Stone work	"	8	"	2	5	4		
14	Covering Stones	1	8	"	21	"	"		
4	Guard Stones	1	"	"	4	"	"		
	Sundries & Superintendence				16	"	8	179	"
	A Skew Tunnel 8 f. Vent 3 feet 6 span								
31 5/6	Cubic yards of Earthwork	"	1	6	2	15	7		
874 1/2	Cubic feet Masonry	"	"	6	136	10	9		
325	Sq: feet Pointing in Cement per 100 sq ft	3	"	"	9	12	"		
5 1/18	Cubic yards of rough Stone	"	8	"	2	8	5		
18	Covering Stones	1	8	"	22	8	"		
4	Guard Stones	1	"	"	4	"	"		
	Sundries & Superintendence				17	9	9	196	"
	A Skew Tunnel 8 f. Vent 3 feet 6 span								
57 19/36	Cubic yards of Earthwork	"	1	6	5	1	10		
1810 1/2	Cubic feet Masonry	"	2	6	283	14	3		
700	Sq: feet Pointing in Cement per 100 sq ft	3	"	"	22	8	"		
16 11/27	Cubic yards Rough Stone	"	8	"	8	3	10		
54	Covering Stones	1	8	"	81	"	"		
4	Guard Stones	1	"	"	4	"	"		
	Sundries & Superintendence	"	"	"	40	4	1	445	"
					Total Estimated Expenses			2865	"

Camp Chatsworth
17th May 1864

T. Evans Wheeler
Superintending Engineer
Royal Engineers

Denny Lieut Col RE
Assistant Engineer 3rd Division

No 20

Chief Surveyors Office
Railway Surveys
25th May 1864.

From

Lieut. Col. Harry P.C.
Deputy Surveyor
Jyg. & Bn

To

The Secretary to Government
P.W.D.

Sir

Note Explanatory of the Estimate of Expenditure for the Construction of 3 1/2 Miles of Branch Railway from the Madras Road at Condoor to the Railway Station at Perumbakkam, and Estimate thereof amounting to Rupees 2865 Four hundred & fifty Rupees

I have the honor to forward herewith an Estimate of Expenditure for the Construction of 3 1/2 Miles of Railway from the Madras Road at Condoor to the Railway Station at Perumbakkam, a distance of 3 1/2 miles, amounting to Rupees 2865 Four hundred & fifty Rupees.

I have &c.

(Signed) H. Harry Lieut. Col.

Deputy Surveyor & Bn

Royapettah Range.

WW 2444/64

Estimate for Construc=
=tion of a Railway
Trade from the
Madras Road at
Condoor to the Rail=
way Station.

No 1706

Sanctioned from the Reserve under

"Communications"

To the Supg Engr 8th Dist With the Reports
" Contr & Asst P.W Accounts
" Accountant Rail
" Financial Railway Dept
" Consulting Engineer for Railways

Chepstow
11th June 1864

X 182

Dated 13th June 1864

Rec'd 24

Sanctioned from the Reserve under

"Communications"

To the Supg Engr 8th Dist With the Reports
" Contr & Asst P.W Accounts
" Accountant Rail
" Financial Railway Dept
" Consulting Engineer for Railways

Chepstow
11th June 1864

X 182

Dated 13th June 1864

Rec'd 25

No 1706 - 11th June 1864