M.R.O. 1—77,005—8-6-31.

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

[illegible] DEPARTMENT.

G.O. No. Press Mis.

Dated 18 .

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 16th June 1864.

No. 324. Read the following Official Memorandum from Lieutenant-Colonel O. W. S. CHAMBERS, R. E., Superintending Engineer, 1st Division, to Colonel C. A. ORR, R. E., Secretary to Government, Department Public Works, dated Waltair, 30th May 1864, No. 230 :—

No. 537 of 23rd February 1864.

1. In their Order as per margin, Government desired that the Place of Arms at Ellore might be obtained from the Quarter Master General's Department, and that then an Estimate might be submitted for adapting that building to a Range Office.

2. The building in question has been obtained from the Military authorities and a receipt has been given them for the same.

3. An Estimate is now submitted amounting to Rupees 300.

4. In addition to the partition wall required to divide the stores from the Office, provision is made to put the whole building in order, to put a glass window into the Office, and to put a fence round the compound.

No. 325. ORDER THEREON, 16th June 1864, No. 1,747.

1. The Estimate submitted with this letter for repairs, &c., to the Place of Arms at Ellore to adapt it to the purposes of a Range Office is sanctioned.

2. The source from which the cost of the repairs is to be met should be reported for the information of Government.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government,

To the Superintending Engineer, 1st Division.
„ Accountant General.
„ Controller and Auditor of Public Works Accounts.

Exd. S. T. Augustin.

Office and Store Keepers District — No 17 of 1864-65.

measurements

Length	Breadth	Depth or Height	Cubic Contents	Particulars	Rate	Per	Amount	Sth.	d.
16'	1-6	11'	264 Cft.	1 Partition Wall	-	-	-	-	
			9 21/27 or Cyds	Brick in clay	2 4 -	Cyd	22	-	-
32	11	- -	352	Plastering 2 sides Partition Walls					
30	16	- -	480	do 1 floor					
92	16	- -	1472	do 1 Verandahs					
			2304 or Square 23-4	Plastering with Cumum	2 8 -	Square	57	9	7
830	11	- -	9130	Whitewashing Walls					
216	8	- -	1728	Inside and Out					
			10858 or Square 108 58	Whitewashing	4 -	do	27	2	4
208	40	- -	8320	Shifting tiles & replacing Cumum battens	1 -	do	83	3	2
				Removing Corn Racks	- -	- -	30	-	-
5'	4'	- -	- -	1 Window Glazed with outward Shutters Complete	- -	- -	20	-	-
452'	-	- -	452'	Bamboo fencing round building	1 -	Ft	28	4	-
								268	3
				Contingencies				31	12
						Total Rupees		300	-

Remarks.

The Estimate allows for repairing the building and for placing a partition Wall across its breadth to form a Range Office and Store.

No 44 Range Office
Ellore
25 May 1864

Rs 300 Rupees Three Hundred only

H. Chumley
Assistant Engineer

Lt Hay

O.B. Chambers Lieut Colo
Superintending Engineer Vizg.

No 1747

The Estimate submitted with this letter for repairs &c to the Place of Arms at Elora to adapt it to the purposes of a Range Office is sanctioned.

The source from which the cost of the repairs is to be met should be reported for the information of Government.

To The Supg Engr 1st Div.
" Accountant General
" Controller & Audr of P.W.

dated 17th June
No 87

Chequed 16th June 1864

To the Secretary to Govt
&c &c &c

dated 30 May 1864
resp 31 do
Rec'd 1 June
No 230
Enclosing Estimate
Forwards an Estimate
for No 300 for adapting
the Place of Arms at
Elora to a Range Office
as per order of Government
No 537 of 25th February
1864.

No 1747-16th June 1864.

Note an Order

1 Cert of Gov for June
No 2521
from
the Supg Engr 1st Divn

Colonel C.S. Carre R.E.
Secretary to Government
&c &c &c

No 824. 820

2. 10th June 1864 - No 15