M.R.O. 1—77,006—8-6-37.

(1) Number of pages 8

(2) Date of repair

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 2875 Press ~~Mis.~~

57-58

Dated 6 - 10 - 1864.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 6th October 1864.

No. 57. Read the following letter from Captain J. G. RYVES, R. E., Superintending Engineer, 1st Division, to Colonel C. A. ORR, R. E., Secretary to Government, Department Public Works, dated Waltair, 17th September 1864, No. 967:—

SIR

1 Plan.
1 Estimate.

1. The accompanying are a plan and estimate for the construction of a calingulah in the Bendamúrlunka channel near Indupilli, at a cost of Rupees 980.

2. Mr. Rundall, in whose Range the Bendamúrlunka channel lies, states that, in the original estimate,* a calingulah was proposed to be built, but that by an oversight it was struck out with the Perúrú lock which it was decided should be omitted.

* For the Channel.

3. Until the calingulah now proposed is built, the water on the Nadipúdi lock lower sill, cannot be kept at a proper level to supply the Amalapúr canal.

4. The rates entered in the estimate have been checked in this Office and found to be moderate.

5. The cost of the calingulah, viz., Rupees 980, can be met from the sum of Rupees 10,417, allotted in the current year for the completion of the Central Delta works.

6. I therefore request the sanction of the Government for the proposed work.

No. 58. ORDER THEREON 6th October 1864, No. 2,875.

The estimate of Rupees 980 for a calingulah in the Bendamúrlunka channel is sanctioned, the cost of the work being met, as proposed in paragraph 5 of the foregoing letter, from the Budget assignment of Rupees 10,417 for "works of irrigation and navigation in the Central Delta."

(True Extract.)
(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 1st Division.
„ Controller of Public Works Accounts.
„ Accountant General.

Exd. S. T. Augustin.

No. 17 of 64/65 — 32

Abstract Estimate for Constructing a Calingulate in the Bendamirlanca Channel near Luxpilli in No. II Central Delta Range Godavery District

Quantity	Description of Work	Rate	Per	Amount		P. C.
108·4·23/32	Cyd. of Brick work in Chunam	4	8	Cy.	486	27
6·85·1/8 27/100	Sqr. of Plastering 2 Coats	4	"	Sqr.	27	66
163 1/4	Cft. of Cut Stone	"	8	Cft.	81	10
22 8/9	Do of Teak wood	28	"	Do.	57	36
	Straps, Nails &c. for Bridge	"	"	"	5	"
36	Cyd. of Rough Stone	2	"	Cy.	72	"
No. 6	Shutters	6	"	Each	36	"
1	Jamboge Shutter	28	"	Do.	28	"
	Iron Work	"	"	"	30	"
	Excavating foundations and filling in	"	"	"	70	"
	Bailing	"	"	"	30	"
					898	87
	Superintendence & Sundries				81	75
						980
	Total Rupees					980

No. II Range Office
Gunnaram 2 September 1864

/Signed/ J. W. Rundall
Actg. Executive Engr. Gody Distt.

/Signed/ J. Turner.
Offg. Collector

/Signed/ W. G. Hogg
Superintending

Captain R.E.
Engineer in Chief

No. 2875

The estimate of Rupees 980 for a Culingulah in the Bendawarlankaw Channel is sanctioned - the cost of the work being met, as proposed in para 5 of the foregoing letter, from the Budget assignment of Rupees 10,417 for "works of irrigation and navigation in the Central Delta.

Chepauk
6th Octr 1864

To The Supg Engineer 1st Dn
" Controller of P.W. Accounts
" Accountant General.

Sept 7th October

X'87

P. W. 1864 Detail
Ctr. of Govt. for Debt
Throw Rs. 4198.
The Superintending Engr.
1st Division-
To the Secretary to Govt.
P.W.D.
Dated 17th Oct. 1864
Desp. 13th Oct. 1864
Recd. 28
No. 967
Enclosures 2
Enclosures Plan & Estimate
for Constructing a Calin-
zgala in the Bundawoor
Eluk's Channel near
Indupilly amounting
to Rs. 980, and requests
Sanction for the same-
With due Order
No. 2875- 6th Oct. 1864

No. 57. 58

C. 10th Octr. 1864 Da. 30th Octr.

4/1861/4