

(1) Number of pages 12(2) Date of repair 12-2(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No.	887	Press
		Mis.
567-569		
Dated	31-3-	18 64.

Not to be folded or roughly handled

1

*Proceedings of the Madras Government, Public Works Department,
31st March 1864.*

No. 568. Read the following letter from Major General S. O. E. LUDLOW, Consulting Engineer for Irrigation and Canal Company, to Colonel C. A. ORR, R. E., Secretary to Government, Department Public Works, dated Kurnool, 2nd March 1864, No. 159:—

SIR,

1. I have the honor to submit for the consideration of Government Plans and an Estimate amounting after revision to Rupees 4,81,800 for ten miles and twenty-eight chains of the Canal between Adamapilly on the Pennaur river and the Cuddapah tank forming the tenth section (or the first portion of the tenth section) of the Main Canal.

2. This portion of the scheme includes an Anicut with head works across the Pennaur, and its submission presupposes the final adoption by the Chief Engineer of the south bank of the Pennaur for the course of the Canal after it leaves the Kundaury valley.

3. In my report, dated 29th October 1862, I stated my reasons for preferring the north to the south bank of the Pennaur for the course of the Canal below the Kundaury valley. An examination of the two Banks was subsequently made by Mr. Latham, one of the Company's Engineers, and a report was drawn up by him showing the comparative cost and advantages of the two lines.

4. Mr. Latham in his report, which though not communicated officially I have had an opportunity of perusing, confirms in an engineering point of view the opinion which I entertained in favour of the south bank of the river for the Canal course. He says: "It will be seen that notwithstanding the great amount of drainage and difficult ground encountered on the north route a lac of Rupees would be saved by adopting it, and two Anicuts entailing occasional danger and stoppage to navigation and a great chance of expense in maintenance would be avoided. Ten miles of length would also be saved. The traffic from the famous Cotton Districts of the Kundaury valley and the north and from the Suggilair Hills on which is the tree jungle nearest the coast of any upon our Canal will be facilitated on the above accounts. In fact the heavy and bulky goods for which the Canal would be adopted in preference to the Kundaury valley Railway would get a cheaper, shorter and more certain route on the north than on the south side of the Pennaur."

5. The traffic from the Suggilair valley would find its way to the Canal whichever side of the river it ran along; the saving in cost of construction I consider of little importance; that of ten miles in the length of the Canal is of more consequence, but the main advantage gained would be the dispensing with the two Anicuts the use of which to complete the line of navigation must always be attended with serious delays and inconveniences.

6. On the other hand if the north bank were adopted, the communication with Cuddapah and the large amount of traffic falling into the Canal in that rich, extensive, and central valley must be sacrificed; a large field of irrigation in the same valley would have to be abandoned and the supply of water which would be pitched up at Adamapilly from the Pennaur for irrigation and navigation as far as Somaiswaram would be lost.

7. These considerations, and they must be allowed to be of great weight, have induced the Chief Engineer, notwithstanding the engineering advantages held out by the north line, to give the preference to that along the south bank of the river.

8. Assuming therefore that all idea of adopting the northern bank of the Pennaur has been finally abandoned, I proceed to remark upon the Estimates for the course along the south bank including those herewith forwarded.

9. The last Estimates submitted to Government and by them sanctioned were for the eighth portion of the Canal as far as the 146th mile. Those for the thirty odd miles of the Canal forming the ninth section, that is between the termination of the eighth section and the Adamapilly Anicut, have not yet been received, neither has that for the portion between Cuddapah and the Guindy spurs where the Canal will begin to skirt the Pennaur on leaving the Cuddapah valley; but there are no particular difficulties in those two portions and the Plans and Estimates for them, which are in a forward state, may be shortly expected.

*Proceedings of the Madras Government, Public Works Department,
31st March 1864.*

10. Below the Guindy spurs the course of the Canal for some miles has been laid out, but I cannot learn that it has yet been determined how it is to be taken across the Cheyaur and how the formidable difficulties above that river are to be overcome. It seems however to be desirable that the whole scheme between Adamapilly and Somaiswaram should be submitted in a complete form before ground is actually broken in the Cuddapah valley.

11. These Plans and Estimates for the tenth section were returned by me to the Chief Engineer for correction and modification. The nature and extent of the alterations which I considered to be necessary are shown in my letter No. 25, dated 3rd February 1864. The Chief Engineer as appears by his No. 30, dated 25th idem, in re-submitting them has adopted all the most important modifications which I suggested.

12. With respect to the wells under that part of the body of the Anicut which stands on sand, although I concur with the Chief Engineer in thinking that the stability of the wall depends on the incompressibility of the sand, I yet consider wells or blocks to be necessary to aduit of the foundations being carried through the superficial stratum of sand which is *generally loose and compressible and liable to disturbance to some depth by currents sweeping along the face of the work*. I would not therefore dispense with them, and if used they should be of sufficient area to give proper support to the base of the wall.

13. Experience will prove whether or not the Aqueducts require any better flooring than has been allowed. The velocity over them is certainly not great, though more than double of what it is in other parts of the Canal. Hand rails 3 or 3½ feet high I consider to be necessary; the parapet of 1½ feet high now allowed in the case of the Boogah Aqueduct is insufficient for safety. In the revised Estimate Sluices to carry irrigating Channels under the stop bank have been provided, and the modifications deemed necessary by the Superintending Engineer for the security of existing irrigation have been adopted, and that Officer has furnished the certificate on that point required by Government.

14. The Chief Engineer has promised to forward an Estimate for an additional bridge in lieu of a ferry for the old Kurnool road. This is the only work wanting in the opinion of the Collector and myself to complete the means of passage across the Canal.

15. Estimates for irrigating Sluices will be furnished hereafter when the necessary surveys have been made.

16. The Chief Engineer's letter and the accompanying Plans describe sufficiently the nature and form of the works. The head works consist of the Anicut (with two sets of under-sluices) Lock and head Sluice. The Anicut is 2,400 feet in length and has its crest eleven feet above the deep bed of the river. It will rest through about one-third of its length on rock, two-thirds on sand, the section in each case being adapted to the particular foundations. A retaining wall built on the rock and extending to the end of the apron will separate the two portions on the lower side, the under-sluices at each extremity are inserted to prevent deposits in front of the Locks and head Sluices, and will allow of as much water as may be required below being passed down the river. The north Lock which will drop the navigation from the Kundaar valley into the basin formed by the Anicut does not appear in this Estimate, but will be included in that for the ninth section.

17. The Canal will have a breadth at bottom of 50 feet with a depth of 5 and side slopes of two to one. Its surface breadth will therefore be 70' except over the Aqueducts, where it is reduced to 25 feet. The total fall in the ten miles is one foot or 1.2 inches per mile, and it is calculated to carry a supply of water of 30,000 cubic yards per hour.

18. The Canal in its course passes clear of the Cantonment, but intersects a suburb of the Town of Cuddapah where however the houses which will have to be removed are of no great value.

19. As the works for which this Estimate provides are in my opinion suitable for the intended purpose and the rates sufficient, I beg to recommend it for the sanction of Government.

*Proceedings of the Madras Government, Public Works Department,
31st March 1864.*

No. 569.

ORDER THEREON, 31st March 1864, No. 889.

1. The Estimates submitted with this letter provide for all the works required between Adamapilly, on the Pennaur river, and the Cuddapah tank, forming the first portion of the tenth section of the Company's Main Canal. The Estimates for the ninth section, and for the remainder of the tenth, are not yet before the Government, but the Consulting Engineer states that they may be shortly expected.

2. The Government agree with Colonel Ludlow that it is highly desirable that the whole scheme between Adamapilly and Somaiswaram should be submitted in a complete form before ground is actually broken in the Cuddapah valley. They accordingly resolve to defer sanctioning the Estimates now before them.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Consulting Engineer Irrigation and Canal Company.
„ Agent for do. do.

Exd. T. Dunn.

N^o 159

Consulting Engineer's Office
Irrigation & Canal Company
Munroo 2^d March 1866

From,

Major General S. C. Ludlow
Consulting Engineer for S. C. C.

To,

Colonel C. A. Orr R. E.
Secretary to Government S. P. H.
Madras

Sir,

1. I have the honor to submit for the consideration of Government plans and an Estimate amounting after revision to Rupees 481,800-- for 10 Miles and 28 Chains of the Canal between Adamapilly on the Pennar River and the Suddapah Tank forming the 10th Section (or the first portion of the 10th Section) of the Main Canal.

2. This portion of the Scheme includes an Arricut with Headworks across the Pennar and its submission presupposes the final adoption by the Chief Engineer of the South Bank of the Pennar for the course of the Canal.

Canal after it leaves the Kunder Valley
3 In my Report dated 29th October 1862
I stated my reasons for preferring
the North to the South Bank of the
Pennar for the course of the Canal
below the Kunder Valley an exami-
nation of the 2 Banks was subsequently
made by Mr. Latham one of the
Company's Engineers and a report was
drawn up by him showing the com-
parative cost and advantages of the
two lines.

4. Mr. Latham in his report, which though not communicated
officially I have had an opportunity
of perusing confirms in an Engineering
point of view the opinion which I
entertained in favour of the South
Bank of the river for the Canal course.
He says "It will be seen that not-
withstanding the great amount of
drainage and difficult ground
encountered on the North Bank
a Lac of Rupees would be saved
by adopting it and two Annicula
entailing occasional danger and
stoppage to Navigation and a great
chance

"chance of expence in maintenance
"would be avoided. Ten miles of length
"would also be saved. The Traffic from
"the famous Cotton Districts of the
"Kunder Valley and the North and
"from the Suggalair Hills on which
"is the tree jungle nearest the Coast
"of any upon our Canal will be facili-
"tated on the above accounts. In
"fact the heavy and bulky goods for
"which the Canal would be adopted
"in preference to the Kunder Valley
"Railway would get a cheaper shorter
"and more certain route on the North
"than on the South side of the Pennar".
5. The Traffic from the Suggalair
Valley would find its way to the
Canal whichever side of the river
it ran along, the saving in cost of
construction I consider of little
importance; that if 10 Miles in the
length of the Canal is of more conse-
quence but the main advantage
gained would be the disposing
with the 2 Annicula the use of which
to complete the line of Navigation
must always be attended with

serious

serious delays and inconveniences.
6. On the other hand if the North
Bank were adopted the communication
with Fuddapah and the large amount
of traffic falling into the Canal
in that rich extensive and central valley
must be sacrificed; a large field of
irrigation in the same valley would
have to be abandoned and the supply
of water which would be picked up in
at Adamapilly from the Pennar for
irrigation and navigation as far as
Semaivaram would be lost.

7. These considerations and they
must be allowed to be of great weight
have induced the Chief Engineer
notwithstanding the Engineering
advantages held out by the North
line to give the preference to that
along the South Bank of the river.

8. Assuming therefore that the
idea of adopting the Northern Bank
of the Pennar has been finally
abandoned I proceed to remark
upon the Estimates for the course
along the South Bank including those
herewith forwarded.

The

9. The last Estimates submitted
to Government and by them sanctioned
were for the 8th Portion of the Canal as far
as the 46th Mile. There for the 30 odd
Miles of the Canal forming the 9th Section
that is between the termination of the
8th Section and the Adamapilly Junction
has not yet been decided whether
has that for the portion between
Fuddapah and the Guindy Spurs
where the Canal will begin to skirt
the Pennar on leaving the Fuddapah
Valley but there are no particular
difficulties in showing two portions and
the plans and Estimates for them
which are in a forward state may
be shortly expected.

10. Below the Guindy Spurs the course
of the Canal for some miles has been
laid out but I cannot learn that it
has yet been determined how it is
to be taken across the Cheyans and
how the formidable difficulties so
above that river are to be overcome.
It seems however to be desirable
that the whole scheme between
Adamapilly and Semaivaram
should

should be submitted in a complete
form before ground is actually broken
in the Siddapah Valley.

11. The Plans and Estimates for the 10th
Section were returned by me to the Chief
Engineer for correction and modification.
The nature and extent of the alterations
which I considered to be necessary are
shown in my letter No. 23 dated 3 February 1864.
The Chief Engineer as appears by his
No. 30 dated 25th Idem in resubmitting them
has adopted all the most important
the modifications which I suggested.

12. With respect to the wells under
that part of the body of the Anicut
which stands on sand, although I concur
with the Chief Engineer in thinking
that the stability of the wall depends
on the incompressibility of the sand
I yet consider wells or blocks to be
necessary to admit of the foundations
being carried through the superficial
stratum of sand which is generally
loose and compressible and liable to dis-
turbance to some depth by currents
sweeping along the face of the work.
I would not therefore dispense with them
and

and if used they should be of sufficient
area to give proper support to the base
of the wall.

13. Experience will prove whether or
not the Aqueduct require any better
flooring than has been allowed.
The velocity over them is certainly most
great, though more than double of
what it is in other parts of the Canal.
Hand rails 3 or 3½ feet high I consider
to be necessary; the parapet of 1½ feet
high now allowed in the case of the
Boogah Aqueduct is insufficient for
safety. In the revised Estimate 2
sluices to carry irrigating channels
under the slope bank have been
provided and the modifications deemed
necessary by the Superintending Engineer
for the security of existing irrigation
have been adopted and that Officer
has furnished the Certificate on that
point required by Government.

14. The Chief Engineer has promised
to forward an Estimate for an additional
Bridge in lieu of a Ferry for the old
Kurnool road. This is the only work
wanting in the opinion of the Collector
and

It does not appear to be proper to
Worship the shadow of

and suggest to complete the means of
passage across the Canal.

15 Estimates for irrigating sluices
will be furnished hereafter when the
necessary surveys have been made.

16. The Chief Engineer's letter and the
accompanying plans describe sufficiently
the nature and form of the works.

The headworks consist of the Anicut
(with 2 sets of under sluices) Lock and
Head sluice. The Anicut is 2,400 feet
in length and has its crest 11 feet above
the depth of the river. It will rest
through about $\frac{1}{3}$ of its length on rocks
 $\frac{2}{3}$ on sand. The section in each case
being adopted to the particular
foundations. A retaining wall built
on the rock and extending to the end
of the apron will separate the 2 portions
on the lower side. The under sluices at
each extremity are inverted to prevent
deposits in front of the Locks and
Head sluices and will allow of as much
water as may be required below being
passed down the river. The North Lock
which will stop the Navigation from
the Hundann Valley into the basin
formed

and

formed by the Anicut does not appear
in this Estimate but will be included
in that for the 9th section.

17 The Canal will have a breadth
at bottom of 50 feet with a depth of 5
and side slopes of 2 to 1. Its surface
breadth will therefore be 70 except
over the Aqueducts where it is reduced
to 25 feet. The total fall in the 10 miles
is 1 foot or 12 inches per mile and it is
calculated to carry a supply of water
of 30,000 cubic yards of water per hour.

18 The Canal in its course passes
clear of the Cantonment but intersects
a suburb of the Town of Cuddapah
where however the houses which will
have to be removed are of no great value.

19 As the works for which this Estimate
provided are in my opinion suitable
for the intended purpose and the rates
sufficient I beg to recommend it
for the sanction of Government.

I have the honor to be,
Sir,

Your most Obedient Servant,
J. P. M. Major General
Consulting Engineer for S. & C. B.

Comd.

But does not propose to Colonel Cudlow that

889

P. H. A.
151

Proceedings of the Madras Government
Under date the 31st March 1864

Read the following letter

Received 2nd March 1864

the Consulting Engineer for
navigation and Canal Company -

Submits for the sanction of
Government plans and an estimate
amounting to Rupees 1,81,800

for 10 miles of the main
canal forming the 10th Section.

The estimates
submitted with this
letter provide for all
the works required
between Adamapilly,
on the Pennar river,
and the Choddapeta tank,
- forming the first
portion of the tenth
Section of the Company's
Main Canal. The
estimates for the ninth
Section, and for the
remainder of the tenth,
are not yet before the
Govt., but the Consulting
Engineer states that
they may be shortly
expected.

The Govt. agree with
Colonel Cudlow that

I should think that we should
take upon ourselves the
modification or alteration of
the plan of the Eng. of the
Company - by so doing we
have certain extent relieve him
from responsibility. The
Consulting Eng. should
therefore I think limit him-
self to suggestions, & should
these not be adopted by
the Govt. - I do not think that
the Govt. should interfere
with adoption - in the case
of the existing plan unless
there is something to show
that they are defective in
any way & that the Govt.
should sanction them.

But does not propose to

Pro-19-200-1862-07
374-379
Copy in a letter to the
of 26-2-1864

11/11/1864
11/11/1864
11/11/1864

The Consulting Engineer

for 10 miles

for 10 miles

for 10 miles

for 10 miles

for 10 miles

for 10 miles

for 10 miles

for 10 miles

for 10 miles

for 10 miles

for 10 miles

for 10 miles

it is highly desirable
that the whole scheme
between Adamapilly &
Tomeiswaram should
be submitted in a
complete form before
ground is actually
broken in the Middlepala
valley. They accordingly
resolve to defer
sanctioning the
estimates now before
them.

after a plan in this
draft, but wants to have
a connected plan of
the works in this part
of the line (the Middlepala
valley) before ground is
broken. This seems to
me prudent & proper
as there known to be
great engineering diff-
culties, & Govt has to
pay interest on the
money expended

undesirable! 17/18
JP

W.B.

The
I think so too - and
with regard to a series
of plans & estimates sub-
mitted by the Compt
I may remark that
the Compt Secy has expressly
said the for the right and
therefore I think it proper
to have a duty of making

28
3

The Consulting Engineer J.C. Comp
Agent

The Dongfeng & Co.
Agent - do -
such reasonable alter-

Recd 1st April -
All the enclosures returned to
Cons. Eng. Secy C No 450 of 65 6/2/65

- various omissions &
additions as may be
considered necessary

