

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public works DEPARTMENT.

G.O. No. 2493	Press
628-620	Mis.
Dated 28-8-	1865.

Not to be folded or roughly handled

18

*Proceedings of the Madras Government, Public Works Department,
28th August 1865.*

Read the following papers :—

No. 628. From Lieutenant-Colonel G. V. WINSOM, R. E., Superintending Engineer, 2nd Division, to Colonel C. A. ORR, R. E., Secretary to Government, Department Public Works, dated Masulipatam, 12th May 1865, No. 15.

SIR,

Rupees 10,500 as per revised estimate now submitted.

„ 834 estimate for out-houses, sanctioned in G. O. No. 1,794, dated 21st June 1864.

Rupees 11,334 Total estimate.

* Rupees 9,700.

1. I have the honor to submit, for the sanction of Government, a revised estimate for constructing a Taluq Cutcherry at Ongole with a terraced roof amounting to Rupees 10,500, or Rupees 800 in excess of the original estimate,* sanctioned in G. O. No. 3,499, dated 30th November 1863.

2. The original estimate was prepared according to the Standard Plan approved by the Board in their Proceedings No. 2,848, dated 13th May 1863, in which a tiled roof was provided for.

3. The Board having lately expressed their opinion in Proceedings No. 6,762, dated 13th October 1864, that terraced roofs would be preferable for all the Taluq Cutcheries, as provided in the Standard Plan subsequently approved by them in their Proceedings No. 583, dated 28th January 1864, I have prepared the revised estimate now submitted, and solicit the sanction of Government, should it meet with approval.

4. Application for the excess sum will be made to Government when the allotment† granted in the Budget of the current year for this work is nearly expended.

† Rupees 5,534.

MEMORANDUM.

1. The undersigned has the honor to request that the Superintending Engineer, 2nd Division, will be good enough to include in the accompanying abstract estimate, the particulars of the estimate sanctioned in G. O. No. 1,794, dated 21st June 1864, for out-offices to the Taluq Cutcherry at Ongole, and to re-submit the papers with the prescribed comparative statement in which should be entered full information regarding the cause of the differences between the original and revised estimates both as respects quantities and rates.

2. No provision for flooring appears to have been made in the revised estimate.

FORT SAINT GEORGE,
23rd May 1865.

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government, P. W. D.

*Proceedings of the Madras Government, Public Works Department,
23th August 1865.*

No. 629. From Lieutenant-Colonel G. V. WINSKOM, R. E., Superintending Engineer, 2nd Division, to Colonel C. A. ORR, R. E., Secretary to Government, Department Public Works, dated Masulipatam, 8th August 1865, No. 53.

SIR,

1. With reference to your Memorandum, dated 23rd May 1865, I have the honor to forward an abstract estimate for the Taluq Cutcherry at Ongole, including the out-offices sanctioned in G. O. No. 1,794, dated 21st June 1864, amounting in all to Rupees 11,334, also the prescribed comparative Statement explaining the cause of the differences of the several items in the original and the revised estimates as requested.

2. My letter No. 15, dated 12th May 1865, returned with your Memorandum under reference, is herewith re-transmitted.

No. 630. ORDER THEREON, 28th August 1865, No. 2,493.

CIVIL WORKS, No. 88.

No. 3,499, dated 30th November 1863.
,, 1,794, ,, 21st June 1864.

1. In the Orders marginally noted, sanction was given to estimates, amounting in the aggregate to Rupees 10,534, for the construction of a Taluq Cutcherry with out-houses at Ongole, in the Nellore District. These estimates provided for a tiled roof, but the Board of Revenue having since given it as their opinion that terraced roofs are preferable for Taluq Cutcheries, the Superintending Engineer submits a revised estimate for the building, amounting to Rupees 11,334, or Rupees 800 in excess of the sum sanctioned.

2. The Governor in Council sanctions the revised estimate, and will be prepared to consider any proposal which the Superintending Engineer may make for the provision of the necessary additional funds.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 2nd Division, with comparative Statement.

,, Controller of Public Works Accounts.

,, Accountant General.

,, Revenue Department.

Exd. T. O'Connor.

No 53

Superintendent

Memorandum

The undersigned has the honor to request that the Superintending Engineer 2nd Division will be good enough to include in the accompanying abstract estimate the particulars of the ^{estimate} sanctioned in G.O. No. 1794 dated 21st June 1864 for Out Offices to the Taluq Cutcherry at Ongole, and to resubmit the papers with the prescribed Comparative Statement in which should be entered full information regarding the cause of the differences between the Original and Revised Estimates both as respects quantities and rates. No provision for flooring appears to have been made in the Revised Estimate.

*W. St. George
23rd May 1865*

*To the Superintending Engineer
of the 2nd Division*

Office of the Madras Government, Public Works Department,
23th August 1865.

34
From
The Supy Engineer
22.9.65

To
The Secy to Govt
P.W.
Madras.

Dated 12th May 1865
Recd 19th

Case 1 P.W. 3066/65

Submitting at Revised
Estimate for Constructing
Talug Cutcherry at
Angole amounting to
Rupees 10500 for
Sanction

10,21,93-28th August 1865

No 53

Supy Engrs Office 22.9.65
Masulipatam 8th August 1865

From

Col. G. V. Winsom R.E.
Supy Engineer 22.9.65

To

Colonel C. A. Orr R.E.
Secretary to Government
D.P.W.

Sir

With reference to your Memo
No. Dated 23rd May 1865. I have the
honor to forward an Abstract &
Estimate for the Talug Cutcherry
at Angole including the out-offices
sanctioned in G.O. No 1791 dated 21st
June 1864 amounting in all to Rs. 1133 1/4
also the prescribed comparative
statement explaining the cause of the
difference of the several items in the
Original and the Revised Estimates as
requested.

2. My letter No 15 dated 12th May 1865
returned on the your Memo under
reference

ABSTRACT ESTIMATE No. of 1865-66.

Leontomiscus. Vol 7 & 8
Sept 1891 at 21 2/4

reference is herewith transmitted.

Rev. 21st June 1865 No. 128
129.

B.T. 1865-52 Depto
No. 1 of 1865 for August
The Supg Engineer
2^d Division
To The Secy to Govt
D.P.W.

Dated 8 August 1865
Rec'd 16 "
B.B.

Submitting for sanction
a revised Estimate
for the construction of
Taling Culchery at Angole
Mellone District amount-
ing to Rs. 11,334 together
with the present
Comparative statement.

No. 629

2493-28 Augt/65

ork

Revised Estimate for constructing a new Taling
Culchery at Angole.

Quantity.	Description of Charges.	Rate.	Amount.	Total.
1202 1/2	l. y. Rough stone in chunam	2 8	3011 4	
374 5/8	do Brick in chunam	3 6	1264 59	
12 7/8	do Arch work	4 4	54 11 6	
8 56	l. ft. Teak wood wrought and put up	2 8	2140	
52 1/4	Sqrs of Terraced roof with brick on edge over teak wood joists & 2 coats plastering	24 8	1280 2	
19	Sqrs of Verandah roof with rafters - rafters & flat tiles	16	304	
200	Sqrs of one coat plastering	1	200	
61 1/4	do of two coats - do	3	185 4	
910	Running feet of cornice per 10 feet	1	90	
200	Sqrs of white wash	13	37 8	
2	Iron gate posts	30	60	
1	Large door 8 1/2 x 6		76 8	
4	Iron barred doors 7 x 4 in - clinging castings	50	200	
4	Iron barred doors 7 x 3 1/2 - do	43	172	
8	Batten doors 7 x 4	15	120	
29	Iron grates windows 2 x 3	10 8	94 8	
75	Circular batten windows 4 1/2 x 3	14	210	
3	Batten windows 4 1/2 x 3	12	36	
75	Running feet Iron railing	2 8	187 8	
	Constructing a well of 6 feet inside diameter		160	
	Carries forward		9883 11 3	

Quantity.	Description of Charges.	Rate.	Amount.	Total.
	Brought forward		9,883 1/3	
	Excavating foundations and filling basement —		60 . .	
	Sundries & Contingencies — 5		556 4/9	
			10,500 " "	10,500 " "
	Constructing a shed for the accommodation of Ryk			
41	b.yr. of Brick in Chumam — 3	10 . .	148 10 .	
982	Sqrs ft. of roofing with paluy. — rafters, bamboo reefers with pan tiles per sqre — 21	" . .	206 10 3	
1339	Sqrs ft. of plastering — 3	" . .	39 13 10	
20	C.yr. of Earth work — 1	6 . .	1 14 .	
	Sundries —		19 15 11	
			417 . .	
	Privy for Prisoners.			
36 1/2	C.yr. of Brick in Chumam — 3	10 . .	132 5 .	
18	Sqrs of plastering — 3	" . .	54 . .	
	Sundries &c —		8 11 .	
			195 . .	
	Privy for butchery servants			
38	C.yr. of Brick in Chumam — 3	10 . .	137 12 .	
208	Sqrs ft. of roofing with pal. — onya rafters, bamboo reefers, nails & pan tiles — 21	" . .	43 10 10	
10	Sqrs of plastering — 3	" . .	30 . .	
	Sundries & Contingencies —		10 9 2	
			222 . .	
	Total for out houses		834 . .	834 . .
	Total Estimate			11,334 . .

Superintending Engineer
Office 2^d Division
Masulipatam 8th August 1885.

Responsible Officer
Superintending Engineer 2^d Div.

No. 2493
 Proceedings of the Madras Government
 Under date the 28th August 1865

Read the following

From the Supt Engineer 2^d Divⁿ Here enter 12th May 1865 No 15
 From ——— 2^d Divⁿ
 Submitting for sanction a
 revised Estimate for the construc-
 tion of Taluk Catcherry at
 Ongole Nellore District amount-
 ing to Rupees 11,334 together
 with the prescribed Comparative
 Statement.

Here enter 8th August 1865
 No 53

No 3499 d/30-Nov/63
 ---1794 d/26-June/64---

MD
 WOH

In the orders marginally
 noted sanction was given to
 Estimates, amounting in the
 aggregate to Rs 10,534, for the
 construction of a Talook
 Catcherry with Out-houses at
 Ongole in the Nellore District.
 These Estimates provided for
 a tiled roof, but the
 Board of Revenue having
 since given it as their
 opinion that tenaced roofs
 are preferable for Talook
 Catcheries

MM 3066/65

Abstract Estimate
 No. of 1865-66.

Nellore District
 Revised Estimate for
 Catcherry & Ruins
 Taluk Catcherry at
 Ongole amounting to
 Rupees 11,334.

Proceedings of the Madras Government

Introduces the Superintending
Engineer submits a revised
estimate for the building
amounting to \$71,334. or \$71,334
800 in excess of the sum
sanctioned.

The Governor in Council
sanctions the revised estimate
and will be prepared to
consider any proposal
which the Superintending
Engineer may make for
the provision of the necessary
additional funds.

W.B.

6	The Sup. & 2 Divs
4	— Controller of P. & A.
3	— Accountant General
21	— Rev. Secy.

44

5

with comparative sketch

Dec 29th August

per 11818 & 2 up to
per no. of Good for
Aug 18 1862
per 24903 (1862)
per no. of the 11800
of 11800 up to 1865

According to the
received at the 11800
Aug 18 1862 for the
construction of a building
Cutechery with out house
at the 11800 & 1865

per 11800 @ 600

per 11800 @ 600