

(1) Number of pages 2(2) Date of repair 12-12-42

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 2881	Press
692-693	~~Mis.~~
Dated 28-9-	1865.

Not to be folded or roughly handled

12

*Proceedings of the Madras Government, Public Works Department,
28th September 1865.*

No. 692. Read the following letter from Lieutenant-Colonel E. A. FOORD, R. E., Superintending Engineer, 5th Division, to Colonel C. A. ORR, R. E., Secretary to Government, Department Public Works, dated Ussur, 19th September 1865, No. 1,577 :—

SIR,

1. I have the honor to forward, for the sanction of Government, an estimate amounting to Rupees 1,050, for " re-constructing a bridge of one arch of 12 feet, in the 110th mile of Trunk Road No. 9," in the South Arcot District.

1 Plan.

1 Estimate:

1 Specification Report.

2. The bridge was carried away in the great flood of last October. As there is always some water in the channel, and occasionally enough to render crossing very difficult, the re-construction of the bridge is much required. If the amount of the estimate cannot be spared from the " Reserve," I can only suggest that the estimate be sanctioned for entry in next year's Budget.

No. 693. ORDER THEREON, 28th September 1865, No. 2,881.

CIVIL WORKS, No. 93.

1. The estimate submitted with this letter is sanctioned.
2. As the Reserve under all heads is exhausted, and as the estimate is below Rupees 2,500, and cannot therefore be entered in the Budget, the execution of the work must be deferred until the next official year, when the Government will endeavour to provide the requisite funds from the grant for Minor Works under " Communications."

(True Extract.)

(Signed) J. H. M. SHAW STEWART, Major, R. E.,
Under Secretary to Government.

To the Superintending Engineer, 5th Division, with one detailed Estimate.
" Accountant General.
" Controller of Public Works Accounts.

Exd. S. T. Augustin.

CommunicationNew Work.Abstract Estimate No. of 1865/66.South Arcot DistrictMT Range.Andalore Taluk

Work—Reconstructing a small Bridge of 12 feet span across the Pongu-
mini Spring channel on the 110th Mile of the Trunk Road No. 9.

Inventories

Items	Rate	Per	Amount	Total
6636 $\frac{3}{8}$ Cubic feet of Brick in Annam—	1	9	left	725 13 7
504 — of Arch work in Annam—	2	"	do	63 " "
21 Squares of Plastering with 2 coats of Annam—	2	8	10 $\frac{1}{2}$	52 8 "
107 $\frac{1}{2}$ Running feet of Cornice work—	4	"	10 $\frac{1}{2}$	26 16 "
Excavating foundation filling approaches—	"	"	"	50 " "
Centring and removing—	"	"	"	30 " "
Baling temporary dam &c.—	"	"	"	50 " "
Incidents—	"	"	"	51 12 5

Total Rupees—1050
Rupees one thousand and fifty only.

See Raubey
A. Collector of S. Arcot.

Ed. Ford Lieut. Col. R. E.
Superint. Engineer &c.

From 28:29/62/45-2501692

22/3/48/55

Received

Civil Works

2887

50

1. The estimate submitted with this letter is sanctioned
2. As the Reserve ~~fund~~ under all heads is exhausted and as the estimate is below Rs 2500, and cannot therefore be entered in the Budget, the execution of the work must be deferred until the next official year, when the Govt. will endeavour to provide the requisite funds from the grant for minor works

[Handwritten initials and signature]

2555 Due to one delayed letter of 11/4/62
320 Acct. Genl.
420 Jntd. Hds. under "Communications"
Sept 28th September 23
28th Sept/65

1865
Pro. of Gov. of Sept 1865

From N^o 3646
The Superintending Engr
5th Division

To The Secretary to Government
D. P. W.

Dated 19th September 1865
Received 22 "
E O

Submitting an Estimate
with plan and Specification
report for Rs. 1050 for recon-
structing a bridge in the
110th mile of G. I. Road
No. 9 in South coast.
no. 2881-2885, Sept 1865

7692.693.