

(1) Number of pages 8(2) Date of repair 31-12-12

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public works DEPARTMENT.

G.O. No. <u>3847</u>	Press Mis.
<u>442-443</u>	
Dated <u>22-12-</u>	<u>1865.</u>

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
22nd December 1865.*

No. 442. Read the following letter from the Officiating Superintending Engineer, 1st Division, to the Secretary to Government, Public Works Department, dated Waltair, 28th November 1865, No. 1,920 :—

1. At paragraph 9 of G. O.* No. 1,168 of 6th July 1864, in the Revenue Department, Government directed that the approaches to the Salt platforms at Nowpada, in the Ganjam District, should be improved without delay.
- 1 Survey.
1 Plan of Tunnel.
1 Detailed Estimate.
1 Abstract do.

* Circulated with G. O. No. 2,024 of the 13th July 1864, Public Works Department.

2. I have, therefore, now the honor to submit an estimate, amounting to Rupees 7,490, for that work, which has been prepared in communication with the Salt Department, and bears the countersignature of the Collector.

No. 443. ORDER THEREON, 22nd December 1865, No. 3,847.

CIVIL WORKS, No. 65.

1. The Governor in Council sanctions the estimate, amounting to Rupees 7,490, for improving the approaches to the Salt pans at Nowpada, in the Ganjam District.

2. The work will, if possible, be entered in the outgoing Budget.
(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer of the 1st Division, with two Enclosures.

- Accountant General.
- Controller of Public Works Accounts.
- Revenue Department.

Exd. S. T. Augustin.

Office / 1st Div
20th Dec / 65

W. A. Scott, Capt. R. E.
Offg. Super Engineer, 1st Div

Public Road — Gangam District — New Work —
Abstract Estimate No 16 of 1865/66

Work — Construction of Certain Salt Roads to Nowpadeh
 Salt pans to connect ^{them with} the road from Nowpadeh to Bonmally
 Length 3 Miles 1577 Yards

Quantity	Description Work	Rate ^{Rs.} _{Ann.}	Amount	Total
16630 $\frac{5}{36}$	Cyds of Earth work	1.00	10396.2	
1417 $\frac{2}{3}$	— of Metalling	10.00	886.48	
5306 $\frac{2}{3}$	— of —	12.00	3980.00	
9109 $\frac{5}{9}$	Square Yards of Surfing	4.50	18912.5	
			60953.4	
	Contingencies	5.00	171.33	6433

Constructing 7 Tunnels of Vent of 3 feet Span.

25 $\frac{2}{3}$	Cyds Stone in Chumam	112.00	4444.8	
22 $\frac{17}{27}$	— Brick in —	236.50	5034.0	
5 $\frac{5}{6}$	— — in — Arch Work	36.00	191.0	
19 $\frac{1}{27}$	— Concrete Work	1.00	11.3	
4	Cyds of Plastering in Chumam	14.00	7.0	
1	Centring	3.00	3.0	
4	Guard Stones	1.00	4.0	
150	Cyds Earth Work	1.00	96.0	
200	Squares of Surfing	4.00	428.0	
			14301.1	
	Contingencies	5.00	715.1	

Total for One — 151.00
 Total for 7 Tunnels — 1057.00

Grand Total Dupes 7490

Supp. Engr. Office 1st Dec 7
 Walter, 28th Nov 1865

J. Peattie Capt. R.E.
 Public Works

84/1065/1066

N^o 1920

Superintending Engineer's
Office, 1st Divⁿ, Waltair.
28th November 1865.

From

Captain J. Beatty R.E.

Offg. Supg. Engineer, 1st Divⁿ.

To

Colonel C. A. Orr R.E.

Secretary to Govt., D.P.W.

Madras.

Sir,

At para 9 of G.O. N^o 1168 of 6th
July 1864, in the Revenue Department,
Government directed that the approach-
es to the Salt plot forms at Nowpada
in the Ganjam District, should be
improved without delay.

2. I have therefore now the honor
to submit an estimate amounting
to Rs 7490, for that work which has
been prepared in communication with
the Salt Department, and bears the
Countersignature

Encl. 4-

1 Summary
1 Plan of work
1 Estimate
1 Atch. - do

Circulated

1 to G.O. No.
2024 of the
13th July 1864
P.W. D.

From the High Commission
Do the Secretary to send

R.M.

Madras.

Oct 28th 1865

Recd. 4th Dec 1865

Dec 12th 1865

Encl. 5

Copy

for information the appraisement of the salt lands at Madras in the year 1865.

3817-2200 1865/65

Madras

16th Dec 1865 O.A. 157

1944 L. 448

3817-2200 1865/65

The Secretary

Council sanction the estimate amounting to Rs 14,000 for improving the appraisement of the salt lands at Madras, in the year 1865.

2 The work will be done.

3 possible, be entered in the

4. The work will be done.

5. The work will be done.

6. The work will be done.

7. The work will be done.