

(1) Number of pages 10
(2) Date of repair Oct 1963
(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public works DEPARTMENT.

G.O. No. <u>1757</u>	Press
<u>61-62</u>	Mis.
Dated <u>4-6-</u>	<u>18 66.</u>

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
4th June 1866.*

No. 61. Read the following Proceedings of the Madras Government in the
Revenue Department:—

Approving of an estimate, amounting to Rupees }
2,840, for constructing a road from Ayothia- } (Here enter 30th May 1866, No 1,278)
pinnam to Balur in the Salem District.

No 62 ORDER THEREON, 4th June 1866, No. 1,7 57.

LOCAL FUNDS, No. 12.
Civil Works.

Communicated to the Superintend-
ing Engineer of the 5th Division, with
reference to the Order of the 23rd April
1866, No. 1,274.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer of the 5th Division.
,, Accountant General.
,, Controller of Public Works Accounts.

Exd. S. T. Augustin.

Gravel

6905 7/8 431 1/4 431 1/4

1864

Communication _____ New Works 21
 Salem District _____ Salem Taluk

Estimate for Constructing a New Road
 from Ayothya-pattanam to Balur.

Description	Dimensions			Quantity	Total
	Length	Bread	Depth		
First Mile					
Earthwork					
Earth from both sides of the Road	1760	6 1/8		1320	
Foundation for Road dam	10	2 1/2		10	
Total Quantity of Earthwork				1330	
Gravelling					
Gravel	960	6 1/16		360	360
Stone Work					
New Stones for Road dam	10	1 1/2	1	15	15
Second Mile					
Earthwork					
Earthwork	1760	6 1/8		1320	
D:	120	6 1/2		360	
D:	1000	2 3/4		1500	
D:	280	4 3/4		840	
Foundation for Road dam	15	2 1/2		15	
Total Quantity of Earthwork				4035	
Gravelling					
Gravel	1280	6 1/16		480	480
Stone Work					
New Stones for Road dam	15	1 1/2	1	22 1/2	22 1/2
Third Mile					
Earthwork					
Earthwork	1060	6 1/8		795	
D: on the Tank bunds	70	4 1/2		110	
Total Quantity				935	
Gravelling					
Gravel	690	5 1/8		431 1/4	431 1/4

Description	Dimensions			Quantity	Total
	Length	Breadth	Depth		
Fourth Mile					
Earthwork					
For raising Embankments	1720	6 1/8		1290	
	140	7 1/2		140	
Total Quantity					1430
Fifth Mile					
Earthwork					
For levelling Roads	1160	6 7/8		870	
" " " " " "	325	2 1/2		325	
" " " " " "	240	6 1/2		720	
	35	7 1/8		122 1/2	
Total Quantity					2036 1/2
Gravelling					
Gravel					
	85	6 7/8		63 3/4	63 3/4
Sixth Mile					
Earthwork					
For Roads dams					
" " " " " "	63	2 1/2		63	
For raising Embankments	1243	6 1/8		932 1/4	
Earthwork	60	7 1/2		210	
	409	6 3/16		460 1/8	
Total Quantity					1665 3/8
Gravelling					
Gravel					
	25	6 7/8		13 3/4	13 3/4
Stone Work					
New Stones for Roads dams					
	38	1 1/2	1	57	57
Seventh Mile					
Earthwork					
" " " " " "	751	6 3/16		844 1/8	
Foundation for Roads dams	880	6 3/4		3960	
Earthwork	15	2 1/2		15	
	111	6 7/8		85 1/2	
Total Quantity					4905 3/8
Stone Work					
New Stones for Roads dams					
	15	1 1/2	1	22 1/2	22 1/2

Description	Dimensions			Quantity	Total
	Length	Breadth	Depth		
Eighth Mile					
Earthwork	1266	6 $\frac{7}{8}$		949 $\frac{1}{2}$	
Foundations for Roads dams	30	2 $\frac{1}{2}$		30	
Earthwork	300	6 $\frac{1}{4}$		450	
For raising Embankments	30	7 $\frac{1}{2}$		105	
For Sloping banks of Streams	140	6 $\frac{1}{2}$		420	
Total Quantity					1954 $\frac{1}{2}$
Stone Work					
New Stones for Roads dams	30	1 $\frac{1}{2}$	1	45	45
Ninth Mile					
Earthwork					
Earthwork	1239	6 $\frac{1}{8}$		929 $\frac{1}{4}$	
Foundations for Roads dams	8	2 $\frac{1}{2}$		8	
Earthwork	520	6 $\frac{3}{16}$		584	
Total Quantity					1521 $\frac{1}{4}$
Stone Work					
New Stones for Roads dams	8	1 $\frac{1}{2}$	1	12	12
Tenth Mile					
Earthwork					
Earthwork	1760	6 $\frac{3}{16}$		1980	
Total Quantity					1980
Eleventh Mile					
Earthwork					
Earthwork	220	6 $\frac{3}{16}$		247 $\frac{1}{2}$	
For Sloping banks of Streams	60	7 $\frac{3}{4}$		315	
Total Quantity					562 $\frac{1}{2}$

Abstract

Particulars

Quantity

Unit

Rate

Amount Total

1	Earthwork	Cyds	1330	6	7/14	110 13 4	
	Gravel	"	350	"	7/4	90 "	
	Stone Work	"	15	"	7/8	7 8 "	
	Total						208 5 11
2	Earthwork	Cyds	1035	"	7/14	336 4 "	
	Gravel	"	480	"	7/4	120 "	
	Stones New	"	22 1/2	"	7/8	11 4 "	
	For Removing Rocks	"	"	"	"	20 "	
	Total						487 8 "
3	Earthwork	Cyds	935	"	7/14	77 14 8	
	Gravel	"	431 1/4	"	7/4	107 13 "	
	Total						185 11 8
4	Earthwork	Cyds	1430	"	7/14	119 2 8	
	Total						119 2 8
5	Earthwork	Cyds	203 1/2	"	7/14	169 12 "	
	Gravel	"	63 3/4	"	7/4	15 15 "	
	Total						185 11 "
6	Earthwork	Cyds	166 5/8	"	7/14	138 12 "	
	Gravel	"	18 3/4	"	7/4	4 11 "	
	New Stones	"	57	"	7/8	28 8 "	
	Total						171 15 "
7	Earthwork	Cyds	4905 3/8	"	7/14	408 12 6	
	New Stones	"	22 1/2	"	7/8	11 4 "	
	Total						4120 " 6
8	Earthwork	Cyds	195 1/2	"	7/14	162 13 4	
	New Stones	"	45	"	7/8	22 8 "	
	Total						185 5 11
9	Earthwork	Cyds	152 1/4	"	7/14	126 12 4	
	New Stones	"	12	"	7/8	6 "	
	Total						132 12 10
10	Earthwork	"	1980	"	7/14	165 "	
11	Dz	"	562 1/2	"	"	46 14 "	
	Total						2308 5 10
	Sundries & Contingencies						231 10 2
	Compensation						25 10 "
	Total						300 "
	Total						2810 "

Collector
Salem Range Office
Salem 23rd Decr/64

A. M. Esparme. Assistant Engineer
Salem Range

Proceedings of the Madras Government, Revenue Department, 30th May 1866.

No. 520. Read the following Proceedings of the Board of Revenue, dated 17th May 1866, No. 3,462.

Read the following letter from the Collector of Salem, to the Secretary to the Board of Revenue, dated 14th May 1866, No. 72:—

With reference to the Board's Proceedings, No. 2,853, dated 23rd April 1866, communicating Order of Government, No. 881, dated 17th idem, calling for fuller information as to the necessity of the road from Ayothiaputnum to Balur, I have the honor to state, that the road in question will eventually open up the valley from Toomal to Cottaputty, where there is considerable traffic now in timber and grain.

Submitted for the information of Government, with reference to their Proceedings quoted by the Collector.

No. 521. ORDER THEREON, 30th May 1866, No. 1,278.

Local Funds, No. 17.

Civil Buildings.

Approved.

(True Extract.)

[Signature]

Secretary to Government.

To the Board of Revenue,
the Public Works Department.

Exd. S. T. Augustin

15

1757

18

7-5-4

Communicated to the
Representing Congress of the S^t
Union with reference to the action
of the 23^d April 1866, A^d 12th 14.

Fort St George }
15 June 1861 }

The Disfranchising Congress



of the 3rd Division
"Adjutant General
"Quarters of 10th St. and
"P. 100

P. W. Webb Sept
Pro of Govt for June
No. 1204.

Pro: of the Maoris Govt
in the Rev: Sept

Of 30 May } 1866
Rev: June }

Ca: one. No 1278.

Approving of
an estimate amount-
ing to Rs 2,840 for
constructing a road
from Agorkiaputum
to Balur in the
Salem District.

No. 12

No. 1757. 24 June 66