

(1) Number of pages 8

(2) Date of repair 14-1-45

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public works DEPARTMENT.

G.O. No. 1764	Press
76-77	~~Mis.~~
Dated 5-6-	1866.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department,

5th June 1866.

No. 76. Read the following letter from the Superintending Engineer, 7th Division, to the Secretary to Government, Department Public Works, dated Coonoor, 25th May 1866, No. 24 :—

* No. 4 of 1866-67.

1. I have the honor to submit for sanction an estimate, amounting to Rupees 3,400,* for improving the lower four miles of the Nunjapoogaloor Channel in the Caroor Taluq of Coimbatore District, and increasing the volume of water supplied. This useful channel has undergone some improvement under late sanctions, consisting in repairs to its head sluice, and in the construction of one surplus escape and twenty small irrigation sluices. It is to profit by the economy of water thus effected that the widening of the lower channel is proposed, and this should be carried out as soon as funds are available.

2. The project is recommended by the Range Officer and Revenue authorities to relieve the wants of the two villages lowest down the channel, which suffer greatly from the present precarious supply.

No. 77. ORDER THEREON, 5th June 1866, No. 1,764.

CIVIL WORKS, No. 15.

The Right Honorable the Governor in Council sanctions the estimate, amounting to Rupees 3,400, for improving and widening the lower four miles of the Nunjapoogaloor Channel in the Coimbatore District, and directs that the outlay on the work be charged against the Reserve under "Agricultural."

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 7th Division.

„ Accountant General.

„ Controller of Public Works Accounts.

Exd. S. T. Augustin.

Agricultural

22-4 of 1866/67

Detailed Estimate No 40

District Coimbatore, Taluk Caroor.
Work Improving and Widening Mungapogalore
Channel -

Particulars of work	Measurement			Contents
	C	B	ft	
Widening old Channel	400	b-	5.33	12792
Do	400	b-	5.37	12888
Do	400	b-	6.18	14832
Do	400	b-	6.69	16056
Do	400	b-	7.13	17112
Do	400	b-	7.16	17184
Do	400	b-	7.64	18336
Do	400	b-	8.57	20424
Do	400	b-	6.42	16408
Do	400	b-	4.71	11304
Do	400	b-	5.16	12384
Do	400	b-	5.11	12264
Do	400	b-	4.24	10176
Do	400	b-	4.43	10632
Do	400	b-	3.89	9336
Do	400	b-	3.58	8582
Do	400	b-	4.20	10080
Do	400	b-	5.00	12000
Do	400	b-	3.02	7248
Do	400	b-	4.46	10704
Do	400	b-	4.25	10200
Do	400	b-	4.62	11088
Do	400	b-	4.84	11616
Do	400	b-	4.38	10512
Do	400	b-	4.13	9912
Do	400	b-	4.75	11400
Do	400	b-	4.19	10056
Do	400	b-	5.07	12168
Do	400	b-	5.80	13920
Do	400	b-	5.00	12000
Do	400	b-	4.00	9600
Do	400	b-	3.50	8400
Do	400	b-	4.45	10680
Carried over				38221 1/2

inculcate

Public Works Department

1966

no. 1764

PROCEEDINGS of the MADRAS GOVERNMENT
Under date the 5th June 1866
Read the following

From
The Superintending Engineer
of the 7th Division

(Here enter No. 24 dated 25th May 1866)

The Right Hon
:table the Governor
in Council sanction
the estimate amounting
to Rupees 3400 for
improving and
widening the lower
four miles of the
Kunjapoo-galoon
channel in the
forniturest and
directs that the
outlay ^{on the work} be charged
against the Reserve
under "Agricultural

N.

Wm.

20587 Du
20487
20587 Du
20587 Du

24
4

APB

as a letter from the
Engin^r to the Secy
of the S. P. M. S.
of 24 of 25th May 1866

(River Range)
1865
1865
The Executive Agent
of the River Range
of the S. P. M. S.
of 24 of 25th May 1865
for improving
and widening
Kunjapoo-galoon
channel

20587 Du

I W B Department.

Pro. of Court for June

Aug. 1864.

Pro. of the Marine Corps

of 3rd June 1864

Pro. of the Marine Corps
of 3rd June 1864

(dd) 1864

The estimate amounting
to \$2,500 for improving and
widening the lower four miles
of the Japocoalco Channel,
Cambridge Dist. mentioned.

Aug. 1864.