

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public works **DEPARTMENT.**

G.O. No. 1843	Press
253-254	Mis.
Dated 12-6-1866.	

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
12th June 1866.*

No. 253. Read the following letter from the Officiating Superintending Engineer, 8th Division, to the Secretary to Government, Department Public Works, dated Madura, 1st June 1866, No. 238:—

With reference to G. O. No. 688, of the 28th February 1866, I have the honor to forward an estimate of Rupees 4,900 with plan and report, for substituting a tiled roof for the present thatched roof of the Jail at Paumbem. I had expected

- 1 Abstract Estimate.
- 1 Plan.
- 1 Specification.

to have submitted this estimate much sooner, but it came to my Office first without a plan, then, owing to the death of Conductor Bywater, the plan could not be furnished till Overseer Sanderson arrived at Paumbem.

No. 254. ORDER THEREON, 12th June 1866, No. 1,843.

- - CIVIL WORKS, No. 41.

Madura District.

The estimate of Rupees 4,900, submitted with this letter, for substituting a tiled roof for the present thatched roof of the Jail at Paumbem, is sanctioned for immediate execution from the

grant for Minor Works under "Civil Buildings."

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 8th Division, with Report.

- „ Accountant General.
- „ Controller of Public Works Accounts.
- „ Judicial Department.

Exd. S. T. Augustin.

Special

New work

Abstract Estimate No. of 1866-67

District Madurai

No. Tiling Sull Roof at Paumbeh

Particulars of work	Rate	Amount	Amount of each part			
	Rs	as	P	Rs	as	P
Square feet roofing with old palmyra rafters new reepers flat and Paracal pan tiles & Chunam borders per square Rs. 20 " " 2268 " "						
Extra palmyra couples complete and new collar beams for present couples				588	8	"
					2856	8 "
Square feet roofing with palmyrah reepers flat and pan tiles &c. per square — Rs. 20 " " 1218 3 2						
New palmyra couples				710	12	"
					1928	15 2
Sundries				114	8	10
Total Estimate Rs				4900	"	"

on behalf of the Sudder

the May Offg. Superintendent

1866

Captain R. B. Sanderson Overseer

8th Bn

In charge of appts. Paumbeh

No. 238 Superintendent's Office
Madura 11th June 1866

By

Captain H. S. Sandercock
Off^{ce} Superintendent Engineer S.D. Division

By

Colonel C. A. Cr. R.E.
Secretary to Government S.D. Division

Sir,

With reference to G.O. No. 688 of the 28th February 1866, I have the honor to forward an estimate of Rupees 14900 with plan and report, for substituting a tiled roof for the present thatched roof of the jail at Paimben. I had expected to have submitted the estimate much sooner; but it came to my Office first without a plan; then, owing to the death of Conductor Pyper, the plan could not be furnished, till Overseer Sanderson arrived at Paimben.

I have &c

H. S. Sandercock
Captain R.E.
Off^{ce} Superintendent Engineer S.D. Division

1. The Estimate
1. Plan
1. Report

15/18/66

15/18/66

Enclosure in letter from Mr. Cr. R.E. dated 28th June 1866

To Mr. Cr. R.E. Secretary to Government

8/12319/66

15/18/66

Estimate for tilting the jail roof at Paimben for Rupees 14,900

Caeculati

216. 1843

4

CH-8

Order 33

Product-fact at Commerce,

Sanctioned by immediate
Specification from the South

For minor works under
P.O. Order

[illegible]

With rice Sales
£10,154.8.12 ~~June~~ 1806

42 Montpelier St.
12 June 1886
Gustaf Hauer
12 June 1886