

(1) Number of pages _____

(2) Date of receipt _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 2680

Press
Min.

540-541

Dated 24-8-1866

Not to be folded or roughly handled

113

*Proceedings of the Madras Government, Public Works Department,
24th August 1866.*

No. 540. Read the following letter from the Superintending Engineer, 5th Division, to the Secretary to Government, Department Public Works, dated Salem, 14th August 1866, No. 85 :—

I have the honor to forward, for the sanction of Government, a supplemental Estimate of Rupees 393-12-11 for additional works required at the Jollarett Rest-house. These consist of a well, an aloe hedge for enclosing the compound,

3 Plans.

1 Abstract Estimate.

and an entrance gate with culvert, and are very necessary. The estimate of Rupees 3,410, for the Rest-house, was sanctioned in G. O., No. 3,287, on the 1st November 1865, work to the amount of Rupees 3,195-11-2 was done in the last official year, and the sum of Rupees 361*

* G. O. No. 1,919, dated 20th June 1866.

was allotted for the current year. The Rest-house has been completed for Rupees 3,291-0-10, and with the saving, the extra works have been partly carried out; but a further sum of Rupees 128-2-7 is required, which may be transferred from the Minor New Works allotment of Bangalore, and I request the sanction of Government for the same.

No. 541. ORDER THEREON, 24th August 1866, No. 2,680.

MILITARY WORKS, No. 28.

The supplemental Estimate of Rupees 394 submitted with this letter for additional works required at the Jollarett Rest-house in the Salem District is sanctioned. The proposed extra outlay during the current year will be met from the source pointed out by the Superintending Engineer of the 5th Division.

Rupees 128-2-7.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 5th Division.
,, Military Department.
,, Controller of Public Works Accounts.
,, Accountant General.

Ed. S. T. Augustin.

Salem District ——— Posson Range ——— Tripatore Taluq
Abstract Estimate No. 30.
Work. Supplemental estimate for completing a Rest House at
Jollarapett.

Quantities	Particulars of work	Per	Rate	Amount	Total
20 ¹² / ₂₇	— Well — C. yds. of Brickwork in Chumand	Cyd	3 8	71 8 0	
49 ¹ / ₈	— do; — Sinking well —	do	12	37 3 6	
17 ¹ / ₂	— do; — do; — do; —	do	8	8 12	
8 ³ / ₄	— do; — do; — do; and blasting rock —	do	2 8	21 4	
1 ¹ / ₂	Sq. ft. — Plastering with 2 coats of Chumand —	Sq. ft.	3	4 8	
1	Cyds. of Spreading earth round the well —	Cyd	2	8	144 6 4
	— Gate and Gateway —				
6 ² / ₃	Cyds. of Excavating foundation —	Cyd	1	1 8	
8 ² / ₃	— do; — Rough stone work in Chumand	do	2	13 5 4	
5 ¹ / ₉	— do; — Brick work in — do; —	do	3 8	17 4 2	
2 ¹ / ₃	Sq. ft. — Plastering with coat of — do; —	Sq. ft.	2 8	5 13 4	
2	Head pieces for Pillars including plastering work in Chumand —	each	3	6	
1	Jungle wood gate 12x5 in halves with iron hinges, clamps, bolts and Lock well tarred over. —	do	35	35	78 7 6
	Tunnel of 1 inch 3x3 to cross over Railway boundary ditch near gate				
18 ² / ₃	Cyds. of Excavating foundation —	Cyd	1	1 2 8	
18 ² / ₃	— do; — Rough stone in clay —	do	1 8	28	
10 ¹² / ₂₇	— do; — Brick work in Chumand —	do	4	41 12 5	70 15 1
	— Hedge —				
600	Pg. yds. of Planting Aloe Hedge and watering —	Pg. yd.	2	75	
300	Cyds. of Earth work making a ditch for forming a bank @ 12 —	Cyd	1	26	100
	Carried over				393 12 11

Brought forward	393	12	11
Deduct sum paid out of estimate for Rest House	119	3	2
Amount now requiring sanction	274	9	9

Coimbatore Range Office
Malapady 21st June 1866

J. W. Carpenter
Assistant Engineer
Edmund Leitch Col. R. E.
Superintending Engineer

3rd Division D. G. W.
Salem District
Coimbatore Range.

22nd 3353/66

Supplemental
Abstract
Estimate for completing
a Rest House for
a Troop at Jolarpet, in
the Coimbatore Range.

Amount of Estimate Rs 274.9.11

N^o 85- Superintending Engineer's Office
Salem 14th August 1866.
From The Superintending Engineer;
5th Division

To The Secretary to Government.
Department Public Works.

Sir,
I have the honor to forward for the
sanction of Government, a supplemental estimate
of Rupees 393-12-11 for Additional Works
required at the Jolarpet Rest House.
These consist of a Well, an Aloe hedge for en-
closing the compound and an entrance gate with
culvert, and are very necessary. The estimate of
Rupees 3410, for the Rest House was sanctioned
in G. O. N^o 3287 on the 1st November 1865,
work to the amount of Rupees 3,195-11-2 was
done in the last Official year, and the sum of
Rupees 361, was allotted for the current year.
The Rest House has been completed for
Rupees 3,291-0-10, and with the saving the extra
works have been partly carried out; but a
further sum of Rupees 128-2-7 is required,

res 4
to.

1919
1866.

No. 2680

Proceedings of the Madras Government

Under date the 24th Aug 1866
Read the following

From

The Supg. Engineer of the
5th Division = (H.R. No. 85 dated 14th August 1866)

The Supplemental estimate of Rupees 394 submitted with this letter for additional works required at the Sollarpett Rest House in the Salem District is sanctioned - The proposed ^{extra} outlay during the current year will be met from the source pointed out by the Superintending Engineer of the 5th Division

Rs 128-2-7.

[Signature]
W.D.

- 6 To the Supg. Engr. 5th Div.
- 7 -- Military Dept.
- 4 -- [?] of the [?]
- 3 -- Accountant General

Dup^d 27: Aug^t

30

[Signature]

[Signature]
The Secy. to Govt. of Madras
14th August 1866
Received 15th August 1866
No. 85.

Enclosed 4
Submitting for sanction
a Supplemental estimate
for extra works to the
Sollarpett Rest House.

P W 1855 Depto

Pro: of Govt for August

No 2601.

Pro: of the Madras Govt

D/24th August/85

The supplemental
estimate of Rspees 394
for additional works
required at Sollarpett
Rest-house in the Sa-
lem District, sanction-
ed, &c.

A 570. 541