

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referrer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 2880	Press Mis.
221-222	
Dated 10/11/1866	

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
10th September 1866.*

No. 221. Read the following letter from the Superintending Engineer, 3rd Division, to the Secretary to Government, Public Works Department, dated Camp, Colaganhully, Raidroog Taluq, 28th August 1866, No. 1,548 :—

1. I have the honor, with reference to G. O. No. 2,749, of 18th September 1865, to submit the accompanying estimate,* &c., for laying down cut-stone drains in the European Barracks at Bellary, and to inform you that the same has met with the approval of His Excellency the Commander-in-Chief.

2. I had roughly estimated the cost of this work at Rupees 10,000, as I was informed that the cut-stone work could be done under Rs. 2 the running foot. Paragraph 12 of letter No. 83, of 19th July 1865. A small portion of the stone was provided at this low rate, but the Stone Wudders soon found that it was insufficient, and it has been therefore necessary to increase the rate.

3. I am glad to be able to inform you that, since the breaking up and closing of the old drains, there have not, I was told by the Major General Commanding the Division, been any cases of a typhoid nature.

No. 222. ORDER THEREON, 10th September 1866, No. 2,880.

MILITARY WORKS, No. 15.

1. The Governor in Council sanctions the estimate amounting to Rupees 17,000 for laying down cut-stone drains in the European Barracks at Bellary.

2. The work is in progress under the authority of G. O. No. 2,749, dated 18th September 1865, and Rupees 5,000 have been provided for it from the current year's Reserve.

(True Extract.)

Colonel, R. E.,

Secretary to Government.

To the Superintending Engineer, 3rd Division.

„ Controller of Public Works Accounts.

„ Accountant General.

„ Military Department.

Ed. S. T. Augustin.

New work

ABSTRACT ESTIMATE.

Military

Bellary District.

Estimate of the probable expense of laying down cut stone drains to carry off the water from the washhouses of the European Infantry Barracks.

Quantities.	Description of Work.	Rate.	Amount.	Amount of each part
3178 1/2 cft	Excavation for foundations --- c.ft. @	3 -	220 11 -	
1177 1/2 cft	Foundation of concrete well rammed. cft. @	1 6	821 7 1/2	
876 1/4 cft	Cut stone slabs 3 ft. in width sloped, including bedding in Chumam pointing & followed to the centre 3 inches	3 -	13731 -	
4577 cft	Drain of long undressed granite slabs edges cut and pointed with Chumam including stone in Chumam under slabs to give the proper slope.	1 -	600 -	
2300	Stone in Chumam work to drain from No. 4 to No. 7 to give the required slope to the cut stone drain. foundations, and pointing	2 -	287 8 -	
	Add for excavation and concrete required to the 370 c.ft. of 11 junction lines	69 10 9	69 10 9	5723 1 1/2
	Summies @ 5 per cent			786 1/2
5000	Taking up old drains and filling in with gravel, re-building sundry garden walls (Actual Cost)			474 6 11
Total Estimate Rs				16997 -

N Bellary
19 July 1866

Assistant Engineer D.P. M.
A. W. M. Major R.E.
Superintendent P. J. M.

By Order
J. H. M. M.
D. S. - 21 sh. G. M. f. d. 1/2

Superint^g Engineer's Office 3rd Divⁿ
Bellary District
Railway Station
Camp Pochanahally
28th August 1886.

N^o 1528

From
The Superintending Engineer
3rd Division

To
The Secretary to Government
Public Works Depart^t

Sir,

I have the honor with reference to
S. O. N^o 2749 of 18th September 1865 to submit
the accompanying Estimate N^o 1 for laying down
cut stone drains in the European Barracks at
Bellary and to inform you that the same has
met with the approval of His Excellency the
Commander in Chief.

2. I had roughly estimated the cost of
this work at Rs. 10000, as I was informed that
the cut stone work could be done under Rs. 2
the running foot - a small portion of the stone
was provided at this low rate but the stone bidders
soon found that it was insufficient and it has
been therefore necessary to increase the rate.

3. I am glad to be able to inform you
that, since the breaking up and closing of the
old drains, there have not, I was told by the
Major General commanding the Division, been
any cases of a typhoid nature.

I have the honor to be,
Sir,

A. W. D. Major G.
Superint^g Engineer 3rd Divⁿ

Rs. 17,000

Per 12 of letter
N^o 83 of 19th July
1865.

Abstract Estimate.

new work. Military

Rs. 17,000

Estimate of the probable
expense of laying down cut
stone drains & carrying off the
water from the machanicos
of the European Infantry
Barracks.

Estimate No. 1699.

July 1872

Public Works Department.

210,2880

PROCEEDINGS of the MADRAS GOVERNMENT

Under date the 10th Sept/66
Read the following

(Here enter No. 1548 dated 28th Aug 1866)

The Governor in Council sanctions the estimate amounting to Rupees 17,000 for laying down cut stone drains in the European Barracks at Bellary.

The work is in progress under the authority of G.O. No. 2749 dated 18th Sept 1865, and Rupees 5000 have been provided for it from the current year's Revenue.

From the Supt Engineer
of the 3rd Division

W.M.

To Sd. Ac. with specific
to Cont. M. S.
to Sd. Ac.
to Sd. Ac.

21st Sept 1866

O. P. M. S. D. O. Ac.
No. 1 of 10th Sept 1866
from

including 27th Aug
1866

the Supt. Eng.
1866

21st Sept 1866
No. 3 of 10th Sept 1866

Dec 3

1548

Reference to G.O. No. 2749 dated
18th Sept 1865, for sanctioning
Plan to provide for the
laying down cut stone
drains in the European Barracks
amounting to Rs. 17,000.

210,2880 - 1866 - 210,2880

210,2880 - 1866 - 210,2880

P. W. 1866. Department.
Proc. of Govt. for Sept
No. 2800

PROCEEDINGS OF GOVERNMENT. *of Texas*

Dated *10 Sept 1866*

*the amount of \$17,000
for the buying down of claims
outstanding to the Government
Bureau at a selling discount.*

A. L. J. 1866

Sept 16 1866