M.R.O. 1—77,006—8-6-37.

(1) Number of pages 12

(2) Date of repair 16.2.43

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 2851 Press Mis.—

223-224

Dated 10-5- 1866.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department,
10th September 1866.

No. 223. Read the following letter from the Superintending Engineer, 5th Division, to the Secretary to Government, Department Public Works, dated Bangalore, 31st August 1866, No. 93 :—

2 Plans.
2 Abstract Estimates.
2 Specifications.
2 Site Plans.

1. As called for in G. O. No. 327, of the 4th of February 1865, I have the honor to submit for sanction plans and estimates for the undermentioned buildings in the District of Salem :—

Constructing a Táluq Cutcherry at Namakal, estimate Rupees... 13,370
Constructing a Sub-Magistrate's Cutcherry at Pennagaram, estimate Rupees 3,380

2. The design for the Táluq Cutcherry is in accordance with the Standard Plan, and that for the Sub-Magistrate was prepared in communication with the District Magistrate and the Superintendent of Police; and both the plans have been approved by the former.

No. 224. ORDER THEREON, 10th September 1866, No. 2,881.

CIVIL WORKS, No. 40.

The estimates submitted with this letter for a Táluq Cutcherry at Namakal and for a Sub-Magistrate's Cutcherry at Pennagaram, in the Salem District, are sanctioned; but as there is no probability of funds being available for the commencement of the works during the current official year, the Superintending Engineer of the 5th Division is requested to enter the estimates in his Budget for 1867-68.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 5th Division.
,, Controller of Public Works Accounts.
,, Accountant General.
,, Revenue Department.

Exd. S. T. Augustin.

No. 5. 5th Division P.W. 83

Salem District — Salem Range.

Civil Buildings — New work — Darampuri Taluk.

Abstract of an Estimate for constructing a Sub. Magistrate's Kachari at Pennagaram.

Quantity or Number	Description of work	Per	Rate	Amount	Total
128 5/6	Cub. yards of rough stone in chunam	Cy.	2 8	322 1 4	
259 1/3	do do of brick work in chunam	do	3 8	907 10 8	
281 1/4	Cub. ft. of arch work in chunam	Cft.	2 9	48 5 5	
91 1/4				295 12	
95	Squares of Plastering with 2 coats of chunam	Sqr.	3 4	308 12	
33 1/8				839	
31 7/10	Squares of roofing with Palmyra couples and rafters	do	25	8678	
16 1/2	Squares of flooring with 8" Square tiles in chunam	do	6	99	
3	Batten Doors	Each	16	48	
6	do do Windows	do	12	72	
3	Iron Revolving Doors	do	45	135	
10	Post for veranda	do	4	140	
68	Running feet of plank	Rft.	2	8 8	
28	Cub. ft. of Jungle wood wrought and put up	Cft.	2 8	70	
1	Entrance Door			28	
10	Iron Lyatings	Each	5	50	
				11 15 6	
143 3/4 / 144 1/2	Cub. yards of earth work	Cy.	1 4	11 13 4	
				3266 7 11	
	Excavating a well			250	3266 10 9
					163 11 11
	Sundries and Contingencies				143 5 3
				Total Rupees	3410

Salem Range Office
Yerkaud 6th July 1866

Rupees Three thousand four hundred and ten only

A. Edgeworth Lieut R.E.
Assistant Engineer

D. Ellicott
Collector of Salem

J.W.M. Lieut & Co R.E.
Superintg Engr 5th Div

5-4 Division D. P. W.

Civil Building — New Work

Abstract Estimate No. of 1866/67.

Salem District — Akbar Range — Namacal Taluq

Work — Constructing a New Taluq Kutcherry at Namacal agreeably to the Standard Plan.

Quantity	Description	Rate	Amount	Total
566	C.yds. of rough stone work in chunam for foundation	2 8	1415	
748 13/16	—Do— brick in chunam work from basement	4	2994	12
31 17/27	—Do— Semi Circular Arch work with chunam above doors and windows	4 8	142	5 4
247 57/100	Squares of plastering for walls with 2 coats of chunam	3	742	12 4
71 17¼/100	—Do— of flooring with 1 brick course & 3" thick brick jelly & chunam & well rubbed	4	284	11
4 7¼/27	C.yds. of cut stone & chunam work for flooring to entrance and portion of Verandah	18	76	13 4
49 69/100	Sqrs. of terrace work with brick on edge jelly 3" thick & 3 courses flat tiles & 3 coats chunam including wood work complete	60	2981	6 4
19 9/100	Sqrs. of sloping terrace to verandah with Palmirah rafters and reepers 3 courses of flat tiles and 3 coats of chunam	28	534	8 4
	Carried over		9172	6 10

5-Division D.P.W.

Salem District

Erskine Retaining.

D.P.W.25/67

Abstract of estimate for constructing an Out Patients Accomodation Shed in the Compound of Taluq Cutcherry at Namacaram.

Copy of Contractor's Estimate

Quantity	Description	Rate	Amount	Total
	Brought forward		9172 6 10	
210 2/27	Rg yds of cornice work	1 " "	210 1 2	
5	Breastsummers 10½X¾X½ each	10 " "	50 " "	
4	〃 10 X¾X½	9 8 "	35 " "	
2	〃 9½X¾X½	9 " "	18 " "	
8	〃 8 X¾X½	8 8 "	65 " "	
10	〃 7½X¾X½	8 " "	80 " "	
1	Front gate door with frame 11X5½ complete with teak wood having 3 pieces of plank diagonally screwed over it	60 " "	60 " "	
8	Frames with door complete 3½X7	27 " "	216 " "	
6	〃 with Iron bar doors complete for Prisoners & Treasury rooms 3½X7	40 " "	240 " "	
24	Windows with frames complete with Iron bars 3X5½ @	25 " "	600 " "	
8	〃 for Lock up with interior Iron linning with wooden frame	25 " "	200 " "	
2	Ventilators with interior Iron linning with wooden frame and for Treasury 1X3	8 " "	16 " "	
350	Rg yds ft in of wooden railing to be fixed to separate subsidiary jail and Cutcherry including gateway	" 5 "	175 " "	
1	Ladder with jungle wood sides plank fixed 14X1½	25 " "	25 " "	
1	Well complete 6 ft in diametre	100 " "	100 " "	
1291	C yds of Earth work for excavating foundation hard & easy soil	" 2 "	161 6 "	
	Scaffolding & sundries @ 5 per cent		1142 9 14 "	
	Total		570 2 "	12,000 " "

Quantity	Description	Rate	Amount	Total
	Brought forward			12,000 " "
	Abstract of a shed for Pyots and others with Pillars 37½X16½ Sq ft			
75 15/27	C yds of Rough stone in Chunam for foundation	2 8 "	188 14 2	
25 15¾/27	〃 of brick in chunam	4 " "	102 5 4	
10 45/100	Roofing with palmirah rafters across bamboo mats tiles Chunam borders &c	18 " "	188 1 7	
6 10¾/100	Sq ft of flooring with 1 course bricks and brick jelly & Chunam 3" thick well rubbed	4 " "	24 12 "	
9 30/100	〃 of rough plastering including white washing to base ment and pillars	2 " "	18 9 7	
17	Palmirah breastsummers for Verandah double joining	2 8 "	42 8 "	
160	C yds of excavating foundation hard and easy soil	" 2 "	20 " "	
			585 2 8	
	Sundries including Scaffolding &c @ 5 per cent		24 13 4	
	Total			610 " "
	Abstract of a Shed for Cutcherry Servants 15½ X 11 Sq ft			
		2 8 "	112 10 6	
45 5/16	C yds rough stone in chunam	4 " "	126 15 1	
31 5-3/72	〃 Brick in Chunam			
2 52/100	Sq ft roofing with Palmirah rafters across bamboo mats & tiles & Chunam borders &c	18 " "	45 5 9	
1 58/100	〃 of flooring jelly & Chunam 3" thick well rubbed	4 " "	6 3 10	
	Carried over		291 3 2	12,610 " "

Superintg. Engrs. Office 5th Division
Bangalore 31st August 1866.

No. 93.

From

Quantity	Description	Rate	Amount	Total
	Brought forward		291 3 2	2610 " "
10 3/4	Sqrs. of rough plastering including white-washing for walls	2 . .	21 8 .	
100	C.yds. excavating foundation hard and easy soil	" 2 .	12 8 .	
			325 3 2	
	Sundries including scoffolding &c. @ 5-%		14 12 10	
	Total			340 . "
	Abstract for open Latrine for Prisoners 18½ x 16 Sqrs.			
47 24/48	C.yds. rough stone in chunam	2 8 .	113 . 2	
33	Do- brick in chunam work	4 . .	132 . .	
15 27/100	Sqrs. of 1 coat plastering and white-washing	2 . .	30 8 7	
2 16/100	Do- for flooring with brick jelly and chunam 3 thick well rubbed	4 . .	8 10 3	
116	C.yds. of excavating foundation hard and easy soil	. 2 "	14 8 "	
			304 11 .	
	Sundries including scoffolding @ 5-per cent		15- 5 .	
	Total			320 " "
	Compensation for Land		100 " .	100 " "
	Grand Total			3370 . "

Rupees Thirteen thousand three hundred and seventy only.

Superintg. Engineer's Office
Bangalore 4th August 1866

Ill and Sundt. Cod. 1866.
Superintg. Engineer 5th Div.

A. Rathmell
Collector of Salem.

5th Division D. P. W.

Salem District

Attur Range

No. W 3625/65.

Abstract Estimate for Constructing a New Taluq Cutcherry with terraced roof according to Standard Plan at Namacul in the Namacul Taluq.

Amount of Estimate Rs. 13370

Superintg. Engr's Office 5th Division
Bangalore 31st August 1866.

No. 93.

From,

The Superintending Engineer
5th Division.

To

The Secretary to Government
D. P. W.

Sir,

Enclosures.
2 Plans.
2 Abstract Estimate
2 Specifications
2 Site plans.

As called for in G.O. No. 327 of the 4th of February 1865, I have the honor to submit for sanction plans and estimates for the undermentioned buildings in the District of Salem.

Constructing a Taluq Cutcherry at Namakkal Estimate Rs. 13,370 — —

Constructing a Sub Magistrates Cutcherry at Rasipuram. Estimate Rs. 3380 — —

2- The design for the Taluq Cutcherry is in accordance with the Standard plan and that for the Sub Magistrate was prepared in communication with the District Magistrate and the Superintendent of Police; and both the plans have been approved by the former.

I have the honor to be
Sir
Your most obdt. Servt.

E H Ford Lt. Col. R.E.
Superintg. Engineer

X
13

Public Works Department.

?

No. 2881

PROCEEDINGS of the MADRAS GOVERNMENT
Under date the 10th Sept/66
Read the following

From the Supt. Engineer of
the 5th Division - (Here enter No. 73 dated 31 Aug 1866)

The estimates submitted under this letter for a Talug Cutcherry at Ramakal and for a Sub Magistrates Cutcherry at Pennagaram in the Salem District are sanctioned; but as there is no probability of funds being available for advances at the commencement of the works during the current official year, the Supt. Engineer of the 5th Div. is requested to enter the estimates

To SE 5th Div with the two letters & plans
To Cuddalore two specifications
to CE
To Record

Supt. 11 Sept 66

On Bill Stamp Rs. 1 Paper for Estimates from the Superintending Engineer 5th Division.

To The Secretary to Government P.W.D.

Dated 31st Aug 1866. Received 4th Sept 1866.

No. 73.

Enclosures 8.

2 Plans Specifications Estimates

Forwarding for sanction Plans and Estimates for constructing a Talug Cutchery with Ramakal Choultry & Sub Magistrates Cutchery with Choultry at Pennagaram in the Salem District.

Ans. 2881 - 10th Sept 66.

No. 223

Ent. 9th Sept 66

ni his Budget for
1867 68

P. W. 1866. Department.

Bo. of Genl for September

No. 2891

PROCEEDINGS OF GOVERNMENT. February

Dated 10th Septr 1866.

An estimate of Rs 1,33,700 for the construction of 2 plug Cut. Sluices at Kannathil in the Salem Collectorate.

A 223. 224.

5th Septr/66 D. 6th