

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

DEPARTMENT.

G.O. No. _____	Press Mis. _____
Dated _____ 18 _____	

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
19th September 1866.*

No. 506.

Dated 19th September 1866, No. 3,014.

CIVIL WORKS, No. 95.

Funds having now been placed at the disposal of Government for appropriation to the construction of the

Central Jail which it is proposed should be erected at Vellore, it is desirable that no time should be lost in making a commencement of the work. The Superintending Engineer will therefore hasten the submission of the plans and estimates of the building.

2. As it is desirable that the Jail should be completed as economically as possible, the Government consider that, with the exception of the foundations throughout, and of the Hospital, Store and Office, and the Wards, as also the entrances, the building may be of brick in mud. For the enclosure wall, strong piers of brick or stone in mortar may be built at intervals of twelve or fifteen feet, and the interspaces filled up with a wall of sun-dried brick in clay. The Government are of opinion that considerable saving may probably be made in roofing and palisading, if the latter be entirely constructed of palmyra, and only the trusses and brestsummers of the former of teak, the rafters, the joists and the couples of all the buildings being of palmyra, or of jungle wood if the latter be procurable of tolerable quality at a cheap rate.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,

Secretary to Government.

To the Superintending Engineer, 4th Division.
" Judicial Department.

Exd. T. O'Connor.

Ch. J. J. J.
Public Works Department.

No. 3014

PROCEEDINGS of the MADRAS GOVERNMENT.

Under date the 19th Sept. 1866.

Read the following

(Here enter No.

186 .)

N.
IP
W
Funds having now
been placed at the dis-
posal of Government
for appropriation to the
construction of the Cen-
tral Jail which it is
proposed should be erected
at Vellore, it is desirable
that no time should be
lost in making a com-
mencement of the work.
The Supg Engineer will
therefore hasten the
submission of the plans
and

and estimates of the building)

2. As it is deemed that the Jail should be completed as economically as possible, the Govt. considers that, with the exception of the foundations throughout the hospital, store and Office, and the wards, as also the entrance, the building may be of brick in mud. For the enclosure wall, strong piles of brick or stone in mortar may be built at intervals of 12 or 15 feet, and the inter-spaces filled up with a wall of sun dried bricks.

brick in clay. The Govt are of opinion that considerable saving may probably be made in roofings and palling, if the latter be entirely constructed of palmyra, and only the trusses and beams of the former of teak, the rafters, the joists and the couples of all the buildings being of palmyra, or of jungle wood, if the latter be procurable of tolerable quality at

76
The S. Neg 4th bn ✓
Judicial Dept ✓ a cheap rate.

Sept 19/9/86

AB

O 21 1866 Depo-
Pro. of Gov. for Sept

A 3014

Pro of the Madras Court
Df 12 September 1866.

Certain instruc-
tions issued relative to the
carriage, preparation of
plans and estimates, &c.
for the construction of
Central Jail at Vellore

A 506.