MRO 1—77,006—8-6-37.

(1) Number of pages 6

(2) Date of repair 23-2-43

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 3248 Press ~~Mis.~~

276—277

Dated 12—10— 1866.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 12th October 1866.

No. 276. Read the following letter from the Superintending Engineer, 6th Division, to the Secretary to Government, Department Public Works, dated Tanjore, 1st October 1866, No. 788 .—

I have the honor to submit, for the approval of Government, the enclosed estimate of Rupees 150, for suspending a bell in the grand gate of the Arsenal in the Fort of Trichinopoly. The estimate has received the approval of His Excellency the Commander-in-Chief; provision may be made for the work from the allotment for Minor New Works under the head "Military."

Enclosure 1.

No. 277. ORDER THEREON, 12th October 1866, No. 3,248.

MILITARY WORKS, No. 12.

The estimate is sanctioned.

(True Extract.)

Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 6th Division.
" Accountant General.
" Controller of Public Works Accounts.
" Military Department.

Exd. S. T. Augustin.

Military. Ordnance.

Trichinopoly Division. Minor Irrn Works

Abstract Estimate No. 1866/67. 13

Work.— Constructing a frame Work for suspending a Bell on the Grand gate of the Arsenal in the Fort at Trichinopoly with Sound Countrywood and Well Tarred.

Quantity	Description of Work.	Rate	Amount	Amount of Each Spl.
36 13/16	Cft. of sound Country wood @	2 4	82 13 3	
1.	Teakwood Wheel 3-5 in diameter 4" thick with Iron Clamps complete	15	15	
1.	Large Iron cross Bar	"	4	
2.	Small Bars for Support @	1	2	
2.	Sets of Iron Nails @	" 8	1	
1.	Iron Axle tree	" "	5	
	Iron Works complete Iron nuts &c.	" "	12	
102.	Cft. of Brick in Mortar	" 2	12	12
1.	Cottah Rope	" "	"	12
	Tarring Countrywood Work		3	
	Scaffolding Sundries & Contingencies		11	10 9
			Total Estimate Rupees	150

Trichinopoly.
Exd. 1 Ranger Office
11th September 1866.

Supg. Engineer's Office 6th Dec.
January Octr. 1866

1st Sept. J. Greenaway Lieut.-Col.
Executive Engineer
Trichinopoly.

Captain R.E.
Supg. Engineer 6th Division

No 788

Sir,

Captain R. H. Clarke R.E.
Superintending Engineer 6th Div.

Sir,

I have the honour to submit for the approval of Government the accompanying Estimate of the expenditure required for erecting a Bell on the Arsenal Gate of the Fort at Fredericktown, the Work proposed to be executed by Military Artificers.

I have the honour to be
Sir
Your most obt Servant
W. F. Drummond Captain R.E.
Supt Engineer 6th Division

Enclosure No 1 —
in a letter from the
Supt Engineer 6th Div.
to the Secretary to
Government No 788
of the 1st October 66.

P.W. 407/66
12 Oct 66

Abstract Estimate for
Constructing a frame
work for suspending
a Bell on the front
gate of the Arsenal
in the Fort at Fredericktown —
From 12th October 1866 No 276.

Dept. 1866 Despatch
From Govt. of India October
No. 4071

The Supt. Engr
6th Div.

To

The Secretary to
Government
P.W.D.

Dated 9th
Received 13th October
1866.

Letter No. 788-

Ca: one
exo. 3248. 12th Octr/66
Submits for
Approval Estimate
amtg. to Rs. 150
for putting up
a Bell at the
Arsenal at
Trichinopoly
with a view

exd. 3248

The estimate is
sanctioned -

Wm

Stuart St George
12th Octr/66

6 Wasers
3 " Lascars
4 " Controller
1 " Mug. Dept.

Dept. 13th October

No. 276. 277

Dept. 8th Octr. 1866 R-16th