M R O 1—77,006—8-6-37.

(1) Number of pages 6

(2) Date of repair

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 3257 Press Mis.

295-296

Dated 12-6- 1865.

Not to be folded or roughly handled

17

Proceedings of the Madras Government, Public Works Department,
12th October 1866.

No. 295. Read the following letter from the Acting Superintending Engineer, 1st Division, to the Secretary to Government, Public Works Department, dated Waltair, 26th September 1866, No. 133 :—

1. I have the honor to enclose plan and estimate for an Apothecary's quarter at Parvatipoor ; the building is much needed, as it is proposed to fill the new Jail as speedily as possible by the removal of Convicts from Vizagapatam Jail, hill-men whose health has suffered by being brought to the coast.

1 Plan.
1 Estimate.

2. If the Government cannot furnish funds for the immediate construction of the building, I beg sanction for its entry in the Budget of 1867-68.

No. 296. ORDER THEREON, 12th October 1866, No. 3,257.

CIVIL WORKS, No. 57.

The Government sanction for entry in the Budget of 1867-68, the estimate of Rupees 2,770 submitted with this letter for quarters for an Apothecary at Parvatipoor in the Vizagapatam District.

(True Extract.)

Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 1st Division.
,, Controller of Public Works Accounts.
,, Accountant General.
,, Judicial Department.
,. Inspector General of Police.

Ed. S. T. Augustin.

2 qts Green paint 3 Coats to Doors & Bs

Vizagapatam District

Abstract Estimate No of 1865/66

Work — Constructing Quarters for Assistant Apothicary with out Offices proposed at Parvatipúr

Quantity	Description of Works.	Rate Per	Amount	Total
137 1/3	Cube Yards of Rough stone in Chunam	1 50	Cy.	179 13 3
152 1/9	Do of Brick work in Do	1 15.	Do	294 11 5
7. 2/9	Do of Arch work in Do over Doors	24.	Do	16 4.
25. 76/100	Squares of Roofing with Palmyra or Country wood Rafters, Reepers, Couples, Rails, Flat & pantiles & Chunam borders &c Complete	17	Sqrs.	437 14 8
66-0	Squares of Plastering with 2 Coats of Chunam & whitewashing	2 6.	Do	156 12.
16-0	Do of Flooring with brick on edge in Chunam and Levelling Course underneath & plastering	54.	Do	84 ..
72	Squarefeet of Paving with stone Slabs to the steps	12 ..	Sqr.	8 10 3
	Excavating foundations and filling in Basements	....		10 ..
89 11/36	Cft of Country wood wrought & put up	1 12.	Cft	156 4 6
10	Pairs of Country wood panelled & Venetian Doors with Frames &c Complete 7 1/2 × 4	27 12.	Each	277 8.
1	Do of Do Do 6 1/2 × 3 1/2	21 4.	Do	21 4.
7	Do of Country wood Venetian window Shutters with frames &c 5 × 3 1/2	16 4.	Do	113 12.
	4 Brass locks of 8 inch Complete	3 ..	Do	12 ..
15	Sqrs. Green paint 3 Coats to Doors & Windows	2 ..	Sqr	30 ..
20	Do Applying 2 Coats Tar to the Reepers &c	1 ..	Do	20 ..
	Contingencies at 10 .. Pct.			181 11 2,000

Brought Over ——— 2,000

Cook Room & Godowns

48 1/2	Cft	of Rough stone in Chunam	1 5	Cft	63 106
71 1/27	-Do-	of Brick in Chunam	1 15	Do	137 102
2 1/27	-Do-	of Flat Arches	24	Do	4 94
1.2/9	-Do-	of Circular Arches	3	Do	3 108
29	Cft	of Cornice work	26	Cft	4 86
8.70/100	Sqrs	of Roofing with Palmyra or Country wood Rafters, Reepers, Nails, Flat and pantiles and Chunam borders &c Complete	15	Sqr	1308
25	Sqrs	Plastering with 2 Coats of Chunam & whitewashing	26	Sqr	59 6
3 4/10	-Do-	of Flooring with brick on Edge in Chunam & Levelling Course under neath	54	Do	17 138
		Erecting a Masonry Togong			10
		Excavating foundations & filling in Basement			6
8.7/10	Wall Plates of Country wood rough & unplaned		1 12	Cft	14 123
3	Pairs of Country wood Batten doors with frames &c Complete 6 1/2 x 3		159	Each	46 11
4	-Do- of -Do- Battened windows, Shutters and Iron bars with frames &c Complete 4 x 3		9 10	Do	38 8
		3 Iron padlocks with Key	1 8	Do	4 8
		Making one Ventilator over the roof			7
7	Sqrs	Applying 2 Coats tar to the reepers	1	Sqr	7
2 3/4	-Do-	Red paint 3 Coats to Doors & Windows	1 10	Do	4 76
		Contingencies	at 10	Rs	59 45
					620

Drains

10.23/27	Cft	Rough stone in Chunam	15	Cft	14 310
18.17/27	-Do-	Brick work in -Do-	1 15	Do	36 16
0.31/108	-Do-	-Do- Flat arch work	3	Do	0 139
13 1/2	Cft	of Cornice work	26	Cft	2 19
		Carried Over			53 410 2,620

Brought Over — 53 410 2,620

1.92/100	Sqrs	Roofing with Palmyra or Country wood Couples, Reepers, Nails, Flat and pantiles and Chunam borders &c	15	Sqr	28 420
7.3/10	-Do-	Plastering with 2 Coats Chunam & whitewashing	26	Do	22 15
83/100	-Do-	Flooring with Brick on Edge in Chunam and Levelling Course underneath	54	Do	4 58
2/2	-Do-	Applying tar, 2 Coats to the Couples & Reepers	1	Do	2 8
2 1/12	Cft	of Country wood wall plate	1 12	Cft	3 104
1	Pair of Batten door with frames &c with Country wood Complete 6 1/2 x 3		158	Each	15 8
1	Country wood necessary seat				5
		including Masonry work			1
6	Wooden bars for 3 Bulls Eyes				1
		Red paint 3 Coats			1 8
1	Iron pad lock				11 411
		Contingencies — at	10	Rs	150
		Total Rupees			2770

Captain R.E.

Superintending Engineer 1st Div

Superintending Engr's Office
1st Div. Vellore
5th April 1865

J.E. Tennent
Dy Insp Genl Police
N.R.

Chief Office of the Insp Genl of Police
Madras 23rd April 1866

Inspector General of the Police

Superintending Engineer's Office, 1st Div.
Waltair, 26th September 1866.

No 133
Dep 227

From Lieut. Colonel F. J. Moberly R.E.
Ag. Superintending Engineer 1st Div.

To
Colonel C. A. Orr R.E.
Secretary to Government, F.W.D.
Madras.

Encls 2. 1 Plan Estimate.

Sir,

I have the honor to enclose plan & estimate for an Apothecary's Quarter at Sar-=vatipur= the building is much needed as it is proposed to fill the new jail as speedily as possible by the removal of Convicts from Vizagapatam jail - till men whose health has suffered by being brought to the Coast.

2. If the Government cannot furnish funds for the immediate construction of the Building, I beg sanction for its entry in the Budget of 1867/68.

I have &c.

F. J. Moberly
Lieut. Col. R.E.
Ag. Superintending Engineer 1st Div.

Enclosure in a letter No 133 dated 26th September 1866 from the Agent Superintending Engineer 1st Div. to the Secretary to Government F.W.D.

Estimate for Sanitary Quarters for Apothecary with out Offices, Compound & Sanatorium.

Quantity to be 2770.

Ex. 12 "Civil" 1866 L. No 295.

Public Works Department.

No. 3257

PROCEEDINGS of the MADRAS GOVERNMENT.

Under date the 12th October 1866

Read the following

From The Acting Superintending Engineer of the 1st Division

(Here enter No. 133 dated 26th Sept. 1866.)

The Government sanction for outlay in the Budget of 1867/8, the estimate of Rs 27/0 submitted with this letter for Quarters for an Overseer at Vizagapatam in the Vizagapatam District

To The Dy
" Controller
" Acct Genl
" Judicial Depd
" Inspector Genl of Police

dispd 1st October

No. 133

Dated 26th Sept 1866

Rec'd 27th Sept 1866.

Enclo. 2

To The Secretary to Govt. P.W.D.

Sir,

I have the honor to submit herewith a Report, Estimate, Plan & Elevation for Quarters for an Overseer at Vizagapatam in the Vizagapatam District.

Forwarded Plan & Estimate = mate for an Overseers = ters at Vizagapatam to be built at the Executive Engineer at the Vizagapatam Dist. in the Vizagapatam Dist.

No. 3257 - 12 Oct 1866

C. 8th Oct 1866 R. 16th

P. W. 1866 Depart.t

Nos of Govt. for Oct.r 1866

No 3267

Ex.o of the Madras Govt.

Dated 12th October 1866

The estimate of Rupees 2770 for the construction of Quarters for an Apothecary in the Vizagapatam District Sanctioned for entry in the Budget of 1867-68.

No 295.296

e. 8th Dec.r 1866 R. 10th