

T.M.O

(1) Number of pages 20(2) Date of repair 9-3-43

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public works DEPARTMENT.

G.O. No. <u>3901</u>	Press Mis.
<u>162-163</u>	
Dated <u>11-12-</u>	<u>1866.</u>

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
11th December 1866.*

No. 162. Read the following letter from the Collector of South Arcot, to the Secretary to Government, Public Works Department, dated Cuddalore, 3rd December 1866, No. 65 :—

At the request of Colonel Foord, the Superintending Engineer, 5th Division, I have the honor to forward, duly countersigned by me, the accompanying plans and estimates for re-opening the Amoor channel, a branch of the Ragavien, and which is likely to prove a remunerative work, and, in concurrence with Colonel Foord, I therefore solicit the sanction of Government for the proposed outlay, which I presume may find a place in the Budget of the next official year.

No. 163. ORDER THEREON, 11th December 1866, No. 3,901.

CIVIL WORKS, No. 33.

1. With this letter the Collector of South Arcot submits an estimate amounting to Rupees 8,830 for the improvement of an existing channel from the Ragavien channel to the Poodoopoliem tanks, and for re-opening, in continuation of it, the old Amoor channel in the South Arcot District.

2. From the papers submitted by the Collector, the Government note that the proposed works will not only ensure the irrigation of existing lands, but will bring under cultivation 357 Cawnies of Nunjah land which are now lying waste, and admit of 475 Cawnies of dry land being converted into wet. The return expected from the work is Rupees 3,636 per annum, being upwards of 40 per cent. on the outlay.

3. Under these circumstances, the Governor in Council sanctions the estimate for entry in the outgoing Budget.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 5th Division, with one Specification and one Survey.

- .. Accountant General.
- .. Controller of Public Works Accounts.
- .. Collector of South Arcot.

Ed. S. T. Augustin.

Detailed Estimate No. of 1866/67.

South Arcot District. Clavanadur Taluk.

Work—Improving the existing channel from the Pagavien main channel to the Poodopaliam Tanks, and in continuation re-opening up the old Amoor channel, for the irrigation of the lands in the villages of Poodopaliam, Paliagarum, Amoor, Ottamundul, Konalavady, Tennavalum, Vatur, Tholungumput, Kaschiput, Kolathoor, Manacoofum, Chundam, &c.

Particulars of work	Measurement in feet			Cubical contents
	Length	Breadth	Depth	
<u>Earthwork</u>				
From Head Sluice on the South bank of the Pagavien channel				
Widening Channel	300	6	7 $\frac{1}{4}$	13050
Do	270	6	3 $\frac{1}{4}$	5265
Do	2018	6	6 $\frac{1}{4}$	75675
Do	1380	6	5 $\frac{1}{4}$	43470
Do	855	6	3 $\frac{1}{4}$	16672 $\frac{1}{2}$
Do	775	6	5 $\frac{1}{2}$	25575
Do	2280	6	2	27360
Do	800	7 $\frac{1}{2}$	1 $\frac{1}{4}$	7500
Do	2330	9	2 $\frac{1}{4}$	47182 $\frac{1}{2}$
Do	936	9	1 $\frac{1}{2}$	12636
Do - up to Head Sluice for the Poodopaliam tanks	880	9	3	23760
Cutting channel	585	15	3	26325
Do	666	15 $\frac{1}{2}$	3 $\frac{1}{2}$	36130 $\frac{1}{2}$
Do	774	15 $\frac{3}{4}$	3 $\frac{3}{4}$	45714 $\frac{3}{8}$
Do	980	16 $\frac{1}{2}$	4 $\frac{1}{2}$	72765
Carried over				479080 $\frac{1}{2}$

Brought forward—				479080/8
Cutting Channel—	585	17	5	49725
Do	552	17 1/4	5 1/4	49990 1/2
Do	450	18	6	48600
Do	810	18 3/4	6 3/4	102515 3/8
Do	540	18 1/4	6 1/4	61593 3/8
Do	760	17 3/4	5 3/4	77567 1/2
Do	700	18 1/2	6 1/2	84175
Do	980	19 3/4	7 3/4	150001 1/4
Do	880	21 1/4	9 1/4	172975
Do	720	22	10	158400
Do	900	21 1/2	9 1/2	183825
Do	720	20 1/4	8 1/4	120285
Do	1418	19	7	188594
Do	1170	18 3/4	6 3/4	148078 1/8
Do	558	18 1/2	6 1/2	67094 1/2
Do	603	17 1/2	5 1/2	58038 3/4
Do	459	17 1/4	5 1/4	41568 3/16
Do	605	18	6	65340
Do	1180	18 1/2	6 1/2	141895
Do	846	18 1/4	6 1/4	96496 7/8
Do	620	17 1/2	5 1/2	59675
Do	666	16 1/2	4 1/2	49450 1/2
Do	855	16	4	54720
Do	666	15 1/4	3 1/4	33008 5/8
Do	648	14 1/2	2 1/2	23490
Do	504	14 3/4	2 3/4	20443 1/2
Do	378	15 1/4	3 1/4	18734 5/8
Do	747	15 3/4	3 3/4	44119 1/16
Do	306	15 1/2	3 1/2	16600 1/2
Do	342	15 1/4	3 1/4	16950 3/8
Do	360	15	3	16200
Do	548	14 3/4	2 3/4	22228 1/4

Brought forward—				2921466
Cutting Channel—	280	15 1/4	3 1/4	13877 1/2
Do	333	15 1/2	3 1/2	18065 1/4
Do	333	16	4	21312
Do	594	17	5	50490
Do	261	16 1/2	4 1/2	19379 1/4
Do	342	15	3	15390
Do	324	14 1/2	2 1/2	11745
Do	675	15 3/4	3 3/4	39867 3/8
Do	360	15 1/2	3 1/2	19530
Do	315	15 3/4	3 3/4	18604 1/16
Do	270	15 1/2	3 1/2	14647 1/2
Do	280	15 3/4	3 3/4	16537 1/2
Do	162	16 3/4	4 3/4	12889 7/8
Do	414	16	4	26496
Do	775	14 3/4	2 3/4	31435 5/16
Do	387	14 1/2	2 1/2	14028 3/4
Do	468	14	2	13104
Do	423	13 1/4	1 1/4	7005 5/16
Do up to Amos Bank—	826	13	1	10738

Total cubic feet— 3296609 3/8

or Do yards— 122096 5/8

Collector of South Arcot Abstract

Quantity	Description of work	Rate	Amount	Total
122096	Cubic yards of Earth work—	per Cyd . . .	7631 . . .	7631 . . .

3^d Range Office South Arcot. Total of Estimate Rupees— 7631 . . .

For Mian Amicus

10th November 1866

Charles Danks

Superintending Engineer 3^d Range South Arcot.

Agricultural

Original Work

Detailed Estimate No. of 1866/67.

South Arcot District. Ellavanasur Taluk

Work — Constructing a Head Sluice on the ^{bank of the} Poodopolium and Anoor Channel for the Poodopolium Tanks.

Particulars of Work.

Measurement in feet
L B H. Cubical Content

Foundation to front wall and abutments	43	3 1/2	3	451 1/2
— 1/2 — to wing walls —	18	3 1/2	3	175 1/2
— 1/2 — to rear portion of wing walls —	10	3	3	90
— 1/2 — to Retaining wall —	9 1/2	2	4 1/2	85 1/2
— 1/2 — to flooring to Apron —	8 1/2	5	1 1/2	63 3/4
— 1/2 — to — 1/2 —	9	7 1/4	1 1/2	97 7/8
— 1/2 — to — 1/2 —	2 1/2	9 1/2	1 1/2	35 5/8
Superstructure to front wall and abutment	35 1/2	2	6	426
— 1/2 — — 1/2 —	17	2	3	102
Arch —	8	10	1 1/2	120
Covering to — 1/2 —	10	1/2	1	5
Packing to — 1/2 —	11	1/2	3	16 1/2
— 1/2 —	11	1 3/4	3	57 3/4
Parapets —	46	1 1/2	2	138
Wing walls —	18	2 1/4	6	243
— 1/2 —	18	1 1/2	1 3/4	47 1/4
Rear portion of wing walls —	10	1 3/4	6	105

Total Cubic feet — 2260 1/2
or Cubic yards — 83 2/3

Abstract of the Estimate.

Quantity	Description of work	Rate	Amount	Total
83 2/3	Qty of Briets in channel work —	Pls: 3	257	
6	600 lbs Stones —	each 38	21	
	Carried over —		272	

South Arcot District

No. 3 Range

Detailed Estimate No. 1866/67

No 4903/66

Work — Improving the existing channel from the Vengal main channel to the Vengal tank, and in continuation re-opening up the old Anoor channel

Amount of Estimate Rs 1631-0-0

Abstract of the Estimate

Quantity	Description of work	Rate	Amount	Total
138	by 7 of 1 Brick in Chunnawwatto	Plg 3. . .	414 . .	
12	large Stones	each 3 8 .	42 . .	
2	Sill Stones	" 3 8 .	7 . .	
2	Leak wood Shutters	" 15 . .	30 . .	
	Excavating foundation		11 . .	
	Scaffolding and Sundries		16 . .	520 . .

Total of Estimate / Refus — 520 . .

3rd / Range Office South Arcot
 Ponnies Amicul 10th November
 1866
Charles Le
 Collector of South Arcot.

Mr. J. V. A. S. S. S.
 Sub-Engineer No 3 Range
 South Arcot
 E. M. J. M. S. S. S. S.
 Superintending Engineer

Amount of Estimate Rs 520.00

on the south bank of the
 Ragavie Channel at the head
 of the Pooderpalin and Chunnaw
 Channel.

No 49 83/61

Detailed Estimate No 49 83/61

No III Range

South Arcot District

Statement showing the amount of increase of revenue that will be realized by improving the old channel which branches from Ragavie Channel and supplies the Amoon & Villages.

Names of Villages	Amoon	Ottamundab	Vadakkonavaladi	Ponnaralund	Velur	Thulur	Thashepett	Thallathur	Wunthuppur	Elanthur	Total	Remarks
Amoon	71										500	1001 7
Ottamundab		7									150	227 7 10
Vadakkonavaladi			11								200	353 11
Ponnaralund				5							150	260 10
Velur											500	567 8
Thulur											500	635
Thashepett											50	50
Thallathur											100	162 8
Wunthuppur											100	217 13
Elanthur											125	125
Total	97 8 1	7 10 6 9	260	550 10	475	2375	3636	9				
Total Ponnaralund including Ponnaralund Ponnaralund Ponnaralund Ponnaralund Ponnaralund Ponnaralund Ponnaralund Ponnaralund Ponnaralund Ponnaralund Ponnaralund Ponnaralund												3636 9

24th October 1866.

Charles Le
 Collector

E. M. J. M. S. S. S. S.
 Superintending Engineer

Mr. J. V. A. S. S. S.
 Sub-Engineer No 3 Range
 South Arcot

Agricultural

Original work

Abstract Estimate No. of 1866/67

South Arcot District. Ellavanasur Taluk

Work — Improving the existing channel from the Pagavien main channel to the Poodospochem Tanks, and in continuation re-opening up the old Amoor channel, for the irrigation of the lands in the villages of Poodospochem, Paliagarum, Amoor, Ottanundul, Konalawady, Pennavallum, Valur, Tholingumpul, Kesthipul, Kolathur, Moosopum, Elunderay &c, constructing 2 Head Sluices & improving 2 Road tunnels —

Quantity	Description of work	Rate	Amount each part	Amount
<u>Earthwork to channel</u>				
122096	122096 cu yds of Earthwork — per cu yd. 1. 7631			7631
	Total Earthwork			7631
<u>Head Sluice of 2 vents</u>				
138	138 cu yds of Brick in chunam work — per cu yd. 3. 414			414
12	12 Cross stones — Each 3 8. 42			42
2	2 Sill stones — Do. 3 8. 7			7
2	2 Oak wood shutters — Do. 15. 30			30
	Excavating foundation —			11
	Scaffolding and Sundries —			16
	Total			520
<u>Head Sluice of 1 vent</u>				
83 2/3	83 2/3 cu yds of Brick in chunam work — per cu yd. 3. 251			251
6	6 Cross stones — Each 3 8. 21			21
1	1 Sill stone —			3 8.
1	1 Oak wood shutter —			15
	Excavating foundation —			6
	Scaffolding and Sundries —			13 8.
	Total			310
	Carried over			8461

8461

Statement showing the amount of increase of revenue that will be realized by improving the old channel & which branches from Pagavien channel must supplies the hungry villages —

and 3 more

Brought forward — 8461 " "

Improving Two Road Tunnels under which the channel has to be conveyed — 339 " "

3^d Range Office South Arcot }
 Ponnies Annicut 10th } Total improvement to Tunnels — 339 " "
 Nov sub-ss 1866 } Total of Estimate Rupees — 8800 " "

Rupees eight thousand and eight hundred only thirty

Approved
 Sub Engineer N. 3 Range South Arcot

Charles de la Roche
 Collector of South Arcot

E. A. Ford South Arcot
 Superintending Engineer

South Arcot District
 No 483/64
 N. 3 Range

Madat Estimate No. of 1866

Work — Improving the existing channel from the Paganin main channel to the west of the Vanki, and in continuation to opening up the old Annemiam mel, constructing 2 Road offices and improving 2 Road Tunnels.

Amount of Estimate Rs. 8800-0

No 65

From Charles H. Read Esq.
 M. A. of South Arcot

To Colonel C. A. Orr B. E.
 Secretary to Government
 Public Works Dept.
 Fort St. George

Sir,

At the request of Colonel Ford the Superintending Engineer 5th Division, I have the honor to forward duly countersigned by me the accompanying Plans & Estimates for re-opening the Annam channel a branch of the Paganin which is likely to prove a remunerative work, in concurrence with Colonel Ford, I therefore solicit the sanction of Govt. for the proposed outlay which I presume may find a place in the Budget of the next financial year.

I have the honor to be, Sir, your most Obedt Servant

Charles de la Roche
 Collector

South Arcot
 10th Dec 1866


114-8802-1866-101-114

South Coast District

2. From the papers submitted by the Collector, the Government note that the proposed works will not only ensure the irrigation of existing lands, but will bring under cultivation 275.357 Acres of Vunjah Land which are now lying waste, and admit of 475 Acres of dry land being converted into wet. The return expected from the work is Rs 3,036 per annum, bringing a surplus of 40 per cent

on the outlay.

Under these circumstances, the Governor in Council sanctions the Estimate for entry in the outgoing budget.



The S. Engr. Sth Div. with one specific & one survey
" Accts Genl
" Controller P. R.
" Accounts
" Coll of Santa Lucia
Sept 17th December 1866

M. S. despatched to S. Engr 5th Div
11-12-66

S. C. with one survey & one specific despatched to the S. Engr 5th Div
17th Dec 1866

Little Mark 1868 10/12/10

1890

View of the Machine from

October 11 - December 1868

No 162-163