

(1) Number of pages 14
(2) Date of repair 12-3-43
(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. <i>4023,</i> <i>425-426.</i>	Press Mis.
Dated <i>20-12-</i> 18 <i>66.</i>	

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
20th December 1866.*

No. 425. Read the following letter from the Executive Engineer in charge of Superintending Engineer's Office, 8th Division, to the Secretary to Government, Department Public Works, dated Madura, 5th December 1866, No. 1,525 :—

1 Revised Estimate.
1 Comparative Statement.

1. I have the honor to forward a comparative Statement and a revised Estimate, amounting to Rupees 2,080,

for constructing a new Police Station-house attached to the Taluq Cutcherry at Dindigul, 2nd Range, Madura District, and to state that the original estimate of Rupees 1,800 for this work was framed in December 1864, by the then Range Officer Lieutenant W. Coningham, and sanctioned by Government in their Proceedings No. 1,750, dated 23rd June 1865.

2. The difference between the original and revised estimates, viz., Rs. 280, is principally owing to the rise in cost which has taken place in prices of labor and material since the date of preparation of the estimate in 1864. There is also an increase arising from an error in the original estimate, wherein the number of square feet in the roofing was incorrectly stated.

No. 426. ORDER THEREON, 20th December 1866, No. 4,023.

CIVIL WORKS, No. 83.

Under the explanation afforded, the revised estimate of Rupees 2,080, submitted with this letter, for the

construction of a new Police Station in connection with the Taluq Cutcherry at Dindigul in the Madura District is sanctioned.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 8th Division,
,, Accountant General.
,, Controller of Public Works Accounts.
,, Inspector General of Police.
,, Judicial Department.

Ed. S. T. Augustin.

Comparative Statement showing the difference between the Original and Revised Estimates for Constructing Police Station House attached to proposed bazaar at Dindigul.

Description of work	Per	Original Estimate			Revised Estimate			Differences	
		Quantity	Rate	Amount	Quantity	Rate	Amount	Increased	Decreased
								Amount	Amount
Removing roof from north end of building	Sq ^{re}	10 ² / ₂₅	12	7 9	10 ² / ₂₅	12	7 9		
Roofing to main building with country wood rafters Colar beams bamboo rafters, flat & pan tiles & nails &c. Complete	do	15 ²⁴ / ₂₅	27	242 14 3	17 ⁹⁵⁴ / ₁₀₀	29 ¹² / ₁₀₀	498 4	55	59
Roofing to Verandah with flat & pan tiles country wood rafters bamboo rafters &c. do	do	11 ³ / ₄	21	246 12	12 ² / ₂	21	262 8	15	12
Breastworks to country wood	do	46 ¹¹ / ₁₈	2	93 3	46 ⁸³⁴ / ₁₀₀	2	93 2 7		
Removing walling	do	39 ¹ / ₂	6	14 11 6	39 ¹ / ₄	6	14 11 6		
Rough stone in Chinnam	do	98 ¹ / ₈	1	171 11 6	98 ¹ / ₈	2	220 12 6	49	1
Rough stone in mud	do	99 ³ / ₄	1	124 11	99 ³ / ₄	1	174 9	49	14
Brick in mud	do	15 ¹¹ / ₁₀₀	2	33 14 3	15 ³⁶ / ₁₀₀	3	49 6 1	15	7 10
Brick in Chinnam	do	27 ⁷ / ₈	3	83 10	31 ⁷ / ₈	4	127 8	43	14
Pillars 3 1/2 x 1 1/2 ft diameter including 3 stones	Set ft	40 ¹ / ₂	1	40 8	40 ¹ / ₂	1	40 8		
Pillars 12 x 1 1/2 ft do inclusive top footing and bond stones. Plaster	do	81	15	75 15	81	15	75 15		
Plastering with 2 coats of Chinnam	Sq ^{re}	46 ³ / ₈	2	104 5 6	46 ³ / ₈	2	115 15	11	9 6
Paving with 8" Sq Bricks and levelling concrete beneath	do	16 ⁸⁷ / ₁₀₀	6	109 10 6	16 ⁸⁷ / ₁₀₀	7	118 1 5	8	6 11
Doors Vangay wood with 7 Iron bars and Shutter &c. Complete	do	3	23	69	3	23	69		
Batten Door Complete	do	1	16	16	1	16	16		
Windows with 8 Iron bars & Shutter &c. Complete Vangay wood	do	3	18	54	3	18	54		
do Batten Shutter Vangay wood Complete	do	2	13	26	2	13	26		
Excavating foundation & Sandries				85 7 11			116 1 11	30	10
				1800			2080	280	1
							1800		
							280		

Deduct Amount already sanctioned

Amount to be sanctioned

2nd Range Office
Periacolum
15th November 1866

R. G. P. Payne Captain
C. S. P. Payne Ch. Secy. Dindigul
Office 8th Decr

R. G. P. Payne
Asst. Executive Engineer
C.E.

Civil Building.

New work

Abstract Estimate No. of 1866-67

District Madura Taher Pindigul

Work Constructing a new Police Station House attached
to proposed butchery in Dindigul —

Quantity	Description of work	Rate	Amount	Total
10 ² / ₂₅	Square Removing roof from south end of building — at	12	7 9	-
17 ⁹⁵ / ₁₀₀	- D ^o - Roofing to main building with country wood, rafters, Colar beams, bamboo piers, flat & pan tiles nails &c. Complete — at	27 12	498 4	-
12 ¹ / ₂	- D ^o - Roofing to Verandah with flat & pan tiles, country wood, rafters, bam- boo piers &c. Complete — at	21	262 8	-
46 ³² / ₁₀₀	6 ¹ / ₂ feet Broomsticks &c. Country wood at	2	93 2 7	-
39 ¹ / ₄	C ^o yards Removing wall — at	6	14 11 8	-
98 ¹ / ₈	- D ^o - Rough stone in Chumam — at	2 4	220 12 6	-
99 ³ / ₄	- D ^o - Rough stone in mud — at	1 12	174 9	-
15 ⁷ / ₃₆	- D ^o - Brick in mud — at	3 4	49 6 1	-
31 ¹ / ₈	- D ^o - Brick in Chumam — at	4	127 8	-
40 ¹ / ₂	12 ¹ / ₂ feet Pillars 3 ¹ / ₂ x 1 ¹ / ₂ feet Diameter in- cluding 3 stones — at	1	40 8	-
81	- D ^o - Pillars 12 x 1 ¹ / ₂ ft diameter including top footing & bond stones Plaster — at	15	75 15	-
46 ³ / ₈	Square Plastering with 2 coats of Chumam	2 8	115 15	-
16 ⁸⁷ / ₁₀₀	- D ^o - Paving with 8" sq bricks & levelling courses beneath — at	7	118 1 5	-
3	Doors Vengay wood with 7 iron bars & shutters &c. Complete. each — at	23	69	-
1	Butten door Complete — at	16	16	-
3	Windows with 8 iron bars & shutters &c. Vengay wood complete — at	18	54	-
2	- D ^o - Butten shutters Vengay wood complete	13	26	-
	Excavating foundations & foundations		116 1 11	-
Total Estimate Proper			2080	-
Amount already sanctioned			1800	-
Amount to be sanctioned			280	-

2nd Range Office
Perianahowa

15th November 1861

Wm. W. Carpenter, Captain, U.S. Army, Appointed Executive Engineer
Eng. in Ch. Supr. Eng. Co. 1st Regt.

Suprs Engrs Office 8th Dec
N 1525 Madura 5th December 1866

From

Captain P. M. Payne
Executive Engineer in ch of
Superintd Engrs Office 8th Dec

To

Colonel. C. A. Orr R.C.
Secretary to Government D. P. W.

Sir

I have the honor to forward
a comparative statement, and a
revised Estimate amounting to Rs.
2,080, for constructing a new Police
Station House attached to the Talug
Cutcherry at Pindiful, 2nd Range
Madura District and to state
that the Original Estimate of Rs 1800
for this work was framed in December
1864. by the then Range Officer Lieutenant
W. Boringham & sanctioned by Government
in their Proceedings N 1750 Dated 23rd
June

Encls. 2

1 Revised Estimate

1 Comparative

Statement

1/2354/11

Madura District

2nd Range Pindiful

Small Buildings

1865-66

1865-66

Revised Estimate for

Constructing a Police

Station House attached

to the Talug Cutcherry

at Pindiful.

Submitted to 21050-

June 1865.

2 The difference between the Original
& Revised Estimates viz \$280 principally
owing to the rise in cost which has
taken place in prices of labor and Materials
since the date of preparation of the Estimate
in 1861. - There is also an increase arising
from an error in the Original Estimate
wherein the number of Square feet
in the roofing was incorrectly
stated.

I have &c

Geo. M. Poyer Captain
Executive Engineer in Ch of
Superintending Engrs Office
8th Division

C. 120882 1866 Ca. 17

4235

Under the explanation
 afforded, the revised estimate of Rs.
 2080, submitted with
 this letter, for the con-
 struction of a new Police
 Station in connection
 with the Taluk Cutchery
 at Dinoligul in the
 Madina District is
 sanctioned.

From the Executive Engineer in
 charge of the Supt. Office
 8th Division

To the Secy. to Govt.
 Public Works Dept.
 Madras

Dec 21st December

Public Works Department.

4023

PROCEEDINGS of the MADRAS GOVERNMENT

Under date the 20th Decr. 1866.
Read the following

From the Executive Engineer in
charge of the Supt. Office
8th Division

(Here enter No. 1525 dated 5 Decr. 1866)

Under the explanation
 afforded, the re-
 vised estimate of Rs.
 2080, submitted with
 this letter, for the con-
 struction of a new Police
 Station in connection
 with the Taluk Cutchery
 at Dinoligul in the
 Madina District is
 sanctioned.

40

P. W. 1867. Department.

Proc. of Govt for Sec

No. 4023

6

PROCEEDINGS OF GOVERNMENT. *of Madras*

Dated *20th Decr 1867*

*The reversed vote
made of Rs 2000 for the
Construction of Police
Station in Connection
with the Falug Catchment
at Dindigul, in the
Madras St. Sanction*

P 425-426