

(1) Number of pages 16

(2) Date of repair 10. 10. 1966

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. <u>4073</u>	Press ~~Mis.~~
<u>528-529.</u>	
Dated <u>22 - 12 - 1966.</u>	

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
22nd December 1866.*

No. 528. Read the following letter from the Executive Engineer in charge of Superintending Engineer's Office, 8th Division, to the Secretary to Government, Department Public Works, dated Madura, 13th December 1866, No. 1,597 :—

With reference to G. O. No. 2,891, dated 10th September last, I have the honor to forward a plan, specification, and an estimate of Rupees 4,650, for building Jailer's quarters, and with out-houses attached, to the new Jail under construction at Madura.

- 1 Plan.
- 1 Abstract Estimate.
- 1 Report.

No. 529. ORDER THEREON, 22nd December 1866, No. 4,073.

CIVIL WORKS, No. 105.

1. The Government approve of the erection of Jailer's quarters in connection with the new District Jail at Madura at a cost of Rupees 4,650. They observe that the design submitted by the Superintending Engineer corresponds with the standard plan which was circulated with G. O. No. 2,891, dated 10th September 1866.

2. The amount now sanctioned should be included in the revised estimate for the Jail which was called for in G. O. No. 3,919, dated 12th December 1866.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 8th Division.

- .. Accountant General.
- .. Controller of Public Works Accounts.
- .. Judicial Department.

Report

Estimate for Constructing the Sailors Quarters
with out Offices at Madras.

1. Amount of Estimate Rupees (4,650-0-0)

Four Thousand Six Hundred and Fifty,

Comprising the following items.

131 ²¹/₆₄ C^o y^o Rough Stone in Chum at 1-2-0-542-11-10.

281 ⁵⁷/₁₆ D^o Brick in Chumam at 5-0-0-1406-9-0

5 ³¹/₁₄₄ D^o Flat arch work in door at 7-5-0-38-2-1.

158 ¹/₂ D^o Earth at 1-6-0-14-13-9

184 ⁷/₉₆ C^o feet Vangay wood (wrought) at 3-4-0-598-3-10

9489 ³/₄ Sqre feet Plastering 3 Coats
per square at 3-8-0-332-2-1.

1944 ¹/₂ D^o Flooring with brick
on edge and levelling
course underneath per sqre 13-0-0-252-12-6.

3000 D^o Roofing with reapers
nails flat & pan tiles
and Chumam borders
8 ¹¹/₁₆ Complete per sqre at 10-0-0-300-0-0

596 ¹/₂ D^o Roofing with rafters,
reapers, nails, pan tiles
8 ¹¹/₁₆ per sqre at 28-0-0-167-0-3

10. Pannelled doors 7 ¹/₂ x 4 Complete at 38-0-0-380-0-0

1. D^o do 6 ¹/₂ x 3 ¹/₂ do at 28-0-0-28-0-0

2. Batten do 6' x 3' do at 25-0-0-50-0-0

1. D^o do 6' x 3' do at 20-0-0-20-0-0

7. Windows (Pannelled) 5' x 3 ¹/₂ do at 22-0-0-154-0-0

3. D^o (batten) 4' x 3' do at 15-0-0-45-0-0

Carried Over 4329 7 4

Brought forward — 4329.74

3. Wooden Crofces for attic windows — 1-8- — 4-8- —

Scaffolding & Sundries — 86.00

1. Mearth — 10.00
4430.00

Contingencies at about 5 per cent. — 220.00

Total Expenses — 4650.00

2. The building is to be raised on a basement 2 feet in height above foundations, which are to be sunk 3 feet. The principal walls and pillars are to be 17 feet high, and the Verandah pillars 8 feet.

3. The building is to contain 6 Rooms and out offices viz.

One room 18 feet long by 18 feet broad —

Three — 18 — do — do — by 12 — do — do —

Two — 12 — do — do — by 12 — do — do —

and the open Verandah 13½ feet broad in front.

Godown & Cookroom.

1. Godown 12 feet long 10 feet broad —

1. Cookroom 12 — do — do — 10 — do — do —

Privy.

10 feet long by 8 feet broad —

1st Range Office
Madras
11 December 1866

P. J. S.
Esq.

A. C. L. H. H. H.
Sub Engineer in chg
1st Range

P. J. S. Captain

Executive Engineer in chg of
Supp. Engr's Office & J. S.

Brought forward		33	13	4	3500
109 $\frac{3}{4}$	Square feet of Flooring with brick on edge and levelling course underneath	13	24	10	2
1779	Square feet Plastering with 3 Coat of Chum	3	0	62	4 2
449 $\frac{1}{2}$	Square feet Roofing with wall plates, rafters, keepers, nails, pau hilo including Ridge ventilator on one side per Square	20	125	13	9
25	Cy of Earth Excavating foundation	1	6	2	5 6
2	Door battem with frames, hooks, hinges & all Complete	6	3	25	50
3	Windows with wooden bars & all Complete	15	45		
	Constructing Strath		10		
	Sundries at about 2 per Cent		65	0	14 11
Total Rupees					670

Privy					
11 $\frac{77}{100}$	Cy of Rough Stone in Chumam at	4	2	40	5
10 $\frac{115}{144}$	Cy of Brick in Chumam at	5		93	15 11
80	Square feet of Flooring with Square bricks and brick on edge underneath per Square	13		10	6 4
953 $\frac{1}{2}$	Square feet of Plastering with 3 Coats of Chumam per Square at	3	0	33	5 11
147	Square feet of Roofing with Couple rafters Collar pieces, keepers, nails, and pau hilo & all Complete per Square at	20		41	2 6
13 $\frac{1}{2}$	Cy of Earth Excavating foundation @	1	6	1	4 0
1	Door battem with frames, hooks hinges & all Complete 3 x 6 at	20		20	
3	Wooden Cof frames for attic windows	1	0	4	0
	Scaffolding and Sundries & all			252	15 11
				7	
Total Rupees					
Carried Over					

Brought forward	4430
Contingencies at about 5 per Cent	220
Total Estimate Rupees	4650

I do hereby Certify that the above Estimate for Constructing Jailors Quarters with out Offices at Madura, Amounting to Rupees (Rs 4650—) Four thousand six hundred and fifty, provides for every thing necessary and at no supplementary works will afterwards be required.

1st Range Officer
Madura
11th December 1866
J. J. S. S. S.

A. B. G. K. S.
Sub Engineer in charge of 1st Range Madura

P. J. Payne Captain
Executive Engineer in charge of Supr. Engrs Office & Dye

114
Sup^d Engrs Office 8th D^o
No 1597 Madras 13th December 1866

From.

Captain C. M. Payne
Executive Engineer in Ch. of
Sup^d Engrs Office 8th D^o

To
Colonel. C. A. Orr R.E.
Secretary to Government D. P. W.

Sir
With reference to G. O. No 2891
dated 10th September last I have the
honour to forward a Plan, Specification,
and an Estimate of Rs 1650 for
building Jailor's Quarters & with
out houses, attached to the new Jail
under construction at Madras.

Yours, &c

C. M. Payne Captain
Executive Engineer in Ch. of
Sup^d Engrs Office 8th D^o

2/2552/66

Enclosure 3
1 Plan
1 Specification
1 Report

For clearance of 2 in a letter
from the Engrs in Ch. of
Sup^d Engrs Office 8th D^o
No 1597 dated 13th Decem
1866 No 514 of 66.

By
The Secy to Govt
D. P. W.

Approved by
District Madras

Approved by
District Madras
Constructing the Jailor's Quarters
and out Houses at Madras

Madras - 4630

13d.

Public Works Department.

No 4073

PROCEEDINGS of the MADRAS GOVERNMENT

Under date the 22nd Decr, 1866
Read the following

From The Cp: Engineer in charge of
Dept: Engineer's Office 5th Division (Here enter No. 1597 dated 13th December 1866)

The Government
approve of the erection
of Jailer's Quarters in
connection with the ^{new} Dis-
trict Jail at Madras
at a cost of Rs. 4,650.
They observe that the
design submitted by
the Superintending Engr.
corresponds with the
standard plan which
was circulated with
G. O. No. 2891, dated
10th Sept. 1866.

The

Plc 1866 No 4073
Cp: Engineer in charge of
Dept: Engineer's Office 5th Division
11/12/66 25142

The Cp: Engrs in chg of
Dept: Engrs Office 5th Div.

The Secy to Govt
D. J. P. C. W.

Dated 13th Decr 1866

Under 13.

The Secy to Govt

Ordinance for conducting
the Jailors' Quarters with
and houses attached
to the New Jail at
Madras.

No 4073-22nd Decr 1866

19th Decr 1866 282125

No 528

The amount now
provisioned should
be included in the
revised Estimate for
the Jail which was
called for in G.O.
No. 3919, dated 12th Dec/66

P. W. 186 . Department.

No. 4073.

PROCEEDINGS OF GOVERNMENT.

Dated

John P. ...
12-1-67

[Signature]

To
The S. Engr 8th Dec ✓
3 Acct Genl
4 Controller
11 Judicial Dept

54
11

Acct 20. 5-28
M. S. Recd to the S. Engr 8th Dec 22nd December
P. C. - to all 5th January/67
e. 19th Dec 1866 (Dr. 21st)

P W 1066 Dep
Pro: & Genl for Genl

No 4043

Pro: & the Major Genl

Of 22 Decr 86

An estimate of Rs
4650 for the erection of
Quarters (Scailers) in Can..
" section with the new
Dt Jail at Madras,
approved with remarks.

Sp 538-529

~~Sp 538-529~~