MRO 1—77,004—8-6-57.

(1) Number of pages 10

(2) Date of repair 1 D 1 1

(3) Initials of the Referencer

# MADRAS RECORD OFFICE.

## Government of Madras.

Public Works DEPARTMENT.

G.O. No. 799 Press ~~Mis.~~

212-213

Dated 10 — 3. 1866.

***Not to be folded or roughly handled***

*Proceedings of the Madras Government, Public Works Department,* 10*th March* 1866.

No. 212. Read the following Proceedings of the Madras Government in the Judicial Department :—

Communicating to the Civil Judge of Bellary an endorsement by the Public Works Department, observing that it has been found impracticable to provide for the new Court-house at that Station in the Budget of 1866-67. } (Here enter 5th March 1866, No. 332.)

No. 213. ORDER THEREON, 10th March 1866, No. 799.

CIVIL WORKS, No. 30.

Communicated to the Superintending Engineer of the 3rd Division.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
*Secretary to Government.*

To the Superintending Engineer, 3rd Division.

Exd. S. T. Augustin.

New Work.
Judicial.

Abstract.

# Work Continuing & Court House at Bellary.

| Quantity | Items of Work. | Rate | | | Per | Amount | | | Total. |
|---|---|---|---|---|---|---|---|---|---|
| 76784.11 | Stone in Chunam | " | 2 | " | ₹ ft | 959.8 | 1 | 10 | |
| 3636.7 | Arch work | " | 6 | " | " | 1363 | 11 | 6 | |
| 509 19. | Plastering | 4 | " | " | ₹ sqre | 2036 | 12 | 1 | |
| 1838.6 | Door Work moreach kind complete | 4 | " | " | ₹ ft | 7354 | " | " | |
| 102.56 | Terracing with brick on edge. 2 ft | 55 | " | " | ₹ sqre | 6740 | 12 | 8 | |
| 2338. | Bengal terrace & Verandah | 15 | " | " | " | 350 | 11 | 2 | |
| 1116. | Rftg Granite slabs | " | 8 | " | ₹ ft | 558 | " | " | |
| 23.32. | Plastering and Cutting grooves | 5 | " | " | ₹ sqre | 116 | 9 | 7 | |
| 828 | Rftg Cornice work | " | 8 | " | ₹ ft | 414 | " | " | |
| 60. | 1 ft. Folding door 10×6. Do. | 1 | 10 | " | ₹ ft | 97 | 8 | " | |
| 240 | " Door with Shutters 4×7-6 Do 8. | 1 | 8 | " | " | 360 | " | " | |
| 1701 | " Iron bars & windows Do 4×9.8 Do 46 | 1 | 10 | " | " | 2764 | 2 | " | |
| 260. | " Ventilators. 5×2 Do 26. | 1 | 8 | " | " | 390 | " | " | |
| 1. | Iron bars & Gates in front | 182 | " | " | each | 182 | " | " | |
| 1834.4 | Filling in Basement | " | " | 3 | ₹ ft | 286 | 9 | 3 | |
| 8149. | Flooring with Goa slabs | 8 | " | " | ₹ sqre | 651 | 14 | 9 | |
| 13016. | Pointing the floors (Gala) | 2 | " | " | " | 260 | 5 | 1 | |
| 4522. | 1 ft Sq Plain painting | 3 | 8 | " | " | 158 | 4 | 3 | |
| 221 | 1 Coat of wood oiling | 2 | " | " | " | 442 | " | " | |
| 23692 | Cft Excavation | " | " | 2 | ₹ ft | 246 | 12 | 8 | |
| | Sum carried at 5 per Cent | | | | | 1717 | 13 | 2 | |
| | Total for Lower Storey | | | | | | | | 35990 " |
| | **Upper Storey.** | | | | | | | | |
| 7760-6 | Stone in Chunam | " | 2 | 6 | ₹ ft | 1212 | 9 | 3 | |
| 7260. | Plastering | 4 | 8 | " | ₹ sqre | 326 | 11 | 2 | |
| 231-6 | Rftg Slabs | " | 9 | " | ₹ ft | 130 | 3 | 6 | |
| 252.3/4 | Wt of Wrought Iron work | " | 4 | " | ₹ lbs | 63 | 2 | " | |
| 8 | Shoes of Cast Iron | 5 | " | " | each | 40 | " | " | |
| | Carried over | | | | | 1772 | 10 | 11 | 35990 " " |

| | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | Brought Forward | | | | | | 1772 | 10 | 11 | 35990 " |
| 725-4-11 | Cfbog work through Ld Pankeys | 4 | 8 | " | yds | 3264 | 5 | 6 | | |
| 803. | Terracing with brick on edge. 8cm | 55 | " | " | yds | 441 | 10 | 4 | | |
| 80.74 | Brugat terrace & verandahs | 15 | " | " | " | 1211 | 1 | 7. | | |
| 60 | Cfbog Door 8x7-6 No 1. | 1 | 8 | " | yds | 90 | " | " | | |
| 60 | " of Do. 4x7-6 No 2 | 1 | 8 | " | " | 90 | " | " | | |
| 18 | " of window 3x5 No 1. | 1 | 8 | " | " | 22 | 8 | " | | |
| 720. | " Do. 4x10 No 18. | 1 | 8 | " | " | 1080 | " | " | | |
| 81 | " Ventilators 3x1-6 No 18. | 1 | 8 | " | " | 121 | 8 | " | | |
| 5784.6 | Painting the wall. 8cm | 2 | " | " | yds | 115 | 12 | 7. | | |
| 575. | Cfbog Cornice work. | 1 | " | " | yds | 575 | " | " | | |
| 4½ | Cfbo of green painting | 4 | " | " | yds | 18 | " | " | | |
| 92½ | " of floor oiling | 2 | 8 | " | " | 231 | 4 | " | | |
| | Fixtures. | | | | | | | | | |
| 450 | Cfbog cloth screen 12-6x18 No 2. | " | 4 | " | yds | 225 | " | " | | |
| 205-6. | " of Railings | 1 | 8 | " | " | 308 | 4 | " | | |
| 2 | Punkahs. 12 x 3. | 20 | " | " | (cm) | 40 | " | " | | |
| | Sundries at 5 per Cent. | | | | | 482 | 15 | 1 | 10030 | " |
| | Total Estimate | | | | | | | | 46020 | " |
| | Deduct for Convict Labor | | | | | | | | | |
| | Stone masonry | | | | | 7206 | " | " | | |
| | Arch work | | | | | 454 | " | " | | |
| | Plastering | | | | | 787 | " | " | | |
| | Roofing | | | | | 1456 | " | " | | |
| | Pointing | | | | | 46 | " | " | | |
| | Cornice work | | | | | 116 | " | " | | |
| | Flooring | | | | | 325 | " | " | | |
| | Green painting & floor Oiling | | | | | 141 | " | " | | |
| | Excavating & filling in basement | | | | | 489 | " | " | 11020 | " |
| | Balance Estimate Prisons | | | | | | | | 35000 | " |

Bellary.
30th November 1865.

Lieut Colonel
Superintendent of Prisons

Lieut Colonel
Engineer & Dirn

5

## *Proceedings of the Madras Government, Judicial Department, 5th March* 1866.

No. 18. Read the following letter from the Superintending Engineer, 3rd Division, to the Secretary to Government, Public Works Department; dated Nundial, 5th February 1866, No. 206.

I have the honor to forward herewith Plan and Estimate, amounting to Rupees 35,000, for constructing a Court House at Bellary, and request the sanction of Government for the same. The Plan is approved by the Judges of the High Court

2. The work has been entered in the Budget for 1866-67 already submitted by me.

---

Referred to the Judicial Department, with reference to the Orders in that Department, No. 31, dated 13th January 1865. It has been found impracticable to allot funds for the work in the Budget of 1866-67.

FORT SAINT GEORGE, *9th February* 1866.

(Signed) C. A. ORR, Colonel, R. E.,
*Secretary to Government, P. W. D.*

No. 19. ORDER THEREON, 5th March 1866, No. 332.

Communicated to the Civil Judge of Bellary.

(True Extract).

G. J. Cumberland
*Chief Secretary.*

To the Civil Judge of Bellary.
„ Public Works Department, with two Plans and one Estimate.

Erd. R. H. Lee.

List Civil Works

No. 799

Comm^d to the

Sup^g Engineer

of the 3^d Div^n

Fort St George
10th March 1866

6 to SE 8 Div^n

16/2

Desp^d 12^th March

No 291.