M.R.O. 1—77,006—8-6-37.

(1) Number of pages 8

(2) Date of repair 5-1-43

(3) Initials of the Referencer

# MADRAS RECORD OFFICE.

## Government of Madras.

Public works DEPARTMENT.

G.O. No. 191 Press Mis.
413-414

Dated 17—1— 1866.

**Not to be folded or roughly handled**

No. 413. Read the following letter from the Superintending Engineer, 5th Division, to the Secretary to Government, Department Public Works, dated Salem, 6th January 1866, No. 53 :—

1. With reference to G. O. No. 2,633 of the 15th of September 1864, I have the honor to forward, for the sanction of Government and entry in the Budget of 1866-67, a revised estimate amounting to Rupees 4,600 for the residence of the Postmaster at Bangalore.

1 Plan.
1 Abstract Estimate.
1 Specification.

2. The estimate and plan were forwarded to the Director General of Post Offices in July, and returned by him with a suggestion that the building used as a Post Office should be enlarged so as to provide accommodation for the Postmaster. This was found to be impracticable, and the plan and estimate for a separate building have now been approved by the Director General.

No. 414. ORDER THEREON, 17th January 1866, No. 197.

**CIVIL WORKS, No. 74.**

1. Under the circumstances which are explained by the Superintending Engineer of the 5th Division, the Government sanction the estimate, amounting to Rupees 4,600, for the construction of a dwelling house for the Postmaster at Bangalore.

2. Part II. of the Budget for the ensuing year having been closed, the Government are unable to make provision therein for the work now sanctioned. The Postmaster General will apply early in May next, for a grant of money from the Reserve of 1866-67.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
*Secretary to Government.*

To the Superintending Engineer, 5th Division, with Specification.
" Postmaster General.
" Public Department.
" Controller of Public Works Accounts.
" Accountant General.

Exd. S. T. Augustin.

5th Division D. P. W

Bangalore — New Work

# Abstract Estimate

Work Constructing a Dwelling House for the Post Master at Bangalore

| Quantity | Particulars of Works | Rate | Per | Amount | Total |
|---|---|---|---|---|---|
| | **Main Block** | | | | |
| 2081 | Cft. Excavation for foundation | " " 1 | Cubft. | 10 13 5 | |
| 2566 | do Stone work in Mortar | " 2 " | do | 320 12 " | |
| 4669 | do Brickwork in do | " 2 4 | do | 680 14 4 | |
| 85 | do Flat Arch work | " 4 " | do | 21 4 " | |
| 7134 | Sft. Plastering with 2 Coats of Chunam | 2 8 " | Sft. | 178 5 7 | |
| 2462 | do Bluewashing | " 3 6 | do | 5 6 2 | |
| 4672 | do Whitewashing | " 2 6 | do | 7 4 10 | |
| 157 | Rft. Cornice work | " 4 " | Rft. | 39 4 " | |
| 1612 | Sft. Flooring with Stone Slabs in bedded in Sand and points with Chunam | 8 " " | Sft. | 128 15 4 | |
| 46¾ | Cft. Teakwood wrought & put up | 3 2 " | Cft. | 146 1 6 | |
| 36 | No. do Couples | 16 " " | Each | 576 " " | |
| 76 | do do Rafters | 4 11 " | " | 356 4 " | |
| 898 | Sft. Green Paint 2 Coats | 5 " " | Sft. | 44 14 5 | |
| 2520 | " Roofing with reepers flat & Pantiles Chunam borders &c. Complete | 16 " " | do | 403 3 2 | |
| 56 | Rft. Ridge Ventilators | 3 7 4 | Rft | 193 10 8 | |
| | | | Carried over | Rupees | 3113 1 5 |

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| | | Brought over | | | | | 3113 | 1 5 |
| 2 | N° | Doors battened with frames fitting &c complete | 24 | 8 | Each | 4 9 | | |
| 6 | d° | Doors (half-panelled half Ventilioned) &c Compl | 32 | 2 6 | d° | 192 | 15 | |
| 12 | d° | Windows (Ventilioned | d° | 16 8 | d° | 195 | | |
| 12 | d° | d° (Glazed &c | d° | 12 | d° | 144 | | |
| 19 | Rft | Steps of Stones | | 3 | Rft | 3 9 | | |
| | | Total | | | | | 3697 | 9 5 |
| | | Scaffolding & Sundry Charges | | | | | 220 | 7 |
| | | Total | | | | | 3918 | |

## Out Houses

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| 486 | Cft | Excavation for foundation | | | 1 Cft | 2 8 6 | | |
| 613 | d° | Stone work in Mortar | | 2 | d° | 76 10 | | |
| 1015 | d° | Brick work d° | | 2 4 | d° | 148 | 4 | |
| 19 | d° | Flat Arch work | | 4 | d° | 4 | 12 | |
| 1710 | Sqft | Plastering with 2 Coat of Chunam | 2 | 8 | Sqft | 42 | 12 | |
| 706 | d° | Bluewashing | | 3 6 | | 2 | | |
| 1003 | d° | Whitewashing | | 2 6 | | 1 | 9 | 1 |
| 107 | Rft | Cornice work | | 2 | Rft | 13 | 6 | |
| 237 | Sqft | Flooring with Stone Slabs | 8 | | Sqft | 18 | 15 | 4 |
| 4 | Cft | Teakwood wrought & put up | 3 | 2 | Cft | 12 | 8 | |
| 195 | Sqft | Green Paint 2 Coats | 5 | | Sqft | 9 | 12 | |
| 476 | d° | Roofing with Reepers &c | 16 | | E | 76 | 2 | 7 |
| 20 | d° | Teak Couples | 7 | | d° | 140 | | |
| 5 | d° | Doors (Batten &c Compl | 24 | 8 | d° | 73 | 8 | |
| 2 | d° | Windows d° | 12 | | d° | 24 | | |
| | | Carried over | | | | | 646 | 7 10 3918 |

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| | | Brought over | | | | | 646 | 7 10 3918 |
| 12 | Rft | Steps of Stones | | 3 | Rft | 2 4 | | |
| | | Total Rupees | | | | | 648 | 11 10 |
| | | Scaffolding and Sundry Charges &c | | | | | 33 | 4 2 |
| | | Total Rupees | | | | | 682 | |
| | | Grand Total Rupees | | | | | 4600 | |

Rupees Four thousand and Six hundred only

Supt Engrs Office
June 1865

E A Ford Lieut Col RE
Superintending Engineer 5th Dn

Superintending Engineer's Office 5th Dn
Salem 6th January 1866.

No. 53.

From,

Lieut.t Colo.l C. A. Foord R.E.,

Superintg Engineer, 5th Divn

To,

Colonel C. E. A. Orr R.E.

Secretary to Government P.W.D.

Sir,

Enclosures
1 Plan
1 Abstract Estimate
1 Specification

With reference to G.O. No. 2,683 of the 15th of September 1864. I have the honor to forward for the sanction of Government an detailed revised estimate in the Budget of 1866/7 amounting to Rupees 4,600 for the Residence of the Post Master at Bangalore.

2. The Estimate and Plans were forwarded to the Director General of Post Offices in July and returned by him with a Suggestion that the building used as Post Office should be enlarged so as to provide accommodation for the Post Master. This was found to be impracticable and the Plans and Estimate for a separate building have now been approved by the Director General.

I have the honor to be
Sir
Your most Obedient Servant

C A Foord Lieut.t Col.l R.E.
Superintending Engineer
5th Division

No. 410-414.

1866 Dept.
Pro.-of Govt. for January
From. No. 76.

The Supg Engineer
5th Division

To
The Secretary to
Government P.W.D.

Dated 6th
Received 8th } January 1866.

No. 55

Enc: 3.
1 Plan
Forwarding for sanction &
entry in the Budget of
1866/7 a revised estimate
with plan &c. for the
Residence of the Post Master
at Bangalore.

with an order
No. 197 17th Jany. 1866.

197 Civil Works
No. 197

1- Under the circumstances which are explained by the Superintending Engineer of the 5th Division, the Government sanction the Estimate amounting to Rs. 4.600 for the construction of a dwelling house for the Post Master at Bangalore.

2. Part II of the Budget for the ensuing year having been closed, the Government are unable to make provision therein for the work now sanctioned. The Post Master General will apply early in May next, for a grant of money from the Reserve of 1866/67.

To
The Supt. Engr. 5th Div.
2. Post Master General
3. Pub. Department
4. Controller
5. Accountant General
Dept. 18 Lancr.

Fort St. George
17 Jany 1866.