M.R.O. 1—77,006—8-6-37.

(1) Number of pages

(2) Date of repair

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 267 Press / Mis.

556-557

Dated 23. 1. 1866.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 23rd January 1866.

No. 556. Read the following letter from the Superintending Engineer, 5th Division, to the Secretary to Government, Department Public Works, dated Bangalore, 21st December 1865, No. 46:—

1 Plan,
1 Section,
1 Site Plan,
} forwarded per banghy.
1 Estimate.
1 Specification report.

1. I have the honor to forward, for the sanction of Government, an estimate of Rupees 27,570 with plan and specification, for Provost yard and cells and quarters for the Provost Serjeant at the New Dragoon Barracks, Bangalore.

2. The estimate has received the approval of His Excellency the Commander-in-Chief, and has only just been returned to me, through the Executive Engineer. The work, after having been stopped like the others at the new Barracks, in the month of May, was again proceeded with under the orders of Government of the 20th September 1865, No. 2,777, and is likely to be completed by the 1st of January.

No. 557. ORDER THEREON, 23rd January 1866, No. 267.

MILITARY WORKS, No. 22.

1. His Excellency the Governor in Council sanctions the estimate, amounting to Rupees 27,570, for the construction of a Provost yard and cells and quarters for the Provost Serjeant at the new Dragoon Barracks at Bangalore.

2. It is observed from paragraph 2 of the foregoing letter from the Superintending Engineer of the 5th Division, that these works were expected to be completed by the 1st instant.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 5th Division, with three Enclosures.
,, Accountant General.
,, Controller of Public Works Accounts.
,, Military Department.

Exd. S. T. Augustin.

No. 46.

Superintg Engineer's Office 6th Dn
Bangalore 21st Decemr 1865

From,

Lieut.t-Coll.o C. e A. Foord R.E.
Superintg Engineer
5th Division

To,

Colonel C. e A. Orr R.E.
Secretary to Government
P.W.D.

Sir,

I have the honor to forward
Enclosures 5.
1 Plan
1 Section
1 Site Plan
1 Estimate
1 Specification
Report
for the sanction of Government an Estimate of Rupees 27570.0.0 with plans and Specification, for Provost Yard and Cells, and Quarters for the Provost Sergeant at the New Dragoon Barracks Bangalore.

2 The Estimate has received the approval of His Excellency the Commander-in-Chief and has only just been returned to me

Through

through the Executive Engineer.
The work after having been
stopped like the others at the
new barracks in the month of
May we do) again proceeded
with under the orders of Government
of the 20th September 1865 No. 2111
and to Civil to be completed
by the 1st of January

I have the honour to be
Sir
Your Most Obedient Servt.
Lt. Ford Lieut. R.E.
Superintending Engineer
5th Divn

Abstract Estimate, for Constructing a Provost Yard &c. for the New Dragoon Barracks at the old Race Course. Bangalore.

Quantity	Description of work		Rate	Per	Amount	Total
	Provost Cells.					
10704	Excavation				1	56
8949	Stone in Sand for foundation		16	do	839	
7085	Stone in Chunam		2	do	886	
30835	Cubic in Chunam		22	do	4176	
1855	Arch work		41	do	473	
26810	Plastering and white washing	2	106	Sft.	712	
11508	Plastering and Lime washing	2	106	do	313	
1302	Lime washing the basement		36	do	3	
632	Painting feet of Carriage work		4	Sft.	158	
9176	Sft. Flooring		7		Sft. 642	
897-10	Iron Dressed wrought and put up		3		Cft. 2693	
1144	Plaster Nails				8 ℔	48
4046	Terracing with brick on edge fully 3 Courses of flat tiles and plastered with 3 Coats of Chunam over the roof and for sealing		27		Sft.	1092
4800	Semi terracing with pea fer 3 Courses of flat tiles Complete		19	4	do	924
27	Pairs of battened Doors with frames Iron fittings Complete		23		℔	621
4	Pairs of Iron barred Windows with battened shutters frame and Iron fittings &c. Complete		23		do	92
		Carried Over				13728

Estimate 1866 Dated 1st January 1866.

Recd. with Letter from Executive Engineer Dated 21st December 1865 Dispd. 1st January 1866.

To
The Secretary to
Government
Public Works Dept.

Sir,

I have the honor to forward herewith an Estimate with Plan and Specification for Constructing Provost Cells and Repairing the Provost Yard &c. for the New Dragoon Barracks at the old Race Course Bangalore.

I have the honor to be
Sir
Your most obedient Servant
Bangalore 26th January 1866.

C. Ramsay Lt. R.E.

Quantity

Description of Work	Qty	Unit	Price	Amount	Total
Brought Over					13728
50 Attic Windows with iron grates and frames pr	9	@	504		
2 Dormer Windows Do Do	50	do	100		
23 Grand Ventilators with Frames and their fastening themin with works	5	@	115		
46 Grand Ventilator perforated wrought Iron plates Do Do	2	26	do	130	
1828 ☐ft of Green paint	5		☐ft	91	
7080 Wood Ceiling	2		do	142	
10704 Filling in (Clare)			¼ ☐ft	14	
5309 Filling in (for distances of 100 ☐ft)	2		do	55	
65 Stone Stabs for under beams and top of the pillars	8	@		32	
68 Alterations for Privy					
99 Stone work in Ohmaan	2		☐ft	9	
23 Brick work in Ohmaan	24		do	14	
296 Brick work in Ohmaan	4		do	6	
54 Plastering and White washing	2	106	☐ft	8	
30 6 ☐ft of Steps	4		☐ft	14	
1 ☐ft of granite Seats for privy together for enclosings in front and sides	1		☐ft	30	
6 Iron Catches to be fixed in the Stones to receive the pans &c	8	@		3	
Sheet Iron partitions					
45 Panelled with	10		☐ft	28	
Demolishing walls already constructed	6		☐ft	10	
Scaffolding and Sundries					
Carried Over					15773 4 3
					754 4 9
					797
					15790 15800

Description of Work	Qty	Unit	Price	Amount	Total
Brought Over					15790 15800
Passage					
excavation	1		☐ft	1	
in Land for foundation	16		do	28	
ne in Ohmaan	2		do	7	
ick Work in Ohmaan	22		do	56	
ering and White washing	2 106		☐ft	20	
ering	7		do	25	
Wood in rough and put up	3		☐ft	160	
after Nails	8	@		2	
ing with brick & all					
Belly with 3 Courses of flat					
d plastering over and	24		☐ft	125	
ng pr Complete					
Ceiling	2		do	8	
Slabs over pillars	8	@		8	
				440	
				20 & 10	
				30	
Scaffolding and Sundries					460 470
ed to Non Comm? Officers Rooms					
excavation	1		☐ft	14	
in Land for foundation	16		do	251	
ne in Ohmaan	2		do	167	
ft of Stone steps	4		☐ft	11	
ick in Ohmaan	22		☐ft	896	
ick work	41		do	73	
tering and white washing	2 106		☐ft	118	
tering and Olive washing	2 116		do	126	
ine washing the basement	36		do	2	
Carried Over					1658 16270

Quantity	Description of work	Date	Price	Amount	Total
	Brought Over			1658	16270
166	Sft. of Carriage work		4	10d	40
43	Sft. of Casing			5	0 3/4
2506	Flooring			7	1 15
320	Seat Wood wrought & put up			3	0 9 6
320	Rafter Nails			0	8 0 13
882	Terracing with best Sawdges Selly & Courses of flatstones plastering and sealing &c. Complete			27	0 2 3 8
1920	Semi terracing with pavers 3 Courses of flatstones &c. Complete		19	4	0 36 7
1	Entrance battened Door with frame and iron fittings &c. Complete			40	0 0 40
4	Pairs of battened Doors with frames and Iron fittings &c. Complete			23	0 8 92
6	Pairs of Seat Wood windows with frame and iron fittings inside glazed and outside battened shutters &c. Complete			30	0 8 180
9	Swing windows with glazed shutters cleats rings and hopes &c. Complete			7	0 8 63
497½	Green painting			0	0 4½ 25
2558	Wood Ceiling			2	0 0 51
1828½	Filling in Close				0 ¼ 2
26	Stone slabs under beams and over pillars Ready and Levelled &c. Rem			0	8 0 13
229	Excavation				0 0 1½ 2
229	Stone in Sand for foundation				0 1 6 0 3 1
	Carried Over				15

Quantity	Description of work	Date	Price	Amount	Total
	Brought Over			3964	16270
205	Stone in Ohmam			2	0 5 26
18	Sft. of steps			4	0 5 5
620	Brick work in Ohmam			24	0 3 90
40	Arch work in Ohmam			4	0 0 10
564	Plastering and White washing		2	106	0 15
532	Plastering and Blue washing		2	116	0 15
44	Carriage work			4	0 1 11
107	Paving the floor with granite stones set in Sand and painted with Ohmam			8	0 0 9
200	Terracing with 3 Courses of flatstones &c.		19	4	0 39
23	Seat Wood wrought & put up		3	2	0 7 3
1	Battened Door 3×6		22	8	0 8 20
1	Window battened 3×5		18	12	0 0 19
40	Green paint			5	0 2
100	Wood Ceiling		2	0	0 2
20	Sft. Rafter Nails			8	0 1
196	Filling in (close)				0 ¼
18	Sft. of stones for Privy seats cut in halves and well dressed together for enclosing in pans and sides			1	0 1 8
15	Sheet iron partitions painted with coal tar			10	0 1 10
4	Iron Catches			8	0 0 2
					4035
	Scaffolding and Sundries				215
	Provost Sergeants Quarters				4250 1550
3533	Excavation				0 1 0 18
3533	Stone in Sand for foundation			16	0 331
1974	Stone in Ohmam			2	0 247
	Carried Over			596	20820

Quantity	Description of work	Rate	Per	Amount	Total
	Brought Over			596	208
49	Rft. of Plano steps	" 4	Rft.	12	
8707	Brick in Chunam	" 2	Cft.	479	
330	Arch work	" 4	do	84	
676½	Plastering and White washing	2 10	Sq.	180	
4951	Plastering and blue washing	2 11	do	135	
472	Blue washing the basement	" 3	do	83	2
196	Rft. of Cornice work	" 4	Rft.	49	
33	Cft. of Coping	" 5	do	10	
2708½	Rft. of Flooring	7	do	194	
287	Teak Wood in Caught & put up	3	Cft.	861	
330	Copper Nails	" 8	C.	14	
822	Terracing with Brick Rounded Sally 3 Courses of flat tiles and plastering Over and ceiling complete	27	Sq.	222	
2148	Semi terracing with Reapers 3 Courses of flat tiles complete	19 4	do	413	
10	Venetianed and half pannelled Door with frame and Iron fittings complete	24	do	240	
6	Pairs of Venetianed Windows with frame and Iron fitting inside glazed complete	30	@	180	
4	Swinging windows with glazed shutters cleat and paper complete	7	@	28	
3	Pairs of Battened Doors with Iron fittings complete	18	@	54	
2	Pairs of Battened Windows with Iron fittings complete	15	@	30	
969½	Green paint	5	Sq.	48	
	Wood Oiling	2	do	112	
	Carried Over	4643		2052	

Quantity	Description of work	Rate	Per	Amount	Total
	Brought Over	4643		20820	
2646½	Filling in Plano		¼	Cft. 3	
14	Plano Slabs over pillars and under beams	" 8	@	7	
15	Rft. of Fine plaster	" 7	"	Rft. 7	
	Per Rainy			25	
				4685	
				237 12	2
				255	
	Scaffolding and Sundries				4885
					4943
	Palisading				
270	Excavation for foundation		1	Cft. 1	
240	Brick in Chunam		22	do 32	
352	Teak Wood wrought & put up	3		do 1056	
1972	Nails		8	@ 82	
				1171	
				69	12
	Scaffolding and Sundries				1240
					1500
					27570
	Grand Total Rupees				27000

Exd. Engrs office
Vengalare 29th August 1865

H. Mulock Captain RE

Executive Engineer Vengalare

S. Subramaniar B.C.E.
Superintendg D.S.W.

Examined & Checked RE.
Superintendg Engr S.C. &c

Public Works Dept.

No 267

Proceedings of the Madras Government

Under date the 23rd January 1866

Read the following

From the Supdg Engr. 5th Dn.

Forwarding for sanction an Estimate with plan & Sec for Provost yard and cells & Quarters for the Provost-Sergeant at the New Dragoon Barracks, Bangalore.

Here under 21st December 1865 No 461

His Excellency the Governor in Council sanctions the Estimate amounting to Rupees 27,670. for the construction of a Provost Yard and Cells and Quarters for the Provost Sergeant at the new Dragoon Barracks at Bangalore

It is observed from para 2 of the foregoing letter from the Superintending Engineer of the 5th Division that the

these works were expected to be completed by the 1st Instant

Sir

I am Supg Capt. S. Dr. Watts's Enclosure
" acct. Genl. √
" Controller √
" Military Dept. √

Dear Sir 24th January

30

Pt. 2. 1866 Dept to
Pow: of Gov.t for Jany.

No. 267
Pow: of the M.Gen.l
of 23d Jany 166

Provost yard
and Cells and Quarters
for the provost Sergeant
at the new D. Jagoan
Barracks at Bangalore
the estimate amounts
to Rs.27.070 for the
construction of same
tioned.

No. 556. & 557.