

(1) Number of pages 6

(2) Date of repair 8-1-03

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 414	Press
86-81	~~Mis.~~
Dated 2 - 2.	1866.

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
2nd February 1866.*

No. 80. Read the following Proceedings of the Madras Government in the
Military Department:—

Approving of the estimate, amounting to Rupees }
1,500, for sinking two wells on the ground } (Here enter 26th January 1866, No. 330.)
selected for a cholera camp near Trichinopoly.

No. 81. ORDER THEREON, 2nd February 1866, No. 414.

MILITARY WORKS, No. 10.

1. Communicated to the Superin-
tending Engineer of the 6th Division.

2. The work may be at once pro-
ceeded with, its cost, viz., Rupees 1,500, being charged against the Reserve under
"Military."

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,

Secretary to Government.

To the Superintending Engineer, 6th Division.

„ Accountant General.
„ Controller of Public Works Accounts.
„ Military Department.

Exd. S. T. Augustin.

Military Trichinopoly District No 1 Range. New Work.
Abstract Estimate No. 1865/66 ✓
Work. — Approximate Estimate for sinking
2 Wells each 75 feet deep by 9 feet in diameter in the
 Ground selected for a Cholera Camp near the 4th
 Mile Stone of Poducottah Road at Trichinopoly.

Quantity	Description of Work	Rate	Amount	Amount of each Part.
45	Cy & Lamination including bolting & perp	4	39 6	
45	do do do do	1	45	
45	do do do do	1 8	67 8	
45	do do do do	2	90	
45	do do do do	3	135	
1485	Q ^{ty} of Well Bricks in Mortar for cft	3	278 7	
205	do Bricks in Mortar — do	2	25 10	
1	Teakwood Beam wheel & roller		25	
	do — seating over the Well		20	
	sundries contingencies		24 1	
	Total for a Well		750	
	Total Estimate for 3 Wells as above		2250	
	Total Estimate Rupees		2250	

Approved Signed J. Greenaway M.C. Eng.
Supg Engrs office 6th Dec 1st Nov 1865. T. F. D. K. Captain R.L.
Tanjore As. Supg. Engrs 6th Dec

Estimate for
 sinking 2 wells in
 the ground marked
 for Chelva Camp
 in Trichinopoly
 amounting to Rs 1500
 2250-0-0
 1/10/14369

No. 12,128 of 1866

419
1/10/14369

Enclosure
 No. 1/1866

MILITARY DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

3✓

Read the following papers :—

From the Superintending Engineer, 6th Division, Camp Chitlaroy, 6th January 1866, No. 1642; to the Secretary to Government, Public Works Department.

I have the honor to forward an estimate of Rupees 1,500, for sinking two wells on the ground in the neighbourhood of Trichinopoly, which has been selected for a cholera camp.

Enclosures 2.
 1 Estimate.
 1 Letter.

2. The estimate has received the approval of His Excellency the Commander-in-Chief; it is entered in the budget list of 1866-67 of works below 2,500 Rupees. The original estimate provided for three wells as you will observe.* The estimate must be regarded as an approximate estimate only—if water is found nearer to the surface than 75', the cost of the wells will fall within the estimated amount. If funds can be provided from the reserve, the wells might be excavated at once.

3. On the undermentioned work a saving of Rupees 1,416 has been effected, but as it is a budget work, I presume that the saving cannot be appropriated for the wells.

Budget No.	Name of work.	Amount of allotment for 1865-66.
7	Racket and Fives' Court for the Artillery.	4,420.

Referred to the Military Department for disposal. Funds are available from the reserve under "Military."

11th January 1866. (Signed) C. A. ORR, Colonel, R. E.,
 Secretary to Government, P. W. D.

ORDER, No. 330, 26th January 1866.

Approved.
 (True Extract.)

Munro
 Deputy Secretary to Government.

To the Public Works Department, with two enclosures.
 „ Quarter Master General.

Erd. J. E. Cashart.

4th 1866 Dep't
Pro: of Govt for February
No 419

Pres. of Gov't in the
Mil. Dept.

267
Nov 30

82 No. 200

Approving of
the estimate amounting
to ~~Rs~~ 1,500 for sinking
two wells on the ground
selected for a cholera
camp near Trichinopoly

With an order

no. 414-2nd July 1866

End

Lucy Weston

414 210

Course to M. J. E. of the S. B.

2. The work may be all over

proceed with, its cost, viz. \$20.15

being charged against the Revenue

17055608 ~~inches~~ inches
320 ~~feet~~ feet - 80

10 West 3rd Ave
2 Central Ave
2nd West - 8th St

Street & Gauge, N.Y.C.
2nd May 1866

and July 1866 } Will.