

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public works DEPARTMENT.

G.O. No.	1251	Press
		Mis.
505-06		
Dated	27-4-	1867.

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
27th April 1867.*

No. 505. Read the following letter from the Officiating Superintending Engineer, 8th Division, to the Secretary to Government, Department Public Works, dated Madura, 10th April 1867, No. 69 :—

1. With reference to G. O. No. 3,359, dated 20th October 1866, I have the honour to submit the revised estimate of Rupees 6,900, with plan and report, for making additions to the public Offices at Tuticorin. Provision has been made

1 Plan sent separately.
1 Report.
1 Estimate.

for laying down a granite curb to the Customs Godown's verandah, and a granite pavement from the Customs House to the shore-end of the jetty.

2. A sum of Rupees 3,545 was expended on the buildings in the past year; but work is now suspended under paragraph 79, of G. O. No. 3,938, of 14th December 1866.

No. 506. ORDER THEREON, 27th April 1867, No. 1,251.

CIVILL WORKS, No. 44.

The Governor in Council sanctions the revised estimate of Rupees 6,900 submitted with this letter, and directs that the work, upon which Rupees 3,545 are reported to have been expended up to 31st March, be completed with as little delay as possible from funds specially provided for it in the Budget estimate of the current official year.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 8th Division, with one Specification.
,, Accountant General.
,, Controller of Public Works Accounts.
,, Revenue Department.

Exd. S. T. Augustin.

Abstract Estimate No. of 1866/67
 District Sinnerelly Taluk Ottapicdarum
 Work - Constructing Addition and Alteration to
Public Office at Interior

Quantities	Description of Work	Rate	Amount	Amount of each part
	<u>See Custom House & Post Office</u>			
	<u>Lower Story</u>			
2. $\frac{24 \frac{3}{4}}{27}$	Regards Concrete — at	3	8	12
65 $\frac{19 \frac{1}{2}}{27}$	— de Sand Stone in Cham — at	6	375	10 10
1. $\frac{21 \frac{3}{4}}{27}$	de Cornice work with hard			
	Sand Stone in Cham — at	10	17	14 8
606	Square feet Terracing with Bricks on edge jelly two courses of flat tiles and 3 coats of Plastering to the ceiling and top of Terrace per 100 Sq feet — at	28	169	10 10
186	Square feet Flooring with 12 in. ches Square 3 thick hard Sand Stone in Cham per 100 Sq ft — at	6	11	2 6
1329 $\frac{2}{8}$	Square feet Plastering — at	3 8	46	8 5
123 $\frac{5 \frac{1}{4}}{14 \frac{1}{2}}$	Ce feet. Wroughtwood — at	3 8	431	11 10
89 $\frac{2 \frac{1}{2}}{10}$	— de Mango Planks — at	3	268	12 6
1716	Sq feet Removing & replacing roof of Palmira rafters & beams flat and Pantiles Cham borders with a portion of new materials — at	20	343	3 2
1.	Pannelled door ($3 \frac{1}{2} \times 6 \frac{1}{2}$) half Venetian with frames hooks hinges bolts &c complete — at	38	38	

2	Windows (3 1/2 x 4 1/2) half Venetian with frames hooks hinges bolts per complete — at	20	40		
6	Bracket Stones each — at	8	3		
1 1/2	Cubic yards Bath work — at	1	2	9	5
<u>Upper Story</u>					
0.02 43/100	Ce yards Sand Stone in Cham — at	6	482	13	10
187 2/10	Perfect Plastering per 100 sq ft — at	3	8	311	8
702	do. Sloping Terrace to Verandah with 2 courses of flat Tiles bricks Jelly & two coats of plastering per 100 Square feet — at	20	140	6	4
2 1/8	Perfect Wrought wood — at	3	8	73	15
3	Doors (3 1/2 x 6 1/2) half Venetian with frames hooks hinges bolts per complete — at	38	114		
5	Windows (3 1/2 x 4 1/2) — do — do — at	20	100		
6	Bracket Stones — each — at	8	3		
1	Wooden Stair case complete — at	50	50		
11 28 3/4	Perfect Oak wood for wooden rail coat	4	44	12	5
144	Scaffolding and Sundries —		185	7	11
			202	7	6
	Total Rupees —				3080

Master Attendant Office

14 8

Enclosure 2 in a letter
from the Office of the
S. G. No 67 dated 10th
April 1867

To
The Secy to Government
D. P. Off
D. N. 1394/67

Estimate for constructing
additions & alterations
to Public Office at
Tubicorin

Master Attendants Office

4 $\frac{22\frac{1}{2}}{27}$	Regards Concrete	at	3		14	8	
148 $\frac{19\frac{1}{2}}{27}$	de Sand Stone in Chum	at	6		892	4	5
983 $\frac{1}{4}$	Sq feet flooring 12" square 3" thick hard Sand Stone in Chum per sq ft		6		58	15	11
723 $\frac{3}{4}$	Sq ft Terracing with bricks on edge Jelly 2 courses of flat Tiles & 3 coats of Plastering to the ceiling & top of Terrace per 100 Sq ft	at	28		202	10	4
1 $\frac{15\frac{1}{2}}{27}$	Regards Cornice work with hard Sand Stone in Chum	at	10		15	13	2
6 $\frac{8\frac{1}{2}}{27}$	Regards removing Old work	at	8		3	2	6
5017 $\frac{1}{2}$	Sq feet Plastering per 100 Sq ft	at	3	8	175	9	9
138 $\frac{65\frac{1}{2}}{144}$	Regards Wrought wood	at	3	8	484	9	4
55 $\frac{10\frac{1}{2}}{10}$	de Mango Planks	at	3		164	15	6
1	Door (4 $\frac{1}{2}$ x 6 $\frac{1}{2}$) half Venetian with frames hooks hinges bolts						
	de Complete supplied						
5	Windows (3 $\frac{1}{2}$ x 4 $\frac{1}{2}$) de de	at	20		100		
68 $\frac{20}{27}$	Regards Earth work	at	1		4	4	8
1 $\frac{10\frac{1}{2}}{27}$	de Sand Stone in Chum to arch door ventilators		3		4	2	8

Upper Story

51 $\frac{16\frac{1}{2}}{27}$	Regards Sand Stone in Chum	at	6		309	11	6
1522 $\frac{15\frac{1}{2}}{10}$	Square feet Plastering per 100 Sq ft		3	8	53	4	11
910	de Sloping Terrace to Veranda with two courses of flat Tiles bricks Jelly & 2 coats of Plastering per 100 Square feet	at	20		182		

28 $\frac{12}{100}$	Wrought wood _____ at	3	8	170	13	6	3086
900	Specify removing & replacing roof of Palmaria Rafter and Renders flat and Pan tiles with Cham borders with a portion of new materials per 100 Specify at	20		180			
4	Doors ($3\frac{1}{2} \times 6\frac{1}{2}$) half Venetian with frames hooks hinges bolts & complete _____ at	38		152			
3	Windows ($3\frac{1}{2} \times 4\frac{1}{2}$) do do at	20		60			
1	Wooden Stair Case Complete at	50		50			
8 $\frac{1275}{100}$	Specify Teak wood for wooden nails Sea golding and Sundries	4		35	8	7	
	Total Rupees			3516	13	6	
1378	Stone coping to Verandahs of Godown and Causeway Specify flooring & coping with granite stone with Cham under neath including Cart hire from Palamcottah to Tuticorin exclusive of the value of port stones which are to be supplied gratis per 100 Specify at	22		303	2	6	3820
	Amount of Estimate Rupees						6900

A. W. Webb

1st Range Office

Palamcottah

15th March 1867

Asst. Engineer in Charge

Off. Superintending Engineer

Asst. Engineer in Charge

1st Range Office

Tuticorin

No 69
Super. Engr. Office 8th D.
Madura 10th April 1867
Thru

Captain H. C. Prendergast R.E.
Off. Superintending Engineer 8th D.

Colonel C. A. Arden R.E.
Secretary to Government D.F.W.

Enclosure 3

1 Plan
1 Report
1 Estimate

With reference to G. O. No 3359
dated 20th October 1866. I have the honor
to submit the revised Estimate of Rs
6900— with plan & report for making
additions to the Public Offices at
Tuticorin. Provision has been made
for laying down a granite curb to the
Quatomo godowns verandah. and a
granite pavement from the Customs

House to the shore end of the jetty.

2 A sum of Rs 3545 was expended
on the buildings in the past year but
work is now suspended under para
79 of C.O. No 3938 of 14th December 1866.

I have &c

Wm Lumsden Captain R.E.
Off^r Superintending Engineer
8th Division.

Proceedings of the Madras Government

Under date the 27th April 1867

Had the following
From The Off^r Superintending Engineer 8th Division

A.E. dated 10th April 1867
No. 69

The Governor in Council sanctions the revised Estimate of Rs. 5900 submitted with this letter, and directs that the work, upon which Rs. 3545 are reported to have been expended up to 31st March, be completed with as little delay as possible from funds specially provided for it in the Budget Es-
timate of the Current Official year.

The S. Engr. gtd. with one
Accts Genl. ^{specific}
Controller ✓
Rev. Depld ✓

Recd 29/4/67

[Signature]

[Signature]

[Signature]

[Signature]

8th Division

[Signature]

[Signature]

[Signature]

Dated 10th April 1867

No. 3

[Signature]

revised Estimate of Rs.

5900 for making additions

to the Public Office at

Chelvarin.

No. 1257-27th April 1867.

No. 575

No. 1257-27th April 1867.

Public Works 1867 (Depart^{ts})

Pro. of Govt. for April

No. 1251

Pro. of the head & as Govt.
Of 27th April 1867

The revised estimate
of Rs. 6,900, for making addi-
tions to Public Offices, at
Tuticorin in the Tinnevely
District, sanctioned

M. 505-506

C. 185-24 June 1867 On 26th