

(1) Number of pages 854(2) Date of repair 2-5-67(3) Initials of the Referencer [Signature]

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.G.O. No. 1844-45- Press
Mis.

440-442

Dated 20-6-1867.

Not to be folded or roughly handled

No 440. Read the following Proceedings of the Board of Revenue, dated 21st May 1867, No. 3,141:—

Read the following letter from the Acting Collector of Nellore, to the Secretary to the Board of Revenue, dated 6th May 1867, No. 130.

1. I have the honour to forward, herewith, the plans and estimates for improvements to the irrigation works in the Pennair Delta, prepared by the Superintending Engineer at an outlay of Rupees 4,12,100, and request that they may be forwarded on to Government at as early a date as possible, with the Superintending Engineer's letter to the Secretary to Government, Public Works Department, inclosed. As Government have allotted Rupees 25,000 in the Budget estimate of the current year for the work, it is desirable that as early sanction as possible be obtained in order that work up to that amount may be executed before April next.

2. From the information I have collected, it appears that the irrigable area under the present project is Acres 77,121, of which 31,633 are either already irrigated, or unfit for cultivation. From the remainder, Acres 45,488, it is again necessary to deduct a large amount on account of land that for various causes may not be available. The Superintending Engineer has, accordingly, taken Acres 25,500 only as the area to be benefited by these works. Allowing Rupees 4 per acre for water cess, according to Mr. Dykes' proposal, and excluding the dry or punjah shist which would be levied on waste brought under cultivation, the proposed expenditure on these works, viz, Rupees 4,12,100, is calculated to secure a revenue of Rupees 1,02,000 per annum, i. e., 24 74 per cent. on the outlay. I, therefore, trust that the Board will recommend that the sanction of Government be acceded to this project in its present form, as the work promises to be so remunerative.

From the Superintending Engineer, 2nd Division, to the Secretary to Government, Department of Public Works, dated Masulipatam, 3rd May 1867, No. 17.

1. I have the honour to forward plans and estimates as per margin, relative to a project for extending the irrigation from the anicut across the Pennair at Nellore, amounting to Rupees 4,12,100.

- Inclosures *
- 24 Surveys and plans as per list attached
 - 27 Detailed estimates
 - 30 Abstract do.
 - 15 Specification Reports
 - 1 General abstract estimate.
 - 1 Synopsis of the general state of Pennair river from 1861 to 1865
 - 1 Statement of rise of do.
 - 1 Revenue Return

* By Banghy

2. The surveys and levels were commenced last year under my direction by R. Smith, Esq, Executive Engineer at Nellore, to whose able assistance I am indebted for much the greater portion of the labour involved in bringing forward the project. The arrangement of the details, the calculations of the dimensions and discharges of the channels, and the designs, most of the masonry works, are his entirely. The surveys and levels were made by Overseer Cooposawmy Raju, who has proved himself a very efficient Surveyor.

Proceedings of the Madras Government, Public Works Department.
20th June 1867.

3. As I considered that the channels hitherto executed in the Nellore District had been designed too much on the supposition that the Pennair was a constant flowing river, instead of an uncertain stream, having the character of a mountain torrent, rather than of an even flowing river, I requested Mr. Smith to make the channels considerably in excess of what would have been necessary had it been otherwise. I enclose a synopsis and statement of the general state of the Pennair from 1831 to 1865, inclusive, from which it appears that on an average for only 61 days per annum, the water was flush with, or above the crown of the anicut. It is, therefore, evident that to fill the numerous tanks in the Delta so as to receive sufficient to supply two cubic yards per hour per acre, the channels should be capable of conveying a very large quantity during the freshes, and those now projected accordingly, have capacity sufficient to carry from five to six times the water which would be necessary, if the lands were cultivated direct from the channels.

4. The principal features in the present scheme are:—

First—The enlargement of the head sluice by lowering the existing sluices two feet for four feet of their breadth, and the construction of an auxiliary sluice of 6 vents of 3½ feet each, at the site of the old head, which was closed some years ago. This is desirable, as otherwise the loss of head during low freshes by contrasted head works would considerably affect the supply.

Second—The deepening of the main feeder two feet in preference to widening it. The velocity generated* will entail the necessity of pitching the side slopes

* 220 feet per minute.
with stone for about 3,000 yards, where sand is traversed; but on account of the close proximity of the heavy banks already formed by the excavation of the channels, and the desirability of obtaining a maximum supply in low freshes or when the water is below the crest of the anicut, this has been considered the expedient course to adopt. The estimates for these two improvements amount to Rupees 15,300.

Third—The construction of regulating sluices at the heads of the Jaffer Sub and Kistnapatam channels. By the aid of these structures, and the regulating sluices for the Survapully and Wolluru branches in the sixth mile, perfect command over all the main irrigating ducts of the Delta will be obtained within a radius of 3½ miles from Nellore.

Estimate, Rupees 90,300.

Fourth—The deepening of the Survapully new cut, and the enlargement and improving of the old Ramerreddy channel, and the masonry works connected with it as far as the sixth mile from the head sluices.

Estimate, Rupees 1,26,500

Fifth—The construction of a new channel from the sixth mile slitting the high ground by Kulloo pully, Bommichitty, and Gogumandy, to supply the Survapully reservoir with the necessary irrigation and drainage works.

Sixth—The construction of a main reservoir at Survapully, by the enlargement of the present tank, which shall contain 525,80,000 cubic yards of water. Mr. Smith calculates that after supplying "all demands when the water is flush with the crown of the anicut, the channels will be found sufficiently capacious to provide 18,36,400 cubic yards daily, which would enable the reservoir to be filled "in 23½ days, excluding loss by evaporation," and remarks "that as the direct daily

Proceedings of the Madras Government, Public Works Department.
20th June 1867.

"supply can only be depended on for 61 days, annually, and as the reservoir must supply any deficiency that may arise during the other 80 days, the total quantity during the period would be 956,39,400 cubic yards of water, or 95,20,600 cubic yards less than the reservoir would contain on being filled a second time each season."

Seventh—The abandonment of the Yepuru, Kamini, Pudiparty, and Tutty tanks, which after the construction of the Survapully reservoir and the Wolluru channel, respectively, will no longer be needed. Their beds can then be cultivated, and the irrigated area considerably increased.

Estimate, Rupees 33,440

Eighth—The construction of a channel from the Survapully channel to the Idagally tank, so that when water is available, the opportunity may be taken to fill it in a short time by allowing its channel to flow 7 feet deep. A sluice has been provided for it to regulate the supply, and permit the water returning into the channel.

Estimate, Rupees 27,810.

Ninth—The construction of an Irrigation channel from the sixth mile to Wolluru tank, and in continuation to near Gudiving, and the Kundlairoo river irrigating the land as far as the main drainage channel.

Tenth—The conversion of the present supply channel of the Survapully tank into a main drainage, which on being extended will effectually take off the water from the irrigated fields under the Survapully tank and the Wolluru channel, and relieve a considerable tract of land now swamped

5 It may eventually be found that the supply is sufficient to justify an extension of the channel from the Idagally tank in the direction of Trunk Road No. 6. At first it was intended to construct a high level channel from near the present head of the Survapully branch, which should have supplied all the tanks in the neighbourhood of Puddoor, Suduhudi, Kullivapully, &c; but as those tanks already generally receive a fair supply from the Pottitla, and the expense would have been very great, I decided that the idea should not be further entertained as regards the present project.

6. In explanation of the necessity of the principal masonry works which I have not yet noticed, I beg to add that the new ridge proposed at Stonhousepett is rendered imperative, owing to the impossibility of lowering the floors of the present structure. An attempt was made some years ago to do this, and the result was that the arch became considerably cracked.

7. The surplus sluice in the sixth mile is designed to pass off into the main drain, (alluded as the tenth chief feature the scheme,) the local drainage of 18 square miles of country that falls into the Survapully channel at its junction with the old Ramerreddy.

8 The falls adjacent to the Pudipar, Yepuru, Kamini, and Tutty tanks are designed to adjust the difference between slopes of the channel and the country when the tanks are abandoned, otherwise the tanks would suffer severely from erosion.

*Proceedings of the Madras Government, Public Works Department,
20th June 1867.*

9 The rates entered for the masonry works have been carefully fixed by the Executive Officer, with reference to the distance the materials have to be carried, and the style of work proposed.

10. The irrigable area under the present project, as shown by the Collector's statement attached, is Acres 77,121, of which 31,633 are either watered already or are not fit for cultivation. From the remainder, (45,488 acres,) however, it is necessary, in the absence of specific information, to deduct a very large amount on account of land that, from various causes, may not be available, and I, therefore, propose estimating the receipts on 25,500 acres only. Allowing 4 Rupees per acre for water cess, and excluding the dry shist which would be levied on waste to be brought under cultivation, the expenditure now contemplated would secure a revenue of 1,02,000 Rupees per annum, i. e., 24 74 per cent. on the outlay. Under these circumstances, I therefore lay the project before Government with great confidence.

11. Rupees 25,000 have been allotted in the current year's Budget (Item 148,) and pending the formal sanction of the Government of India to the scheme, I request permission for the Executive Officer to spend a portion of the money in collection of materials, &c., so that the present working season may not be lost.

ENCLOSURES Nos 2 to 101.—Plans and Estimates.

Submitted for the early sanction of Government accordingly.

Specification to accompany the Plan and Estimate for constructing the auxiliary Head Sluice.

1. The sluice will consist of six vents, 10 feet $\times$ 3 $\frac{1}{2}$ feet. The front wings to be 26 feet in height for a length of 10 feet, and then decrease by steps of a foot, for 16 feet, measured horizontally, which will reduce the height to 9 feet. The face walls to be 13 feet 7 $\frac{1}{2}$ inches in height, the breadth at bottom and top being 5 feet and 2 feet respectively. The space between the face walls to be filled in with concrete.

2. The laterite at the site to be cut down to the required depth 20-49 feet above mean tide, and the superstructure built on it; no masonry is necessary in the foundation.

3. The wings in rear to be built on the surface of the laterite, the height being, on the average, 10 feet, and the mean breadth 3 $\frac{1}{2}$ feet.

4. The vents to be provided with oak shutters, 4 feet $\times$ 3 inches $\times$ 11 $\frac{1}{2}$ feet, as $\times$ $\frac{1}{2}$ inch on the inner face to reduce friction, the working gear will consist of a screw $\frac{3}{4}$ ths of an inch pitch; a horizontal teak beam 1 foot square laid over the shutter, through which the extremity of the screw will pass and project 6 inches under the shutter for elevating or depressing the screw. An iron plate 9 inches $\times$ 9 inches $\times$ $\frac{1}{2}$ inch will be let into the beam to a depth of half an inch. The nut to be worked by a movable lever 24 inches in length. The beam will be retained in its position by iron ties built into the masonry.

5. The masonry to be of dressed laterite in chunam.

*Proceedings of the Madras Government, Public Works Department,
20th June 1867.*

DETAILED ESTIMATE No. 4.

PENNAIR DELTA.

Constructing an auxiliary Head Sluice, enlarging old Channel, and deepening the Main Feeder from the existing Head Sluice to the head of the Sarvapully Channel.

Particulars of Work.	MEASUREMENT.				Cubical contents.	Rates per Cubic yard.		
	Length.	Breadth.	Height or Depth.	No.				
	Feet.	Feet.	Feet.		Feet.	RS.	A.	P.
HEAD SLUICE.								
<i>Enlarging old Channel.</i>								
Laterite cutting ...	30	42	2	1	2,520	0	8	0
Clearing silt ...	30	31	3 $\frac{3}{4}$	1	3,410	0	1	6
Laterite cutting ...	26	42	2	1	2,184	0	8	0
Do do ...	27	23	2	1	1,242	0	8	0
Do do ...	26	11	17 $\frac{1}{2}$	1	5,076 $\frac{1}{2}$	0	8	0
Do do ...	26	11	8	1	2,288	0	1	6
Earth-work ...	53	23	3 $\frac{3}{4}$	1	4,469 $\frac{3}{4}$	0	1	6
Clearing silt ...	27	1 $\frac{1}{2}$	8	1	324	0	8	0
Removing and re-packing laterite revetment ...	45	24 $\frac{1}{2}$	2	1	2,182 $\frac{1}{2}$	0	8	0
Laterite cutting ...	45	1 $\frac{1}{2}$	15 $\frac{1}{2}$	1	1,220 $\frac{5}{8}$	0	8	0
Do do ...	45	1 $\frac{1}{2}$	10 $\frac{1}{4}$	1	807 $\frac{3}{8}$	0	1	6
Earth-work ...	45	24 $\frac{1}{2}$	3	1	3,273 $\frac{1}{2}$	0	1	6
Clearing silt ...	45	1 $\frac{1}{2}$	10 $\frac{1}{4}$	1	691 $\frac{1}{8}$	0	8	0
Removing and re-packing laterite revetment ...	45	26	2	1	2,340	0	8	0
Laterite cutting ...	22	17	$\frac{1}{2}$	1	192 $\frac{1}{2}$	0	8	6
Do do ...	45	26	3 $\frac{1}{2}$	1	4,387 $\frac{3}{8}$	0	1	0
Clearing silt ...	90	26	2	1	4,680	0	8	6
Laterite cutting ...	90	27	3 $\frac{3}{4}$	1	8,910	0	1	0
Clearing silt ...	145	26	2	1	7,510	0	8	6
Laterite cutting ...	145	27	3 $\frac{3}{4}$	1	14,355	0	1	6
Clearing silt ...	27	92	13 $\frac{3}{8}$	1	34,332	0	1	6
Removing bund								
Demolishing bridge over old supplying channel, and clearing the latter out underneath it	...	...	...	...	...	...		
Connecting existing and proposed head sluices by a parapet wall	276	2 $\frac{1}{2}$	3	...	2,070			
Foundation	276	1 $\frac{1}{2}$	3	...	1,242			
Wall above								
Total cubic feet of laterite in chunam	...	...	...	...	3,312			
Lowering floor of head sluice	...	...	...	...	80	1	4	0
Laterite cutting	...	...	...	...	...	...		
Altering shutters	...	...	...	...	...	...		
<i>Deepening Main Feeder.</i>								
Laterite cutting ...	1,000	52	2	...	1,04,000	0	8	0
Earth-work ...	1,000	20	1 $\frac{1}{2}$	...	30,000	0	1	6
Do do ...	1,000	34	1	...	34,000	0	1	6
Do do ...	1,000	40	1	...	40,000	0	1	6
Do do ...	900	75	3	...	2,02,500	0	1	6
Do do ...	900	30	1 $\frac{1}{2}$	...	40,500	0	1	6
Do do ...	900	23	1 $\frac{1}{2}$	2	62,100	0	2	0
Rubble pitching	900	23	1	...	41,400	0	8	0
Gravel backing	...	...	...	...	...	...		
Compensation for land...	...	...	...	...	...	...		

Proceedings of the Madras Government, Public Works Department,
20th June 1867

ABSTRACT ESTIMATE No. 4.

Quantities.	Description of Work.	Rate.	Amount	Total.
		RS. A. P.	RS. A. P.	RS. A. P.
1	Head sluice—vide separate estimate. <i>Enlarging old channel.</i>	...	...	6,350 0 0
1,118	Cubic yards of laterite cutting	0 8 0	559 0 0	
2,710	Do. of clearing silt	0 1 6	254 1 0	
114	Do. of earth-work	0 1 0	7 2 0	820 3 0
	Demolishing bridge over old supplying channel and clearing the latter out underneath it	...	...	125 0 0
3,312	Connecting existing and proposed head sluices by a parapet wall.	...	...	
	Cubic feet of laterite in chunam	0 2 9	569 4 0	
	Deduct value of old materials	...	216 0 0	3 3 4 0
	Lowering floor of head sluice	...	...	100 0 0
	Altering shutters	...	...	216 0 0
3,852	<i>Deepening Main Feeder.</i>	...	...	
12,852	Cubic yards of laterite cutting	0 8 0	1,926 0 0	
2,300	Do. of earth-work	0 1 6	1,204 14 0	
1,533	Do. of rubble pitching	1 2 0	2,547 8 0	
	Do. of gravel backing	0 8 0	766 10 8	
	Compensation for one tiled and a small compound	...	...	6,495 0 8
	Sundries	...	...	800 0 0
		...	...	50 8 4
	Total estimate	...	...	15,300 0 0

DETAILED ESTIMATE No. 4.

PENNAIR DELTA.

Constructing an auxiliary Head Sluice adjacent to the Anicut.

Particulars of Work.	MEASUREMENT.				Cubical contents.
	Length.	Breadth.	Height or Depth.	Number.	
	Feet.	Feet.	Feet.		Feet.
Concrete ...	35½	14	12½	...	6,251½
				Total...	6,151½
Abutments	23½	4	10	2	1,880
Piers	27½	2½	10	5	3,416½
Caps	2½	2½	2½	5	67½
Skew backs	23	2½	½	5	143½
Do.	23	4	½	2	92
Spandril	41½	23	½	...	715½
Face walls	41½	3½	13½	2	3,958½
Do.	41½	2	13½	...	1,130½

Proceedings of the Madras Government, Public Works Department,
20th June 1867.

DETAILED ESTIMATE No. 4.—(Concluded)

Particulars of Work.	MEASUREMENT.				Cubical contents.
	Length.	Breadth.	Height or Depth.	Number.	
	Feet.	Feet.	Feet.		Feet.
Side walls	23½	3½	12½	2	1,879½
Portion of cut-waters	2½	2½	16	5	375½
Front wings	10	6½	26	2	3,380
Do.	15	5	18	2	2,700
Do.	10	3½	10	2	700
Rear wings	26	3½	10	2	1,820
String course	124	1½	¾	...	23½
Parapet	200	1½	3	...	900
Arch work	23	5½	1½	6	1,190½
				Total...	24,373½
Pointing	...	...	...	...	87
Earth-work	...	...	...	...	1,248
Metaling	...	...	...	...	66½
Teak-wood beam	...	...	...	...	35½
Teak-wood shutters with working gear	...	...	...	...	6
Centering	...	...	...	...	...
Sundries	...	...	...	...	...

ABSTRACT ESTIMATE No. 4.

Quantities	Description of Work.	Rate	Amount	Total.
		RS. A. P.	RS. A. P.	RS.
6,216	Cubic feet of concrete	0 2 0	777 0 0	
24,372	Do. of laterite in chunam	0 2 9	4,189 1 9	
87	Squares of pointing	2 0 0	174 0 0	
1,248	Cubic yards of earth-work	0 4 0	312 0 0	
66½	Do. of metaling	0 4 0	16 10 8	
35½	Cubic feet of teak-wood beam	3 8 0	124 4 0	
6	Teak-wood shutters with working gear	78 0 0	468 0 0	
	Centering	...	150 0 0	
	Sundries	...	138 15 7	
				6,350

Specification to accompany the Plan and Estimate for the Regulating sluice at the head of the Jaffer Sarb's Channel.

1. The sluice to consist of five vents of 6 feet span. The front wings to be 13 feet 6 inches in height, the breadth at bottom and top to be 5 feet 4 inches and 1 foot 6 inches respectively, the foundations of pier to be laid at a depth of 4 feet, the average breadth being 4 feet 3 inches and of abutments 6 feet. The rear wings to be 13 feet in height at the abutments and 9 feet at the returns, the average section

*Proceedings of the Madras Government, Public Works Department,
20th June 1867.*

at the former point being $3\frac{1}{2}$, and $2\frac{1}{2}$ at the latter; the foundation will have an uniform depth of 6 feet, but the section will vary from an average thickness of $6\frac{1}{2}$ at the abutments to 5 at the returns.

2. The flooring in the bays to be inverts of $1\frac{1}{2}$ in thickness, resting on concrete 1 foot thick. The flooring from the bays to the front and rear retaining walls will be $1\frac{1}{2}$ feet in depth, with a bed of concrete 1 foot in thickness. The piers on the up-stream side will project 3 feet to admit of small arches being turned to facilitate the working of the shutters; these will consist of teak planks $6\frac{1}{2} \times 3$ inches $\times 13\frac{1}{2}$ feet. Firm iron bars, varying from 4 inches to $2\frac{1}{2}$ in diameter, to be fixed in each vent to strengthen the shutters, and enable them to be worked easily. The rubble apron in rear to be $35 \times 20 \times 2\frac{1}{2}$, that in front 58 feet $\times 12$ feet $\times 1\frac{1}{2}$. The side slopes of the channel, in rear of the sluice, to be protected for a length of 20 by rubble pitching. The whole of the masonry to be built of dressed laterite in chunam. The floor of the sluice, to be 29.05 feet above mean tide; the level of this has been fixed 2 feet below the bed of the channel, to enable it to be lowered 2 feet at any future time, should it be desirable to increase the discharge in the Jaffer Saib's branch.

DETAILED ESTIMATE No. 4.

PENNAIR DELTA.

Constructing a Regulating Sluice at the head of Jaffer Saib's Channel.

Particulars of Work.	MEASUREMENT.				Cubical contents.
	Length	Breadth	Height or Depth	No.	
	Feet.	Feet	Feet.		Feet.
Concrete—Below Inverts	$9\frac{1}{2}$	$4\frac{1}{2}$	1	3	$117\frac{3}{4}$
Front apron	$9\frac{1}{2}$	$4\frac{1}{2}$	1	2	80
Rear do	$39\frac{1}{2}$	7	1		$276\frac{1}{2}$
Front retaining wall	$41\frac{1}{2}$	$21\frac{5}{8}$	1		$889\frac{1}{2}$
Spandril	$50\frac{1}{2}$	$4\frac{1}{2}$	1		$227\frac{1}{2}$
Total ..	20	$5\frac{1}{2}$	$2\frac{1}{2}$		275
Foundation.—Abutments ..	$9\frac{1}{2}$	$6\frac{1}{2}$	6	2	$1,857\frac{1}{2}$
Piers ..	$12\frac{1}{2}$	$3\frac{1}{2}$	4	4	741
Do front portion	$4\frac{1}{2}$	$3\frac{1}{2}$	4	4	$757\frac{1}{2}$
Front wings	27	$6\frac{1}{2}$	$5\frac{1}{2}$	2	$277\frac{1}{2}$
Rear do	24	$6\frac{1}{2}$	6	2	$2,029\frac{1}{2}$
Returns	$9\frac{1}{2}$	5	6	2	1,872
Front retaining wall	$40\frac{1}{2}$	$2\frac{1}{2}$	$4\frac{1}{2}$	2	585
Rear do	$34\frac{1}{2}$	$2\frac{1}{2}$	6	1	$568\frac{1}{2}$
Superstructure—Abutments ..	$9\frac{1}{2}$	$3\frac{1}{2}$	9	1	$521\frac{1}{2}$
Piers	11	$2\frac{1}{2}$	9	2	619
Do front portion	$4\frac{1}{2}$	$2\frac{1}{2}$	$9\frac{1}{2}$	4	99
Caps	$2\frac{1}{2}$	$2\frac{1}{2}$	2	4	$427\frac{1}{2}$
Skew backs	$10\frac{1}{2}$	$2\frac{1}{2}$	$13\frac{1}{2}$	4	95
Front wings	$26\frac{1}{2}$	$3\frac{1}{2}$	13	2	$2,421\frac{1}{2}$
Coping	$28\frac{1}{2}$	2	11	2	84
Rear wings	24	$2\frac{1}{2}$	11	2	1,518

*Proceedings of the Madras Government, Public Works Department,
20th June 1867.*

DETAILED ESTIMATE No. 4—(Concluded)

Particulars of Work	MEASUREMENT.				Cubical contents.
	Length.	Breadth.	Height or Depth	No	
	Feet.	Feet.	Feet.		Feet.
Superstructure—Coping	$26\frac{1}{2}$	2	$\frac{3}{4}$	2	78
Returns	$12\frac{1}{2}$	$2\frac{1}{2}$	9	2	$562\frac{1}{2}$
Coping	$14\frac{1}{2}$	2	$\frac{3}{4}$	2	42
Backing to arch	11	$2\frac{1}{2}$	$1\frac{1}{2}$	2	$27\frac{1}{2}$
Face walls	$23\frac{1}{2}$	$1\frac{1}{2}$	1	2	$160\frac{1}{2}$
Blocking courses	$44\frac{1}{2}$	$\frac{3}{4}$	1	2	111
Parapets	44	1	1	5	66
Arch work	$9\frac{1}{2}$	9	1	5	$427\frac{1}{2}$
Flooring	1	9	$1\frac{1}{2}$	5	45
Total	$39\frac{1}{2}$	$6\frac{1}{2}$	$1\frac{1}{2}$		$463\frac{1}{2}$
	$41\frac{1}{2}$	$7\frac{1}{2}$	$1\frac{1}{2}$		$444\frac{1}{2}$
	41	22	$1\frac{1}{2}$		$1,357\frac{1}{2}$
	..			..	17,321
Rubble stone (laterite)	85	20	$2\frac{1}{2}$		1,750
	58	12	$1\frac{1}{2}$	..	1,044
	20	17	2	2	1,360
					4,154
					$153\frac{1}{2}$
					78
Pointing ..					1,470
Earth-work					$9\frac{1}{2}$
Metaling					150
Iron bars... ..					$109\frac{1}{2}$
Shutters	$6\frac{1}{2}$	3	$13\frac{1}{2}$	5	
Centering ..					
Baling					
Sundries					

ABSTRACT ESTIMATE No. 4.

Quantities	Description of Work.	Rate			Amount.			Total.		
		RS	A.	P.	RS	A.	P.	RS.	A.	P.
1,857	Cubic feet of concrete	0	2	0	232	3	8			
17,321	Do. of laterite in chunam	0	2	9	2,977	0	9			
78	Squares, pointing	2	0	0	156	0	0			
153	Cubic yards of rubble stone (laterite)	1	2	0	173	1	4			
1,470	Do. of earth-work	0	1	0	91	14	0			
9	Do. of metaling	0	4	0	2	6	0			
109	Cubic feet of teak-wood shutters	3	8	0	383	14	6			
150	R feet of iron bars	...	...	...	184	0	0			
	Centering	...	...	...	150	0	0			
	Baling	...	...	...	250	0	0			
		...	...	...	4,600	8	3			
		...	...	...	119	7	9			
	Sundries							4,720	0	0

DETAILED ESTIMATE No 4.

PENNAIR DELTA.

Deepening the Sarvapully New Cut, and improving the old Ramireddy Channel.

Proceedings of the Madras Government, Public Works Department,
20th June 1867.

No. of Cross Sections.	Particulars of Work.	MEASUREMENTS					WORK TO BE EXECUTED.					Ratio per Cubic yard.	
		Length.	Breadth.	Height or Depth.	Number.	Cubical contents.	Cutting	Banking	Rubble Pitching	Gravel Backing	Turfing		
1	Cutting ..	660	68	12	1	4,48,800	2,07,900	...	...	...	Feet.	Feet.	IS A F
	Deduct present work ..	000	73	5	1	2,40,900	16,500	...	...	...	...	...	0 1 0
	Cutting ..	660	25	1	1	...	18,480	...	...	...	...	...	0 1 0
	Do. ..	660	14	2	1	...	...	...	...	...	16,500	...	0 1 0
	Turfing ..	660	25	...	1	...	...	...	...	...	9,240	...	0 1 4
	Do. ..	660	14	...	1	...	...	...	...	...	...	...	0 1 4
	Rubble pitching	660	23	1 1/2	2	...	...	...	45,540	30,360	...	...	1 2 0
	Gravel backing	660	23	1	2	8,97,600	...	...	...	...	...	...	0 8 0
	Cutting ..	1,320	68	10	1	5,08,200	3,89,400	...	...	...	...	...	0 1 6
	Deduct present work ..	1,320	77	5	1	...	51,480	...	...	...	17,160	...	0 1 0
2	Cutting ..	1,320	13	3	1	...	...	...	...	...	...	...	0 1 0
	Turfing ..	1,320	13	...	1	...	...	...	...	...	...	...	0 1 4
	Rubble pitching	1,320	23	1 1/2	2	...	...	...	91,080	60,720	...	...	1 2 0
	Gravel backing	1,320	23	1	2	8,97,600	...	...	...	...	...	...	0 8 0
	Cutting ..	1,320	68	10	1	3,11,520	5,86,080	...	...	...	...	...	0 1 6
	Deduct present work ..	1,320	59	4	1	...	...	...	...	...	...	...	1 2 0
	Rubble pitching	1,320	23	1 1/2	2	...	...	...	91,080	60,720	...	...	0 8 0
	Gravel backing	1,320	23	1	2	...	...	...	...	...	...	...	0 8 0
	Cutting ..	1,320	68	10	1	...	...	...	...	...	...	...	0 1 6
	Deduct present work ..	1,320	77	5	1	...	...	...	...	...	...	...	1 2 0
3	Cutting ..	1,320	13	3	1	...	...	...	...	...	...	...	0 1 0
	Turfing ..	1,320	13	...	1	...	...	...	...	...	...	...	0 1 4
	Rubble pitching	1,320	23	1 1/2	2	...	...	...	91,080	60,720	...	...	1 2 0
	Gravel backing	1,320	23	1	2	8,97,600	...	...	...	...	...	...	0 8 0
	Cutting ..	1,320	68	10	1	3,11,520	5,86,080	...	...	...	...	...	0 1 6
	Deduct present work ..	1,320	59	4	1	...	...	...	...	...	...	...	1 2 0
	Rubble pitching	1,320	23	1 1/2	2	...	...	...	91,080	60,720	...	...	0 8 0
	Gravel backing	1,320	23	1	2	...	...	...	...	...	...	...	0 8 0
	Cutting ..	1,320	68	10	1	...	...	...	...	...	...	...	0 1 6
	Deduct present work ..	1,320	77	5	1	...	...	...	...	...	...	...	1 2 0

Proceedings of the Madras Government, Public Works Department,
20th June 1867.

No. of Cross Sections.	Particulars of Work.	Length.	Breadth.	Height or Depth.	Number.	Cubical contents.	Cutting	Banking	Rubble Pitching	Gravel Backing	Turfing	Ratio per Cubic yard.
		Feet.	Feet.	Feet.		Feet	Feet.	Feet	Feet.	Feet	Feet.	IS A F
4	Cutting ..	165	68	10	1	1,12,200	4,40,220	...	89,010	59,340	...	0 1 6
	Bridge of two Arches.	...	...	...	...	...	...	...	...	...	...	0 1 2
	Cutting ..	1,155	68	10	1	7,85,400	...	...	...	...	...	0 8 0
	Deduct present work ..	1,320	77	4 1/2	1	8,97,600	...	...	...	...	...	0 1 0
	Rubble pitching	1,290	23	1 1/2	2	4,57,380	...	...	...	...	...	0 1 0
	Gravel backing	1,290	23	1	2	...	...	...	...	...	...	0 0 10
	Cutting ..	462	68	10	1	3,14,160	...	...	90,252	60,168	...	0 0 10
	Iron Aqueduct piers to be demolished and re-built.	...	...	...	...	...	...	...	...	...	...	0 1 2
	Cutting ..	858	68	10	1	5,83,440	4,33,620	...	...	...	...	0 8 0
	Deduct present work ..	1,320	74	4 1/2	1	8,97,600	39,600	...	...	...	...	0 1 0
5	Cutting ..	1,320	15	2	1	...	25,740	...	...	...	...	0 0 10
	Do. ..	1,320	13	1 1/2	1	...	...	...	...	...	...	0 1 2
	Turfing ..	1,320	15	...	1	...	...	...	...	...	...	0 0 10
	Do. ..	1,320	13	...	1	...	...	...	...	...	...	0 1 2
	Rubble pitching	1,308	23	1 1/2	2	...	...	...	...	...	...	0 8 0
	Gravel backing	1,308	23	1	2	5,12,820	...	...	...	...	...	0 1 0
	Cutting ..	814	68	10	1	...	...	...	...	...	...	0 4 0
	Iron Aqueduct to be substituted for Syphon	...	...	...	...	...	...	...	...	...	...	0 2 0
	Cutting ..	506	63	10	1	318,780	483,100	...	...	...	...	0 1 0
	Deduct present work ..	1,320	70	3 1/2	1	831,600	13,860	...	...	...	...	0 1 0
6	Cutting ..	1,320	7	1 1/2	1	...	15,840	...	...	...	...	0 1 0
	Do. ..	1,320	8	1 1/2	1	...	...	...	...	...	...	0 1 0
	Latente cutting	1,320	63	10	1	831,600	...	...	...	...	...	0 1 0
	Deduct present work ..	1,320	64	4	1	337,920	493,680	...	...	...	...	0 4 0
	Cutting ..	1,320	7	1 1/2	1	...	...	...	...	...	...	0 1 0
	Do. ..	1,320	8	1 1/2	1	...	...	...	...	...	...	0 1 0
	Latente cutting	1,320	63	10	1	831,600	...	...	...	...	...	0 1 0
	Deduct present work ..	1,320	64	4	1	337,920	493,680	...	...	...	...	0 4 0
	Cutting ..	1,320	7	1 1/2	1	...	...	...	...	...	...	0 1 0
	Do. ..	1,320	8	1 1/2	1	...	...	...	...	...	...	0 1 0
7	Cutting ..	1,320	7	1 1/2	1	...	...	...	...	...	...	0 1 0
	Do. ..	1,320	8	1 1/2	1	...	...	...	...	...	...	0 1 0
	Latente cutting	1,320	63	10	1	831,600	...	...	...	...	...	0 1 0
	Deduct present work ..	1,320	64	4	1	337,920	493,680	...	...	...	...	0 4 0
	Cutting ..	1,320	7	1 1/2	1	...	...	...	...	...	...	0 1 0
	Do. ..	1,320	8	1 1/2	1	...	...	...	...	...	...	0 1 0
	Latente cutting	1,320	63	10	1	831,600	...	...	...	...	...	0 1 0
	Deduct present work ..	1,320	64	4	1	337,920	493,680	...	...	...	...	0 4 0
	Cutting ..	1,320	7	1 1/2	1	...	...	...	...	...	...	0 1 0
	Do. ..	1,320	8	1 1/2	1	...	...	...	...	...	...	0 1 0

DETAILED ESTIMATE No. 4.—(Continued)
PENNAIR DELTA
 Deepening the Sarvapully New Cut, and improving the old Ramireddy Channel.

Proceedings of the Madras Government, Public Works Department,
 20th June 1867.

Deepening the Sarvaipany River

No of Cross Sections.	Particulars of Work.	MEASUREMENTS.					WORK TO BE EXECUTED					Rate per Cubic yard.
		Length.	Breadth.	Height or Depth.	Number.	Cubical contents.	Cutting.	Banking.	Rubble Pitching.	Gravel Backing.	Turfing.	
8	Cutting...	Feet.	Feet	Feet		Feet.	Feet.	Feet.	Feet.	Feet.	Feet.	Rs. A. P.
	Do. ...	1,320	7	2	1	..	18,480	..	..	..	..	0 2 6
	Do. ...	1,320	4	2	1	201,960	10,560	..	..	..	..	0 2 6
	Laterite cutting ...	374	54	10	1	..	..	..	..	..	..	..
	Iron Aqueduct to be substituted for Syphon											
	Cutting ...	187	54	10	1	100,950	..	..	..	..	..	..
	Bridge Floor to be lowered.											
	Cutting ...	759	54	10	1	409,860	..	..	..	..	..	..
	Deduct present work ..	1,320	64	4½	1	712,800	332,640	..	..	..	..	0 4 0
	Laterite cutting	1,320	54	10	1	319,770	..	..	..	..	..	0 4 0
	Deduct present work ..	1,320	51	4½	1	393,030	9,210	..	..	..	..	0 1 6
	Cutting ...	1,320	7	1	1	..	13,200	..	..	..	..	0 1 6
10	Do. ...	1,320	4	2½	1	213,840	..	..	..	..	..	..
	Do. ...	396	54	10	1	..	..	..	..	..	..	..
	Iron Aqueduct to be substituted for Syphon.											
	Cutting ...	924	54	10	1	498,960	..	..	..	..	..	..

Proceedings of the Madras Government, Public Works Department.
 20th June 1867.

	Deduct present work	1,320	55	4½	1	326,700																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																	
--	---------------------	-------	----	----	---	---------	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

*Proceedings of the Madras Government, Public Works Department,
20th June 1867.*

ABSTRACT ESTIMATE No. 4.

ABSTRACT ESTIMATE No. 4.												
Quantities.	Description of Work.	Rate			Amount.			Total				
		RS.	A.	P.	RS	A.	P.	RS.	A	P		
60,439	Cubic yards of laterite cutting ...	0	4	0	15,109	12	0	40,037	1	11		
1,956	" of gravel do. ...	0	2	6	395	10	0					
49,131	" of do. do. ...	0	2	0	6,141	10	0					
1,37,961	" of cutting	0	1	6	12,933	13	6					
10,853	" of do. ...	0	1	4	904	6	8					
51,227	" of do. ...	0	1	3	4,002	1	9					
1,650	" of do. ...	0	1	2	120	5	0					
8,311	" of do. ...	0	1	0	519	7	0					
3,21,530												
11,244	" of banking ...	0	1	3	878	7	0				2,347	2
12,027	" of do. ...	0	1	2	876	15	6					
8,213	" of do. ...	0	1	1	556	1	5					
685	" of do. ...	0	0	10	35	10	10					
32,169												
15,072½	" of rubble pitching ...	1	2	0	16,956	12	0	16,956	12	0		
10,018	" of gravel backing ...	0	8	0	5,024	0	0					
4,767	Square yards of turfing ...	0	1	4	397	4	0					
4,107	" of do. ...	0	0	10	213	14	6	5,024	0	0		
71,866	" of do. ...	0	0	4	1,497	3	4					
80,740								2,108	5	10		
2	Compensation for land	100	0	0	...			200	0	0		
	Distributing channels				...			200	0	0		
	Masonry Works.—Vide separate estimates											
1	Bridge of 2 arches across the Sarvapully channel, near Stonehousepet ..											
1	Demolishing and re-building the iron aqueduct piers							8,300	0	0		
1	Substituting iron aqueduct for syphon No. 1							680	0	0		
1	Do. do. No. 2							2,100	0	0		
1	Lowering floor of Kristnapatnam road bridge							2,100	0	0		
1	Substituting iron aqueduct for syphon No. 3							70	0	0		
1	Converting bridge across head of Kristnapatnam channel into a head sluice for that branch							2,100	0	0		
2	Irrigation sluices, vide Plan No. 1 ..	250	0	0	...			990	0	0		
1	Constructing a surplus sluice, adjacent to the Sarvapully branch head sluice, across the old Ramreddi channel				...			500	0	0		
	Sundries							6,470	0	0		
	Total Estimate ..							116	9	6		
								90,300	0	0		

*Proceedings of the Madras Government, Public Works Department.
20th June 1867.*

Specification to accompany the Plan and Estimate for constructing a bridge over the Sarvapully Channel near Stonehousepetta.

The bridge to consist of 2 arches of 30 feet span; the rise being 7½ feet; the flooring to be an invert with a versed sine of 1½ feet; the invert will rest on a bed of concrete 6 inches in thickness; the piers to be 5 feet in breadth at bottom, with a batter of 6 inches on each side; the abutment to be 6 feet in thickness, and 12 feet in height; the thickness of the arch to be 2½ feet at the springing line, and 1½ feet at the crown; the wings to be 22 feet in height, the breadth at bottom being 8 feet, which will be reduced by offsets, on the inside, to 2 feet 2 inches at the top; the foundations of the wings to be 6 feet in depth, the average breadth 10 feet; the foundations of the abutments and pier to be 6 feet in depth also, the average breadth of the former will be 8½ feet, and that of the latter 7½ feet; the foundations throughout to rest on a bed of good concrete 1 foot in thickness; the wings to be set out with a radius of 66 feet. The whole of the masonry to be of dressed laterite in chunam.

DETAILED ESTIMATE No. 4.
PENNAIR DFLTA.

Constructing a bridge of two arches across the Sarvapully Channel, near Stonehousepetta.

Particulars of Work.	MEASUREMENT.				Cubical Contents
	Length.	Breadth	Height or Depth	No.	
	Feet.	Feet.	Feet.		Feet.
Concrete.—Abutments ...	35½	11½	1	2	808½
Piers ...	35½	10½	1	1	369½
Wings ...	31	13	1	4	1,612
Retaining wall ...	26	6	1	4	62½
Inverts ...	28½	28	½	2	798
Spandril ...	16½	18	2	1	600
Total ...	...	...	...	...	4,812½
Foundation.—Abutments ...	32½	8½	6	2	3,281
Piers ...	32½	7½	6	1	1,447½
Wings ...	31	10	6	4	7,410
Retaining wall ...	28	3½	5½	4	2,156
Superstructure.—Abutments ...	29½	6	12	3	4,272
Piers ...	29½	4½	12	1	1,575
String courses ...	12½	½	½	...	15½
Caps ...	3½	4	3½	2	117½
Do. ...	4½	5	4½	2	187½
Skew backs ...	21	4	1	1	8½
Do. ...	21	5	1½	2	38½
Backing to arches ...	21	10	1½	2	630
Wings ...	31	5½	22	4	13,867½
Spandril ...	21	6	2½	1	315
	30	2½	2½	...	162½
Face wall ...	14	3½	4½	...	210
	66	3½	4½	...	990
	141½	1½	1½	2	759½
Parapets ...	14½	1	1½	2	506½
	2	2	3½	4	56
Total ...	...	...	...	...	38,454

*Proceedings of the Madras Government, Public Works Department,
20th June 1867.*

DETAILED ESTIMATE.—(Continued)

Particulars of Work.	MEASUREMENT.				Cubical Contents.
	Length	Breadth	Height or Depth	No.	
	Feet	Feet.	Feet.		Feet.
Cornice Running feet.	...	..	...	...	300
Arch-work	39	21	1½	2	3,071½
	31	27	1	2	1,674
Total ..	...	...	...	..	4,745½
Pointing Squares	...	...	...	...	102½
Excavation Cubic yards	...	...	...	...	1,540
Metaling "	...	...	...	...	15
Guard stones "	...	...	...	...	4
Centering... ..	...	...	...	...	...
Baling	...	...	...	...	...
Sundries	...	...	...	...	...

ABSTRACT ESTIMATE No. 4.

Quantities	Description of Work.	Rate.	Amount	Total.
		RS. A. P.	RS. A. P.	RS.
4,812	Cubic feet of concrete	0 2 0	601 8 0	
38,454	" of laterite in chunam ..	0 2 9	6,609 4 6	
4,745	" of arch-work with laterite in chunam.	0 3 0	889 11 0	
102½	Squares of pointing	2 0 0	205 0 0	
300	Running feet of cornice	0 4 0	75 0 0	
1,540	Cubic yards of excavation	0 1 0	96 4 0	
15	" of metaling	0 6 0	5 10 0	
4	Guard stones	4 0 0	16 0 0	
	Centering	...	370 0 0	
	Baling	...	200 0 0	
	Sundries	...	236 10 6	
	Deduct value of old materials	...	9,300 0 0	
			1,060 0 0	8,300

*Proceedings of the Madras Government, Public Works Department,
20th June 1867.*

DETAILED ESTIMATE No. 4.

PENNAIR DELTA.

Deepening the Sarvapully New Cut, and improving the old Ramireddy Channel.
Masonry Works

Particulars of Work	MEASUREMENT.				Cubical contents
	Length.	Breadth.	Height or Depth	No.	
	Feet	Feet.	Feet.		Feet.
<i>Demolishing and re-building Iron Aqueduct Piers.</i>					
Foundation to piers	17	5	5	4	1,700
Piers above	16	3	11	4	2,112
Total cubic feet of laterite in chunam. .	...	...	..	...	3,812
Demolishing existing piers	...	...	...	...	...
Scaffolding, shoring, and sundries	...	...	...	...	...
Baling water	...	...	...	...	...
<i>Substituting Iron Aqueduct for Syphon No. 1.</i>					
Foundation to abutments	7	4	3	2	168
Do. to wings	17½	4	3	4	840
Do. to piers	9½	4	3	4	444
Abutments above	7	2½	4	2	140
Wings do.	17½	2½	6	4	1,050
Piers do.	8½	3	11½	4	1,171½
String course	3½	3½	8	8	65½
Between beams	1½	3	4	4	10½
Caps	3	2½	2	8	126
Skew backs	7½	2	½	4	30
Backing to arches	2	½	½	4	1
Face walls	7	1	½	4	14
Parapets... ..	7	¾	¾	4	15½
Arches	7½	4	¾	2	45
Total cubic feet of laterite in chunam ...	...	...	...	...	4,121½
Running feet of sheet iron trough complete ...	...	..	...	...	80
Pointing Squares.	...	...	...	...	12½
Teak girders	15½	4"	8½"	6	21½
Do. do.	15½	4'	8½	4	14½
Total cubic feet of teak-wood ..	...	...	...	...	36
Excavating foundation	...	..	...	...	...
Baling	...	...	...	...	...
Syphon No. 2, same as No 1	...	...	...	...	...
<i>Lowering floor of Krishnapatnam road bridge.</i>					
Rocky cutting	24	44	3½	1	3,696
Or cubic yards ..	...	...	...	...	137
Syphon No. 3 same as No 1.	...	...	...	...	...

DETAILED ESTIMATE No. 4 — (Concluded)

Particulars of Work.	MEASUREMENT				Cubical contents.
	Length.	Breadth	Height or Depth.	No.	
	Feet.	Feet	Feet		Feet.
<i>Converting bridge across head of Krishnapatnam Channel into a Head Sluice for that branch.</i>					
Foundation piers	15½	4	4	3	732
Do	6	4	4	2	192
Retaining wall	30	2½	4	2	600
Above piers	8½	3	10	3	776½
Do	5½	3	8	5	675
Arch	3	7½	1	4	90
Skew backs	3	2½	½	5	18½
Spandrils	30	3	½	...	45
Flooring	30	1½	1½	...	67½
Do	21	6	1½	...	189
Do	21	4½	1½	...	141½
Total cubic feet of laterite in chunam ...	...	...	...	...	3,527½
Pointing Squares	...	...	...	...	13½
Iron bars Running feet	...	...	...	...	54
Teak shutters	4	5½	3"	12	69
Total cubic feet of teak-wood ...	...	...	...	...	69
Excavation Cubic yards	...	...	...	...	95
Baling	...	...	...	...	...
Centering and sundries	...	...	...	...	...

ABSTRACT ESTIMATE No. 4.

Quantities	Description of Work.	Rate			Amount.			Total.		
		RS.	A.	P.	RS.	A.	P.	RS.	A.	P.
3,812	<i>Demolishing and re-building Iron Aqueduct Piers</i>									
	Cubic feet of laterite in chunam ...	0	2	9	655	3	0			
	Demolishing existing piers ...	...	...	...	40	0	0			
	Scaffolding, shoring, and sundries ...	...	...	...	50	0	0			
	Baling water, &c. ...	...	...	...	34	13	0			
	Deduct value of old materials ...	...	...	...	780	0	0			
		...	...	...	100	0	0			
4,121	<i>Substituting Iron Aqueduct for Syphon No. 1.</i>									
	Cubic feet of laterite in chunam ...	0	2	9	708	4	9			
	Squares of pointing ...	2	0	0	25	0	0			
	Running feet of iron trough complete ...	15	0	0	1,200	0	0			
	Cubic feet of teak-wood ...	3	8	0	126	0	0			
	Excavating foundation ...	...	...	...	20	0	0			
80	Baling, &c. ...	...	...	...	20	11	3			
36		...	...	...						
								2,100	0	0

ABSTRACT ESTIMATE No 4.—(Concluded)

Quantities	Description of Work.	Rate			Amount			Total		
		RS.	A.	P.	RS.	A.	P.	RS.	A.	P.
	Syphon No. 2, same as No. 1 ...							2,100	0	0
	<i>Lowering floor of Krishnapatnam Road Bridge.</i>									
137	Cubic yards of rocky cutting ...	0	8	0	68	8	0			
	Sundries ...	...	...	...	1	8	0			
								70	0	0
	Syphon No 3 same as No 1 ...	...						2,100	0	0
	<i>Converting bridge across head of Krishnapatnam Channel into a Head Sluice for that branch.</i>									
3,527	Cubic feet of laterite in chunam ...	0	2	9	606	3	3			
	Squares of pointing ...	2	0	0	26	3	0			
	Running feet of iron bars ...	...	...	...	71	4	0			
	Cubic feet of teak-wood ...	3	8	0	241	8	0			
	Cubic yards of excavation ...	0	1	0	5	15	0			
54	Baling ...	...	...	...	10	0	0			
69	Centering and sundries ...	...	...	...	28	9	9			
95								990	0	0
	Total Estimate ..	...						8,040	0	0

Specification to accompany the Plan and Estimate for the Surplus Sluice proposed for constructing across the old Ramireddy Channel, adjacent to the Sarvapully branch Head Sluice.

This sluice will consist of five vents of 2½ feet span, the height of the piers being 7 feet. This work has been designed to discharge the local drainage, brought into the Sarvapully channel by the old Ramireddy; as this would be great, in heavy rain, in the event of the Nellore tank being full, provision has been made for dealing with a considerable surplus. The level of the floor to be the same level as the bed of the old Ramireddy at the site of the sluice, which is about 19.32 feet above mean tide, or 5 feet below the level of the bed, of the main channel, immediately in front of it. The sluice when required to act will discharge with a considerable velocity, as the head will never be less than 6 or 7 feet. The front wings to be 17½ feet in height, the average breadth being 4½, the foundations to be 5½ feet deep, with an average breadth of 8½ feet. The rear wings to be 10 feet in height, the breadth at bottom and top being 3½ and 1½ respectively, the foundations to be 6 feet deep with an average breadth of 5½ feet. The spandrils to be filled in solid, and a course of masonry, 1 foot in thickness, to be built over these and the arches. The face falls to be 6½ feet in height, the breadth at bottom and top being 3 feet and 1½ feet respectively. The space between the face walls to be filled in with concrete. The retaining walls will connect the wings front and rear, the section between the former will be as follows: depth 5½ feet, breadth at bottom 4 feet, and top 1½ feet, the rear retaining wall to be 6 feet with an average

Proceedings of the Madras Government, Public Works Department
20th June 1867.

breadth of $3\frac{1}{2}$ feet. The front flooring, between the vents and retaining walls to be $1\frac{1}{2}$ feet in thickness, resting on a bed of concrete 9 inches in thickness. The rear apron and the flooring between the vents to be 2 feet in thickness, the concrete under the former to be 9 inches thick, the space under the flooring of the vents to be filled in with concrete. The shutters will be worked by a screw, the general arrangement being the same as the working gear for the shutter of the auxiliary head sluice. The whole of the masonry to be built of dressed laterite in chunam. The side slopes of the channel in rear will be protected, for a length of 20 yards, by rubble pitching. Beyond the rear retaining wall there will be a rubble apron 16 feet 6 inches $\times$ 20 feet $\times$ 3 feet

DETAILED ESTIMATE No. 4.

PENNAIR DELTA.

Constructing an Irrigation Sluice—vide Plan No. 1.

Particulars of Work	MEASUREMENT				Cubical contents
	Length.	Breadth.	Height or Depth	No.	
Concrete	Feet	Feet.	Feet.		Feet
	$6\frac{1}{2}$	$8\frac{1}{2}$	$1\frac{1}{2}$	...	$43\frac{5}{8}$
	$1\frac{1}{2}$	$4\frac{1}{2}$	$1\frac{1}{2}$	...	$6\frac{1}{2}$
	15	$4\frac{1}{2}$	1	2	$142\frac{1}{2}$
	$12\frac{1}{2}$	$4\frac{1}{2}$	1	2	$112\frac{1}{2}$
Total ...					305
Barrel					
Retaining wall	10	8	$1\frac{1}{2}$	1	100
Front do.	2	$2\frac{1}{2}$	$4\frac{1}{2}$	1	$20\frac{1}{2}$
Foundation.—Front wings	1	$2\frac{1}{2}$	$4\frac{1}{2}$	1	$20\frac{1}{2}$
Rear do.	13	$2\frac{1}{2}$	$4\frac{1}{2}$	2	$321\frac{1}{2}$
Above.—Front do.	$10\frac{1}{2}$	$2\frac{1}{2}$	$4\frac{1}{2}$	2	$236\frac{1}{2}$
Rear do.	12	$1\frac{1}{2}$	$4\frac{1}{2}$	2	$120\frac{1}{2}$
Front face wall	$9\frac{1}{2}$	$1\frac{1}{2}$	$4\frac{1}{2}$	1	$114\frac{1}{2}$
Rear do.	$3\text{--}9\frac{1}{2}$	$1\frac{1}{2}$	$4\frac{1}{2}$	1	$17\frac{1}{2}$
Parapets	$3\text{--}9\frac{1}{2}$	$1\frac{1}{2}$	$4\frac{1}{2}$	1	$3\frac{1}{2}$
Total ...	$3\text{--}9\frac{1}{2}$	$1\frac{1}{2}$	$4\frac{1}{2}$	1	$2\frac{1}{2}$
Rubble stone —(Laterite)	10	7	$1\frac{1}{2}$	...	951
	7	$3\frac{1}{2}$	2	...	105
Or cubic yards.					$45\frac{1}{2}$
Pointing					150
Excavation					$5\frac{1}{2}$
Teak beam					3
Shutter with working gear					129
Baling					$1\frac{1}{2}$
Sundries					...

Proceedings of the Madras Government, Public Works Department
20th June 1867.

ABSTRACT ESTIMATE No. 4.

Quantities	Description of Work.	Rate			Amount.			Total.		
		RS.	A.	P.	RS.	A.	P.	RS.	A.	P.
305	Cubic feet of concrete	0	2	0	38	2	0			
9.1	Cubic feet of laterite in chunam	0	2	9	157	3	3			
3	Squares of pointing	2	0	0	6	0	0			
$5\frac{1}{2}$	Cubic yards of rubble stone (laterite)	1	2	0	6	3	0			
129	Cubic yards of earth-work	0	1	0	8	1	0			
$1\frac{1}{2}$	Cubic feet of teak-wood	3	8	0	2	6	6			
1	Shutter with working gear	...	...	...	12	0	0			
	Baling	...	...	...	10	0	0			
	Sundries	...	...	...	10	0	3			
								250	0	0

Specification to accompany the Plan and Estimate for the Head Sluice of the Sarvapully Branch Channel.

The sluice to consist of eight vents of 6 feet span. The front wings to be 15 feet in height, the breadth at bottom and top to be $5\frac{1}{2}$ feet and 2 feet respectively; the foundations to be laid at a depth of $5\frac{1}{2}$ feet, the average breadth being 7 feet. The rear wings to be $14\frac{1}{2}$ feet in height at the abutments and 10 feet at the returns, the average section at the former point being $3\frac{1}{2}$ feet and $2\frac{1}{2}$ feet at the latter, the foundation will have the depth of $5\frac{1}{2}$ feet at abutments and front wings, $4\frac{1}{2}$ at piers and 6 feet at rear wings and returns, but the section will vary from an average thickness of $6\frac{1}{4}$ at the abutments to $6\frac{1}{2}$ feet at the returns. Piers $4\frac{3}{4}$ feet at bottom, $2\frac{1}{2}$ feet at top on a bed of concrete $6\frac{1}{4}$ in breadth and $\frac{3}{4}$ in depth. The flooring in the bays to be inverts of $1\frac{1}{2}$ in thickness, resting on concrete 9 inches thick. The flooring from the bays to the front and rear retaining walls will be $1\frac{1}{2}$ feet in depth, with a bed of concrete 9 inches in thickness. The piers on the up-stream side will project $2\frac{1}{2}$ feet to admit of small arches being turned to facilitate the working of the shutters, these will consist of teak planks $6\frac{1}{2}$ feet $\times$ 3 inches $\times$ 15. Four iron bars, varying from 4 inches to $2\frac{1}{4}$ inches in diameter, to be fixed in each vent to strengthen the shutters and enable them to be worked easily. The rubble apron in rear to be $51\frac{1}{2}$ feet $\times$ 20 feet $\times$ $2\frac{1}{4}$ feet. The side slopes of the channel, in rear of the sluice, to be protected for a length of 20 feet by rubble pitching. The whole of the masonry to be of dressed laterite in chunam and pointed with chunam. The floor of the sluice to be $24\text{--}32$ feet above mean tide.

*Proceedings of the Madras Government, Public Works Department,
20th June 1867.*

**DETAILED ESTIMATE No. 4.
PENNAIR DELTA.**

Constructing a Surplus Sluice adjacent to the Survapully Branch Head Sluice across the old Ramireddy Channel.

Particulars of Work.	MEASUREMENT.				Cubical contents
	Length	Breadth.	Height or Depth.	No.	
	Feet.	Feet.	Feet.		Feet.
Concrete—Abutments	10½	7	3	2	112½
Piers	24½	20	1	1	367½
Front wings	41	10½	2	2	361½
Rear do.	21	9	2	2	23½
Returns	19	7½	2	2	21½
Rear retaining wall	12½	6	...	...	56½
Front do.	30½	5	...	...	136½
Front flooring	26½	7½	...	...	142½
Rear do.	20½	17	...	...	261½
Below flooring between piers ...	16	3	5	5	180
Spandril	19½	5½	...	...	10,23½
Total ...	...	...	...	...	3,143½
Foundation.—Abutments	10½	5½	6	2	741½
Piers	24½	17½	6	2	2,609½
Front wings	39½	8½	5½	2	3,788½
Rear do.	22½	6½	6	2	1,792½
Returns	14½	5½	6	2	1,051½
Rear retaining wall	14½	3½	6	2	287½
Front do.	10½	4½	7	2	586½
Superstructure.—Abutments	14½	3	7	4	677½
Piers	10½	3	1½	4	1,197
Caps	10½	3	1½	4	36½
Skew backs	39	4½	17½	4	32½
Front wings	39½	2	1	2	5,620½
Coping	25	3½	13½	2	157
Rear wings	25	2	1	2	2,334½
Coping	15	2½	10	2	100
Returns	15½	2	1	2	750
Coping	10½	3½	2½	2	62
Backing to arches	10½	3	1½	2	201½
Spandril	32½	10½	1	4	225½
Flooring over arches	32½	2½	6½	...	349½
Side walls	32½	1½	5½	2	975
Do.	33½	18½	1½	2	101½
Front flooring	24½	23	2	...	678½
Rear do.	10½	2½	2	...	1,138½
Flooring between piers	23	1	1	5	263½
Parapets	...	...	...	2	56
Deduct for vents	16	3	5	5	23,675½
Arch work	10½	5½	1½	5	180
Pointing	...	...	...	...	23,19½
Rubble stone (laterite)	10½	20	3	...	413½
Or cubic yards	20	17	2	2	56
	...	...	...	...	990
	...	...	...	...	1,310
	...	...	...	...	2,850

*Proceedings of the Madras Government, Public Works Department,
20th June 1867.*

DETAILED ESTIMATE No. 4.—(Continued.)

Particulars of Work.	MEASUREMENT.				Cubical Contents.
	Length.	Breadth	Height or Depth	No.	
	Feet.	Feet.	Feet.		Feet.
Excavation	...	...	...	...	959
Metaling	28	1	1	...	8
Teak-wood beam	3	3"	9	5	28
Shutters	...	...	...	...	...
Baling	...	...	...	...	...
Centering	...	...	...	...	...
Sundries	...	...	...	...	...

ABSTRACT ESTIMATE No. 4.

Quantities	Description of Work.	Rate.			Amount.			Total.		
		RS.	A.	P.	RS.	A.	P.	RS.	A.	P.
3,143	Cubic feet of concrete	0	2	0	392	14	0			
25,195	" of laterite in chunam	0	3	1	4,91½	1	7			
443	" of arch work with laterite in chunam.	0	3	4	92	4	8			
56	Squares of pointing	2	0	0	112	0	0			
87	Cubic yards of rubble stone (laterite)	1	2	0	97	14	0			
959	" of excavation	0	1	0	59	15	0			
8	" of metaling	0	14	0	7	0	0			
28	Cubic feet of teak-wood beam	3	8	0	93	0	0			
5	Shutters with working gear	49	0	0	215	0	0			
	Baling	...	...	...	200	0	0			
	Centering	...	...	...	90	0	0			
	Sundries	...	...	...	161	14	9			
								6,470	0	0

DETAILED ESTIMATE No. 4.

PENNAIR DELTA.

Excavating the Sarvapully Channel, and constructing the necessary irrigation and drainage works connected with it.

Particulars of Work.	MEASUREMENT.				Cubical contents.	Rates per cubic yard.
	Length.	Breadth.	Height or Depth	No		
	Feet	Feet.	Feet.		Feet.	RS. A. P.
Head sluice	1,320	56½	3½	1	2,42,385	0 1 0
Cutting	1,320	11½	2	2	609,800	0 1 0
Banking	1,320	56		2	147,840	0 0 4
Turfing	264	64	1	2	23,792	0 1 0
Banking	264	32½	5½	1	49,733½	0 1 0
Cutting	...	...	...	...	...	...

Proceedings of the Madras Government, Public Works Department.
20th June 1867.

DETAILED ESTIMATE No. 4.—(Continued)

Particulars of work.	MEASUREMENTS.				Cubical contents	Rates per cubic yard.		
	Length.	Breadth	Height or Depth.	No		RS.	A.	P.
Aqueduct	Feet.	Feet.	Feet.		Feet.			
Cutting (partly gravel) ..	3,696	34½	7½	1	981,057	0	2	0
2nd mile, cutting gravel, loam, and laterite ..	1,83	34½	8	1	188,508	0	3	0
Cutting do. do	1,297	42½	7½	1	386,623	0	3	0
Bridge of two arches ...								
Cutting laterite, gravel, and loam.	2,310	36½	9½	1	825,311½	0	3	0
Cutting do do	990	36½	9½	1	353,705	0	3	0
3rd mile, cutting do. do	5,280	43	8	1	1,816,220	0	3	0
4th mile, cutting ..	1,620	43½	8½	1	613,080	0	2	0
Bridge of two arches.								
Cutting ..	3,660	43½	8½	1	1,385,106½	0	1	6
5th mile, cutting ..	2,310	42½	7½	1	726,705½	0	1	9
Cutting loam and gravel	2,970	41½	6½	1	856,383	0	1	6
6th mile, cutting stiff clay and laterite ..	2,310	43½	8½	1	804,473½	0	3	0
Bridge of two arches								
Cutting stiff clay and laterite	1,650	43½	8½	1	574,624	0	3	0
Cutting laterite and hard gravel	660	37½	11	1	274,250	0	4	0
Cutting do do	660	38	11½	1	288,400	0	4	0
7th mile, cutting ..	4,220	35	8½	1	1,276,275	0	4	0
Bridge of two arches.								
Cutting laterite and hard gravel	990	35	8½	1	294,525	0	4	0
8th mile, cutting laterite and gravel	2,012	35½	8½	1	620,376½	0	4	0
Do. do	1,400	31½	4½	1	212,022½	0	4	0
12 distributing channels								
Compensation for land.								
11 Irrigation sluices as per Plan No 1								
1 do. do as per Plan No. 2								
Bund across Anikapalli tank supplying channel and valley								
Drainage channel from culvert to old Ramireddy channel.								
Drainage channel from near Anikapalli to Pottempadu swamp								
Cutting ..	2,640	36½	8½	1	824,670			
Do. do.	1,300	37½	9	1	445,500	0	1	2
Do. do.	1,610	34½	7	1	350,360	0	1	2
Total cubic feet of cutting					1,666,230	0	1	2
Or Cubic yards					61,712½			
Deepening and Improving old drain from the Pottempadu swamp to near the village of Darbalamitta								
Cutting ..	3,260	33	6	1	645,480			
Do. ...	3,560	30	4	1	463,200	0	1	0
Do. ..	3,000	28½	3	1	260,775	0	1	0
Total Cubic feet of cutting.					1,369,455	0	0	10
Or Cubic yards					48,498½			
Surplus channel from Sarvapully reservoir escape to Main Drain								

Proceedings of the Madras Government, Public Works Department.
20th June 1867.

ABSTRACT ESTIMATE No. 4.

Quantities.	Description of Work.	Rate.			Amount.			Total.		
		RS.	A.	P.	RS.	A.	P.	RS.	A.	P.
1	Head sluice, vide separate estimate							7,340	0	0
109,781	Cubic yards of cutting	0	4	0	27,445	4	0			
183,317	Do. of do.	0	3	0	34,371	15	0			
36,335	Do. of do.	0	2	0	4,541	14	0			
26,915	Do. of do.	0	1	9	2,943	13	3			
105,006	Do. of do.	0	1	6	9,844	5	0			
10,821	Do. of do.	0	1	0	676	5	0	79,823	8	3
22,585	Cubic yards of banking	0	1	3	1,764	7	3			
1,252	Do. of do.	0	1	0	78	4	0	1,842	11	3
16,427	Square-yards of turfing	0	0	4	342	3	8	342	3	8
12	Distributing channels	200	0	0				2,400	0	0
11	Compensation	300	0	0				3,000	0	0
1	Irrigation sluices, vide Plan No. 1...							3,300	0	0
1	Do do., vide Plan No. 2 ..							280	0	0
	Bund across Anikapally tank supplying channel and valley							150	0	0
	Drainage channel from aqueduct to old Ramireddy channel							770	0	0
	Drainage channel from near Anikapally to Pottempadu swamp.									
61,712	Cubic yard of cutting	0	1	2	4,499	13	4	4,499	13	4
38,840	Deepening and improving old drain from Pottempadu swamp to near the village of Darbalamitta.	0	1	0	2,427	8	0			
9,658	Cubic yards of cutting	0	0	10	503	0	4	2,930	8	4
	Do. of do.									
	Sarpapully channel from Sarvapully reservoir escape to main drain							550	0	0
1	Aqueduct, vide separate estimate							5,000	0	0
4	Bridges of 2 arches, vide separate estimate	3,540	0	0				14,160	0	0
	Sundries							111	3	2
	Total Estimates ..							1,26,500	0	0

DETAILED ESTIMATE No 4.
PENNAIR DELTA.

Constructing a Head Sluice for Sarvapully Branch.

Particulars of Work.	MEASUREMENT				Cubical contents
	Length.	Breadth.	Height or Depth.	Number.	
	Feet.	Feet.	Feet.		Feet.
Concrete.—Abutments					
Piers	11	8½	2	2	136½
Front wings	19½	6½	2	7	631½
Rear do	29	8½	2	2	358½
Do. returns	29	9½	2	2	307½
Front retaining wall	11	8	2	2	132
Rear do	94	5	2	1	352½
Inverts	55½	5	2	1	208½
Front flooring...	9½	5½	2	8	313½
Rear do	73½	19½	2	...	1,074½
Spandril	64	21½	2	...	1,032
	29½	5½	1½	...	245½
Total...					4,792½
Foundation.—Abutments					
Piers	11	5½	6	2	693
Do. front portions	12½	3½	4½	7	1,378½
Front wings	4½	3½	4	7	444½
Rear do	28	5½	5½	2	1,617
Do. returns	29	5½	6	2	2,044½
Front retaining wall	10½	5	6	2	630
Rear do	95	2½	5½	...	1,187½
Superstructure.—Abutments					
Piers	11	3½	10	...	810
Do. front portion	11½	2½	9	2	825
Caps	4	2½	9½	7	1,811½
Skew backs	31½	2½	2½	7	605
Front wings	11	2½	2½	...	187
Coping	28	2½	9½	2	48½
Rear wings	28½	2½	1	2	1,541
Do. returns	29	3½	12½	2	141½
Coping with returns	10½	2½	10	2	2,220½
Front flooring	33	1½	1	2	525
Rear Do	73½	19½	1½	2	114
Face walls	64	22	1½	...	2,177½
Backing to arches	66	2½	1½	...	2,112
Blocking courses	11	3	1½	2	544½
Parapets	70	1½	1	2	33
	69½	1½	1	2	175
Total...					104½
Arch work	9½	9	1½	...	22,023½
	1	9	1½	8	1,026
	9½	6½	1½	8	108
Total...					741
Pointing squares					1,875
Rubble stone laterite.	51½	20	2½	...	95½
	20	17	2	1	2,317½
Or Cubic yards				2	1,360
					3,677½
					136½

DETAILED ESTIMATE.—(Concluded)

Particulars of Work.	MEASUREMENT.				Cubical contents
	Length.	Breadth	Height or Depth	No	
	Feet	Feet.	Feet.		Feet
Earth-work, Cubic yards	...	...	...		1,650
Teak-wood shutters	6½	3"	15	8	195
Metaling Cubic yards.	...	...	...		16½
Iron bars, R. feet	...	...	...		240
Baling	...	...	...		
Centering	...	...	...		
Sundries	...	...	...		

ABSTRACT ESTIMATE No. 4.

PENNAIR DELTA.

Constructing Head Sluice for Sarvapully Branch

Quantities	Description of Work	Rate.	Amount.	Total
		RS. A. P.	RS. A. P.	RS. A. P.
4,793	Cubic feet of concrete	0 2 0	599 2 0	
22,028½	Do of laterite in chunam	0 3 1	4,245 1 3	
1,875	Do of arch work	0 3 4	390 10 0	
95½	Squares of pointing	2 0 0	190 8 0	
136½	Cubic yards of rubble stone (laterite)	1 2 0	153 3 8	
1,650	Do. of earth-work	0 1 0	103 2 0	
16½	Do of Metaling	0 14 0	14 4 8	
195	Cubic feet of teak-wood shutter	3 8 0	682 8 0	
240	R. feet of iron bars	...	295 0 0	
	Baling	...	250 0 0	
	Centering	...	240 0 0	
			7,163 7 7	
	Sundries	...	176 8 5	
				7,340 0 0

ABSTRACT ESTIMATE No. 4.

PENNAIR DELTA.

Constructing an Irrigation Sluice, Vide Plan No. 1.

Quantities.	Description of Work	Rate.	Amount.	Total.
		RS. A. P.	RS. A. P.	RS. A. P.
305	Cubic feet of concrete	0 2 0	38 2 0	
951	Do of laterite in chunam	0 3 4	198 2 0	
3	Squares of pointing	2 0 0	6 0 0	
5½	Cubic yards of rubble stone (laterite)	1 2 0	6 3 0	
129	Do of excavation	0 1 0	8 1 0	
4½	Cubic feet of teak-wood	3 8 0	2 6 6	
1	Shutter with working gear	...	12 0 0	
	Baling	...	10 0 0	
	Sundries	...	19 1 6	
	Total Estimate...	...	...	300 0 0

Proceedings of the Madras Government, Public Works Department.
20th June 1867.

DETAILED ESTIMATE No. 4.
PENNAIR DELTA.
Constructing an Irrigation Sluice—Vide Plan No. 2.

Particulars of Work.	MEASUREMENT.				Cubical Contents
	Length.	Breadth.	Height or Depth	Num- ber.	
	Feet.	Feet.	Feet		Feet.
Concrete	4½	8½	1	0	28-7½
	9½	5½	1	2	97-4½
	8½	4½	1	2	80-9
	4	4½	1	1	18-0
Total	...	...	...	...	224-9
Bund	6	12	1½	1	90-0
Front retaining wall	2	7½	3½	1	12-0
Rear do	1½	1½	3½	1	10-9
Do. do.	4	2	4½	1	26-0
Foundation—Front wings	8½	2½	4½	2	210-4½
Rear do	7½	3½	4½	2	210-11
Above.—Front wings	3	1½	4½	2	108-0
Coping	8½	2	5½	2	21-9
Rear wings	7	1-9½	5½	2	139-7
Coping	7½	2	3½	2	21-9
Face wall	5½	1½	3½	2	52-11
Parapets	5½	1	1	0	5-0½
Total...	2½	½	1½	0	922-4
Deductions for retaining walls					1-9
Net cubic feet	...	...	...	...	920-6
Pointing	...	...	...	...	3½
Rubble stone laterite	5	4½	1½	...	32
	4½	6	2	...	51
Total ..	...	...	...	...	83
Or Cubic yards	...	...	...	...	3½
Earth-work	...	...	...	...	100
Teak-wood beams	...	...	...	...	2½
Shutting with working gear	...	...	...	...	1
Baling	...	...	...	...	...
Sundries	...	...	...	...	...

ABSTRACT ESTIMATE No. 4.

Quantities.	Description of Work.	Rate.	Amount.	Total.
224½	Cubic feet of concrete ...	RS. A. P.	RS. A. P.	RS. A. P.
920½	Do. of laterite in chunam ...	0 2 0	28 1 6	...
3½	Squares of pointing...	0 3 4	101 12 4	...
-3½	Cubic yards of rubble stone laterite.	2 0 0	6 8 0	...
100	Do. of earth-work ...	0 14 0	2 11 0	...
2½	Cubic feet of teak-wood beam	0 1 0	6 4 0	...
1	Shutter with working gear ...	3 8 0	8 13 9	...
	Baling	...	20 0 0	...
	Sundries	...	10 0 0	...
		...	5 13 5	...
				280 0 0

Proceedings of the Madras Government, Public Works Department.
20th June 1867.

Specification to accompany the Plan and Estimate for the Aqueduct proposed for construction near Kanupartipadu

This structure will carry the Sarvapully branch channel over the drainage from the land in the vicinity of Kanupartipadu, and the surplus from the Kanupartipadu tank; it will contain four vents of 4 feet span, the piers being 3 feet in height, and 2½ in breadth. The abutments to be 3 feet in height with an average breadth of 3½ feet. The foundations of the piers and abutments to be 4 feet deep, the breadth of the former at top and bottom 2½ feet and 4½ respectively, the dimensions of the latter at same points being 3½ feet and 5½ feet. At the abutments, the wings will be 18 feet in height, the breadth at bottom being 9 feet and at top 3 feet, this will be increased by a corbel of 1 foot on each side to form a roadway, the wings will be reduced in height by steps of 1 foot up and 2 feet on to 11 feet 6 inches, and be carried at this height 11 feet, making the total length 23½ feet. The outer faces of the side walls to be plumb, the inner to be described with a radius of 14½ feet. The floor of the aqueduct to be 20 in breadth at the level of the bed of the channel, and 28 at the maximum water mark. The floor of the aqueduct and the inner faces of the side wall for a height of 7 feet measured on the curve will have a coat of asphalte half an inch thick.

The masonry to be of dressed laterite in chunam.

DETAILED ESTIMATE No. 4.

PENNAIR DELTA.
Constructing an Aqueduct near Kanupartipadu.

Particulars of Work.	MEASUREMENT.				Cubical contents.
	Length	Breadth.	Height or Depth.	Num- ber.	
	Feet.	Feet	Feet		Feet.
Concrete	34	3	9"	4	306
Total cubic feet	...	...	...	...	306
Foundation—Abutments	39½	4½	4	2	1,416
Do. to piers	39½	3½	4	3	1,652
Do. to wings	11	9½	4	4	1,618½
Do. to do.	11½	8	4	4	1,493½
Abutments above	35½	3½	3	2	692½
Piers do.	37	2½	3	3	832½
Skewback	34	2½	½	3	127½
Do	34	3	½	2	102
Backing to arches	34	5½	1½	2	467½
Spandril	4	6½	¾	3	497½
Caps	2½	1½	1½	6	33½
Wings do.	11½	8	3½	4	1,380
Do face walls.	75½	4½	10½	2	6,971½
Do top courses	75½	4	½	2	300½
Do do	75½	5	½	2	375½
Arch works	34	6½	2	4	1,813½
Inverts	34	4½	1½	4	807½
Total cubic feet	...	...	...	...	20,576½
Pointing	...	...	...	...	69½
Excavating foundation	...	...	...	...	8-9
Asphalte	...	29½	34	...	1,003
Baling	...	...	...	...	or 10½
Centering and Sundries	...	...	...	...	...

Proceedings of the Madras Government, Public Works Department.
20th June 1867.

ABSTRACT ESTIMATE No. 4.

Quantities	Description of Work.	Rate.	Amount.	Total.
		RS. A. P.	RS. A. P.	RS.
306	Cubic feet of concrete ...	0 2 0	38 4 0	
20,571 $\frac{1}{2}$	Do. laterite in chunam ..	0 3 4	4,286 12 4	
69 $\frac{1}{2}$	Squares of pointing ..	2 0 0	139 0 0	
83 $\frac{1}{2}$	Cubic yards of excavation ...	0 1 0	52 7 6	
10 $\frac{1}{2}$	Squares of asphalte ...	19 0 0	190 9 3	
	Baling ...		180 0 0	
	Centering and Sundries ...		112 11 11	
	Total Estimate ...			5,000

DETAILED ESTIMATE No. 4.
PENNAIR DELTA.

Constructing Bridge of two arches 15 feet span across the Sarvapully Branch Channel.

Particulars of Work.	MEASUREMENT.				Cubical contents.
	Length	Breadth.	Height or Depth.	Number.	
Concrete	Feet.	Feet	Feet.		Feet.
	{ 18	12	1 $\frac{1}{2}$	1	270
	{ 14	14 $\frac{1}{2}$	$\frac{1}{2}$	2	304 $\frac{1}{2}$
Total	...	...	...	...	574 $\frac{1}{2}$
Foundation—Abutments					
Pier	21 $\frac{1}{2}$	6	5	2	1,260
Wings	21	4 $\frac{1}{2}$	5	1	416 $\frac{1}{2}$
Plaster to the end	23	6 $\frac{1}{2}$	5	4	2,798 $\frac{1}{2}$
Retaining wall	2	$\frac{1}{2}$	5	4	10
Do	23	2 $\frac{1}{2}$	4	4	560
Above—Abutments	28	1 $\frac{1}{2}$	1	2	84
Pier	20 $\frac{1}{2}$	5	10	2	2,025
Caps	18 $\frac{1}{2}$	3	10	1	555
String course	3	2	2	4	48
Wings	84	$\frac{1}{2}$	$\frac{1}{2}$	...	10 $\frac{1}{2}$
Pilaster	23	3 $\frac{1}{2}$	11 $\frac{1}{2}$	4	3,369 $\frac{1}{2}$
Facewall	2	3 $\frac{1}{2}$	6	4	12
Spandril	{ 18	1 $\frac{1}{2}$	1 $\frac{1}{2}$	2	67 $\frac{1}{2}$
Skew backs	{ 25	1 $\frac{1}{2}$	2 $\frac{1}{2}$	2	178 $\frac{1}{2}$
Do	14 $\frac{1}{2}$	8	1 $\frac{1}{2}$	...	151 $\frac{1}{2}$
Backing to arches...	14 $\frac{1}{2}$	3	1 $\frac{1}{2}$	1	24 $\frac{1}{2}$
Do.	14 $\frac{1}{2}$	2 $\frac{1}{2}$	$\frac{1}{2}$	2	39 $\frac{1}{2}$
Parapets	14 $\frac{1}{2}$	2 $\frac{1}{2}$	$\frac{1}{2}$	...	39 $\frac{1}{2}$
Blocking course	90	7	1 $\frac{1}{2}$	2	88 $\frac{1}{2}$
Pedestals	43	1 $\frac{1}{2}$	3	2	607 $\frac{1}{2}$
Total	14	1 $\frac{1}{2}$	3	4	36 $\frac{1}{2}$
Arch work	...	...	...	...	12,059 $\frac{1}{2}$
Inverts	14 $\frac{1}{2}$	19 $\frac{1}{2}$	1 $\frac{1}{2}$	2	918 $\frac{1}{2}$
Total cubic feet	14 $\frac{1}{2}$	11 $\frac{1}{2}$	1	2	333 $\frac{1}{2}$
Cornice work	...	...	...	...	1,252 $\frac{1}{2}$
Pointing	...	...	...	...	194
Earth-work	...	...	...	...	55
Metaling	...	...	...	...	606
Guard stones	...	...	...	...	52
Centering	...	...	...	...	...
Baling	...	...	...	...	...
Sundries	...	...	...	...	...

Proceedings of the Madras Government, Public Works Department.
20th June 1867.

ABSTRACT ESTIMATE No. 4.

Quantities	Description of Work	Rate.	Amount.	Total.
		RS. A. P.	RS. A. P.	RS.
575	Cubic feet of concrete ...	0 2 0	71 14 0	
12,144	Do. of laterite in chunam ...	0 3 4	2,530 0 0	
1,253	Do. of arch work ...	0 3 7	280 9 11	
55	Squares pointing ...	2 0 0	110 0 0	
194	Running feet of cornice work ...	0 4 0	48 8 0	
606	Cubic yards of earth-work ...	0 1 0	41 10 0	
52	Do. of metaling ...	0 14 0	45 8 0	
4	Guard stones ...	4 0 0	16 0 0	
	Centering ...	...	200 0 0	
	Baling ...	...	100 0 0	
	Sundries ...	...	95 14 1	
				3,510

Specification to accompany the estimate for converting the Sarvapully tank into the Main Reservoir for the southern portion of the Pennair Delta.

1. The embankment to be raised to 6 feet above future tank level ; the breadth at top being 6 feet, with side slopes of 2 to 1 ; the interior to be protected, for a length of 5,270 yards, by a revetment of roughly dressed laterite, carefully packed at right angles to the slope ; the thickness of the revetment at bottom to be 2 feet, and at top (*i. e.*, 2 feet above proposed full tank level) 1 foot ; in rear of the revetment there will be a gravel backing 6 inches thickness.

2. The exterior slope of the work, and the portion of the interior, above the revetment, to be well turfed.

3. The present calingulah to be closed, and a new one constructed adjacent to the village of Anikapally ; the crest being 2 feet below tank high water mark.

4. The five existing sluices to be lengthened and improved. On the completion of the proposed new supply channel the old one will be closed by continuing the tank bund to the high land at Anikapally. In the event of the revetment, as planned, being considered too expensive, a reduction of Rupees 27,248 might be made by altering the interior slope of the bank from 2 to 1 to 1 to 1.

*Proceedings of the Madras Government, Public Works Department,
20th June 1867.*

DETAILED ESTIMATE, No. 4.

PENNAIR DELTA.

Converting Sarvapully Tank into Main Reservoir for the southern portion of the Pennair Delta.

Particulars of Work	MEASUREMENT.			No	Cubical contents.
	Length	Breadth	Height or Depth.		
Banking from Station 2 to Station 6	Feet 1,650	Feet 23 68	Feet. 8 84	...	Feet. 345,396 4,800
Banking from Station 6 to present calingulah	525	34 94	14 47	...	265,430 4,450
Banking site of calingulah	255	35 02	15 01	...	137,868 3,510
Banking Transverse Section No. 1	1,200	40 88	17 44	...	855,536 6,400
Do. do. " 2	1,320	38 14	16 07	...	809,010 9,360
Do. do. " 3	1,140	42 46	18 23	...	852,412 2,120
Do. do. " 4	1,500	41 22	17 61	...	1,088,826 3,000
Do. do. " 5	1,320	38 62	16 31	...	841,457 7,040
Do. do. " 6	1,320	38 09	16 00	...	802,560 0000
Do. do. " 7	1,320	38 92	16 46	...	845,622 6,240
Do. do. " 8	1,800	39 98	16 99	...	1,222,668 3,600
Do. do. " 9	600	38 02	16 01	...	401,742 1,320
Do. do. " 10	1,500	35 08	14 54	...	765,094 8,000
Do. do. " 11	1,260	35 62	14 81	...	664,090 5,720
Banking from Station 52 to Station 55	720	35 64	14 82	...	380,293 0560
Banking from Station 55 to Station 56 exclusive of channel	465	33 44	13 72	...	213,340 5,120
Banking in channel	30	39 44	16 72	...	19,731 0,040
Banking from Station 56 to 60	1,600	31 34	12 67	...	635,244 800
Do. from do 60 to 62	800	26 40	10 20	...	215,424 0000
Do. from do. 62 to 65	1,200	12 98	3 49	...	54,360 2,400
Total...	21,585				11,436,872 9,400
<i>Deduct for existing Bund as follows.</i>					
From Station 6 to present calingulahs	525	18 50	8 50	...	82,556 2,500
Transverse Section No. 1	1,200	47 25	5 78	...	327,726 0000
Do. do. " 2	1,320	55 50	5 29	...	387,545 4,000
Do. do. " 3	1,140	54 00	5 76	...	354,585 6,000
Do. do. " 4	1,500	75 25	5 21	...	588,078 7,500
Do. do. " 5	1,320	54 23	3 92	...	280,711 2,000
Do. do. " 6	1,320	60 75	3 62	...	490,287 8,000
Do. do. " 7	1,320	60 75	4 67	...	374,187 3,000
Do. do. " 8	1,800	56 00	4 73	...	476,784 0000
Do. do. " 9	660	73 00	3 79	...	182,602 2,000
Do. do. " 10	1,500	47 00	2 62	...	184,710 0000
Do. do. " 11	1,260	31 50	1 08	...	78,588 2,000
From Station 52 to Station 55	720	31 50	3 13	...	70,988 4,000
From Station 55 to Station 56	465	15 75	1 64	...	12,010 9,500
Total...					3,691,660 0500
Balance of Cubic feet .. or Cubic yards ..	5,270	3 1/2			7,745 212 8,980
Sundry earth-work...					2,86,859
Total Cubic yards of earth-work ..					2,89,247

*Proceedings of the Madras Government, Public Works Department.
20th June 1867.*

DETAILED ESTIMATE No 4.—(Concluded)

Particulars of Work.	MEASUREMENT.			No.	Cubical contents.
	Length	Breadth	Height or Depth.		
Laterite revetment ..	Feet 5,270	Feet. 8 1/2	Feet. 1/2	...	Feet. 21,409 1/2
Deduct for existing revetment ..	640	1 1/2	1/2	...	480
	640	1/2	1/2	...	160
Total...	...	...	...	...	640
Total Cubic yards of laterite stone revetment ..	...	...	...	...	20,769 1/2
Gravel backing, .. Cubic yards.	5,270	8 1/2	1/2	...	7,136 1/2
Turfig ..	725	Not required.			
	85	16	...	...	1,360
	400	16 1/2	...	...	6,700
	440	16 1/2	...	...	7,205
	380	17 1/2	...	...	6,555
	500	17 1/2	...	...	8,812 1/2
	440	15 1/2	...	...	6,985
	440	15 1/2	...	...	6,985
	410	15 1/2	...	...	6,985
	600	16 1/2	...	...	9,900
	220	15 1/2	...	...	3,437 1/2
	500	13 1/2	...	...	6,750
	420	14 1/2	...	...	6,090
	240	14 1/2	...	...	3,570
	155	13 1/2	...	...	2,131 1/2
	10	13 1/2	...	...	137 1/2
	533	19 1/2	...	...	10,093 1/2
	267	14 1/2	...	...	3,938 1/2
	400	4 1/2	...	...	1,900
Total Square yards of turfig ..	...	...	...	...	99,634 1/2

ABSTRACT ESTIMATE No. 4.

Quantities	Description of Work.	Rate			Amount.			Total.		
		RS.	A.	P.	RS.	A.	P.	RS.	A.	P.
289,247	Cubic yards earth-work, inclusive of tamping	0	1	6	27,116	14	6			
20,769	Cubic yards of laterite stone revetment	3	0	0	62,307	0	0			
7,136	Do gravel backing	0	9	0	4,014	0	0			
99,634	Square yards of turfig	0	0	4	2,075	11	4			
640	Cubic yards of removing and re-constructing old revetment	0	6	0	240	0	0			

ABSTRACT ESTIMATE No. 4.—(Concluded)

Quantities.	Description of Work.	Rate.	Amount.	Total.
		RS. A. P.	RS. A. P.	RS. A. P.
1	New calingulah Lengthening and improving five Irrigation sluices	700 0 0	1,670 0 0	
	Compensation for land		3,500 0 0	
165	Acres ..	40 0 0	6,600 0 0	
165	Do.	5 0 0	825 0 0	
478	Do.	8 0 0	3,824 0 0	
477	Do.	1 0 0	477 0 0	
	Compensation for houses, &c., in the hamlet of Nappaturu.			
1	Chuttrum, with thatched roof			
10	Huts ..		100 0 0	
1	Bourie ..		200 0 0	
1	Do.		150 0 0	
6	Wells ..		300 0 0	
1	Do. belonging to the village of Nagalaram	40 0 0	240 0 0	
	Total ..		40 0 0	
	Deduct value of old materials		1,13,79 9 10	
	Sundries ..		500 0 0	
	Total Estimate ..		1,13,179 9 10	
			820 6 2	
				1,14,000 0 0

Specification to accompany the Estimate and Plan for the Escape proposed for the Sarvapully Reservoir.

1. The length of the body to be 170 feet and flush with the apron, the surface being 2 feet below the future tank high water mark; to retain the water to this level, the body will be furnished with 33 cast-iron posts 2 feet in height, and 63 teak shutters (*i. e.*, two for each vent). The front wings and returns to be 6½ feet in height, the breadth at floor level being 2½ feet, and at top 1½ feet; the batter being on the outer faces. The rear returns to be 3 feet in height with a breadth of 1½ feet at floor level, and 1½ feet at top, the batter being also on the outer faces. The rear returns to be connected by a retaining wall, 4 feet in depth, the breadth at bottom being 2 feet 3 inches and 1½ at top. The apron to be 12 feet in breadth and thick; it will cover the entire space between the body, rear wings, and retaining wall.

2. In rear of the laterite apron there will be one of rubble 10½ feet in length, 10 feet in breadth, and 1½ feet in thickness.

3. The foundations of the whole structure to be 2 feet in depth, with the exception of those of the retaining wall and rear returns, these will be laid at 4 feet below floor level.

4. The masonry to be of dressed laterite in chunam.

NELLORE DISTRICT No. 4.

PENNAIR DELTA.

Constructing an Escape in the Sarvapully Reservoir.

Particulars of Work.	MEASUREMENT.				Cubical contents.
	Length	Breadth	Depth.	Number.	
	Feet	Feet.	Feet.		Feet
Concrete — Apron	178	10-9	6"		934½
Foundation — Body	170	2-9	2	1	935
Wings	14-6	2-5	2	2	149½
Do.	12½	2-4	2	2	100
Returns	7-6	1½	4	2	120
Retaining wall	186	1-9	3	1	976½
Superstructure — Wings	14-6	1½	6 6	2	369½
Do.	12½	1-7½	4-9	2	182½
Returns	7-6	1½	3	2	66
Apron	178	12	1		2,136
Total cubic feet of laterite in chunam	..	..	..	..	5,035½
Rubble apron	19½	10	1-6		2,910
Cubic yards	..	..	..	..	107½
Pointing, ..	Squares			.	30
Cast-iron posts		..	..	.	33
Teak-wood shutters	..	..		..	34
Excavation ..	..	..	..	..	
Sundries ..	..	..	..	..	

ABSTRACT ESTIMATE No. 4.

Quantities.	Particulars of Work.	Rate.	Amount	Total.
		RS A P	RS A P	RS.
934½	Cubic feet of concrete	0 2 0	116 13 0	
5,036	Do. of laterite in chunam	0 2 2	708 3 0	
30½	Squares of pointing...	1 8 0	45 6 0	
107½	Cubic yards of rough stone	1 0 0	107 12 5	
33	Cast-iron posts	12 0 0	396 0 0	
68	Teak-wood shutters	3 0 0	204 0 0	
	Excavation...	..	25 0 0	
	Sundries ..	..	66 13 7	
	Total...	..		1,670

*Proceedings of the Madras Government, Public Works Department,
20th June 1867.*

DETAILED ESTIMATE No. 4.

PENNAIR DELTA.

Lengthening and Improving Iskapaem Sluice in the Sarvapully Reservoir.

Particulars of Work.	MEASUREMENT.				Cubical contents.
	Length.	Breadth.	Depth.	Number.	
	Feet.	Feet.	Feet.		Feet.
Concrete	64	7½	9"		360
	23-9	6½	9"		120½
	20-9	5½	9"		83½
	26	3	9"		58½
	8	2-6	6"		10
	9	11-6	6"		51½
	21	3-9	9"		59½
	17	3-9	9"		47½
	4	4-6	9"		13½
					804½
Total Cubic feet of concrete ..	50	7½	9"		281½
Deduct for existing work...					523
Total Cubic feet of concrete ..					523
Foundation.—Front cistern side walls ...	20	5	4½		450
Wings ...	20-9	3½	3½		551½
Rear cistern side walls ...	11	2-6	3'	2	82½
Wings ...	15-6	2 6	4'		155
Retaining wall ...	26	1-3	2-9		89½
Sluice flooring ...	64	6	2		768
Superstructure.—Do. side walls ...	64	1-9	2'		448
Arch ...	64	5-3	1-6		504
Front apron ...	8	2-6	9"		15
Do. do. ...	11-6	9	1-6		155½
Rear ...	4-3	4-6	1-6		28½
Side walls (at head) ...	11-6	3	11		379½
Blocking course ...	3	2½	7-6		59½
Wings ...	20-9	2½	6-6	2	629½
Rear cistern side walls ...	11-6	1-6	5		86½
Wings ...	12	1-6	5		90
Rear cistern arch ...	4-6	1-6	1-3		8½
Front face walls ...	3	1-6	3		13½
Parapets ...	6 6	1-9	1		5½
	7-6	1-6	1-6		14½
					9½
Total Cubic feet of laterite in chunam...					4,543
Deduct old works ..	50	6			600
	50	1-9	2'		350
	50	5-3	2	2	393½
Total...					1,343½
Total Cubic feet of laterite in chunam ...					3,199½
Cut granite ...	8	3½	1'		21
	2½	1½	1'		2½
	3½	4	1'		15
	1½	4	1'		23
	3½	1	1'		5½
	3½	1	1'		2½
Total...					69½

*Proceedings of the Madras Government, Public Works Department,
20th June 1867.*

DETAILED ESTIMATE No. 4.—(Concluded.)

Particulars of Work.	MEASUREMENT.				Cubical contents.
	Length.	Breadth.	Depth.	Number.	
	Feet.	Feet.	Feet.		Feet.
Deduct... ..	8	1	¾		6
	7	¾	¾		3½
					9½
Total Cubic feet of granite...					59½
Pointing Squares...					10
Excavation					
Sundries					
Four others same as above...					

ABSTRACT ESTIMATE No. 4.

Quantities.	Description of Work.	Rate.	Amount.	Total.
		RS. A. P.	RS. A. P.	RS.
523	Cubic feet of concrete	0 2 0	65 6 0	
3,199½	Cubic feet of laterite in chunam...	0 2 6	499 14 1	
59½	Cubic feet of cut granite...	1 2 0	89 8 0	
10	Squares of pointing	1 8 0	15 0 0	
	Excavation... ..		30 0 0	
	Sundries		0 3 11	
	Total Estimate...			700
	Four others same as above...			2,800
	Grand Total Estimate...			3,500

*Proceedings of the Madras Government, Public Works Department,
20th June 1867.*

DETAILED ESTIMATE No. 4.

PENNAIR DELTA.

Excavating Idagaly Branch Channel, and constructing the required masonry works.

Particulars of Work.	MEASUREMENT.				Cubical contents.	Rates per Cubic yard
	Length	Breadth.	Height or Depth.	No.		
	Feet	Feet.	Feet.		Feet.	RS. A. P.
Head sluice.						
Cutting hard gravel ...	2,310	44½	5½	1	603,006	0 2 6
Cutting stiff clay ...	2,640	41½	3½	1	422,510	0 1 2
Cutting laterite ...	330	42½	4½	1	60,537	0 4 0
Banking ...	230	17½	5½	1	32,113	0 1 6
Second mile, cutting laterite ...	1,320	39½	5	1	260,700	0 4 0
Banking ...	1,340	16	5	1	105,600	0 1 6
Cutting stiff clay ...	2,640	39½	4½	1	500,830	0 1 2
Cutting ...	1,320	39½	4½	1	250,415	0 1 1
Third mile, cutting... ..	1,320	39½	4½	1	212,355	0 1 1
Cutting ...	462	39½	1	1	14,091	0 1 0
Do. ...	3,498	34½	5½	1	658,936	0 1 2
<i>Ipuru and Pudiparty Branch takes off—</i>						
Fourth mile, cutting ...	660	17½	6½	1	76,147	0 1 2
Regulating sluice ...	1,080	13½	3½	1	91,823	0 1 2
Cutting ...						
Six irrigation sluices as per Plan No 1. ...						
Six distributing channels ...						
Minor branch channel ...						
Compensation for land ...						
<i>Ipuru and Pudiparty Branch.</i>						
Head sluice.						
Cutting ...	3,960	25½	5½	1	538,560	0 1 1
Do. ...	2,865	17½	1½	1	76,280	0 1 1
Banking ...	2,865	27½	2	2	312,285	0 1 1
<i>Pudiparty Branch takes off—</i>						
Cutting ...	4,185	13	4	1	217,620	0 1 0
Regulator and fall ...						
Four irrigation sluices as per Plan No 1. ...						
Compensation for land ...						
Minor branch channels ...						
<i>Pudiparty Branch.</i>						
Cutting ...	3,910	12	2½	1	125,120	0 1 0
Banking ...	940	31	2	2	116,560	0 1 0
Regulator and fall ...						
Two irrigation sluices as per Plan No. 1 ...						
Minor branch channels ...						
Compensation for land ...						

*Proceedings of the Madras Government, Public Works Department,
20th June 1867.*

ABSTRACT ESTIMATE No. 4.

Quantities.	Description of Work.	Rate	Amount.	Total.
		RS. A. P.	RS. A. P.	RS. A. P.
1	Head sluice, <i>vide</i> separate Estimate.	0 4 0	2,974 8 0	4,410 0 0
11,898	Cubic yards of cutting ...	0 2 6	3,489 8 6	
22,333	Do. of do. ...	0 1 2	4,726 12 0	
64,861	Do. of do. ...	0 1 1	1,160 8 4	
17,140	Do. of do. ...	0 1 0	32 10 0	
522	Do. of do. ...			12,383 14 10
5,111	Do. of banking ...	0 1 6	479 2 6	479 2 6
1	Regulating sluice, <i>vide</i> separate Estimate.			800 0 0
6	Irrigation sluices as per Plan No. 1.	260 0 0		1,560 0 0
6	Distributing channels ...	50 0 0		300 0 0
	Minor branch channel ...			1,760 0 0
	Compensation for land ...			1,875 0 0
	<i>Ipuru and Pudiparty Branch</i>			
1	Head sluice, <i>vide</i> separate Estimate.	0 1 1	1,541 13 8	1,100 0 0
22,772	Cubic yards of cutting ...	0 1 0	503 12 0	
8,060	Do. of do. ...			2,045 9 8
11,566	Do. of banking ...	0 1 1	783 1 10	783 1 10
1	Fall, <i>vide</i> Plan No 3 ...			970 0 0
4	Irrigation sluices as per Plan No. 1.	260 0 0		1,040 0 0
4	Distributing channels ...	50 0 0		200 0 0
	Compensation for land ...			500 0 0
	Minor branch channels ...			880 0 0
	<i>Pudiparty Branch.</i>			
4,634	Cubic yards of cutting ...	0 1 0	289 10 0	
4,317	Do. of banking ...	0 1 0	269 13 0	
1	Fall, <i>vide</i> Plan No 2 ...	0 0 0	1,040 0 0	
2	Irrigation sluices as per Plan No. 1.	260 0 0	520 0 0	
2	Distributing channels ...	50 0 0	100 0 0	
	Minor branch channels ...		1,320 0 0	
	Compensation for land ...		200 0 0	
	Sundries ...			3,739 7 0
	Total Estimate .			83 12 2
	Deduct value of laterite that will be obtained from the excavation ...			1,500 0 0
	Total Estimate .			33,440 0 0

Specification to accompany the Plan and Estimate for the Idagali Branch Channel Head Sluice.

1. This work to be constructed at the southern extremity of the Sarvapully reservoir, adjacent to the site of the present ealingulah; it will consist of eight vents of 3 feet span, the height of the piers to be four feet, and the breadth 2½. The front wings to be 14½ in height, the breadth at bottom and top being 5½ feet and 2 feet respectively, the rear wings to be 8 feet in height with an average breadth of 2½ feet. The wings in rear and in front to be connected by retaining walls; the rear one to be 5 feet in depth with an average breadth of 2½, the front retaining wall to be the

*Proceedings of the Madras Government, Public Works Department,
20th June 1867.*

same breadth, but only $4\frac{1}{2}$ feet in depth. The flooring throughout to be $1\frac{1}{2}$ in thickness with a bed of concrete 1 foot thick. The face walls to be $7\frac{1}{2}$ in height, the bottom breadth being $3\frac{1}{2}$, and the top $1\frac{1}{2}$ feet. The space between the face walls to be filled in with gravel. The floor of the sluice to be 11.59 feet above mean tide. This sluice is designed to be capable of discharging the required quantity of water when there is but comparatively a small supply in the reservoir.

2. The shutters to be worked by screws, the general arrangement being the same as detailed for the auxiliary head sluice.

3. The masonry to be of dressed laterite in chunam and pointed with chunam.

DETAILED ESTIMATE No. 4.

PENNAIR DELTA.

Constructing a Head Sluice for Idagali Branch.

Particulars of Work	MEASUREMENT.				Cubical contents.
	Length.	Breadth.	Height or Depth.	No.	
Concrete	Feet.	Feet.	Feet.		Feet.
Concrete	50	15	1	...	581
Concrete	44	15	1	...	614
Concrete	16	1	2	8	416
Total...	...	...	...	...	1,511
Foundation — Abutments	...	...	...	...	...
Piers	10	5	5	2	577
Front wings	15	3	3	7	1,286
Rear do	28	4	4	2	1,664
Returns	18	5	5	2	1,020
Front retaining wall	15	4	6	2	150
Rear do	69	2	4	...	819
Superstructure — Abutments	40	2	5	...	800
Piers	10	3	4	...	315
Caps	12	2	4	7	856
Cutwaters	2	2	2	7	82
Skew backs	2	2	14	7	510
Do	10	2	3	7	43
Spandril	10	3	4	2	153
Face walls	4	10	4	...	320
Side do	45	2	5	...	1,706
Front wings	3	2	6	2	94
Coping	28	2	9	...	1,489
Rear wings	28	2	1	...	141
Coping	18	5	11	...	1,320
Coping	18	2	1	...	91

*Proceedings of the Madras Government, Public Works Department,
20th June 1867.*

Particulars of Work.	MEASUREMENT.				Cubical contents
	Length	Breadth.	Height or Depth.	No	
	Feet	Feet	Feet.		Feet.
Superstructure — Returns	15	2	8	2	610
Coping	15	2	1	2	76
Blocking courses	46	1	1	2	138
Parapets	45	1	2	2	182
Flooring	50	18	1	...	1,350
Do	44	18	1	...	1,201
Do	10	2	1	8	346
Do	10	6	1	8	756
Arch work	10	6	1	8	756
Total ..	...	...	...	...	17,872
Tamped graveling for spandrels	41	3	6	...	944
Or cubic yards	...	...	...	...	35
Pointing	...	...	...	...	63
Squares.	...	...	...	...	940
Earth-works	...	...	...	...	43
Cubic yards	...	...	...	...	8
Teak wood beam	1	...	...	...	...
Do shutters with working gear	...	...	...	...	...
Baling	...	...	...	...	...
Centering	...	...	...	...	...
Sundries	...	...	...	...	...

ABSTRACT ESTIMATE No. 4.

Quantities	Description of Work.	Rate.	Amount.	Total
		RS. A. P.	RS. A. P.	RS. A. P.
1,511	Cubic feet of concrete	0 2 0	188 15 4	
7,872	Do of laterite in chunam	0 2 8	2,978 11 7	
35	Cubic yards tamped graveling	0 2 0	4 6 0	
63	Squares of pointing	2 0 0	126 8 0	
940	Cubic yards of earth-work	0 1 0	58 12 0	
43	Cubic feet of teakwood	3 8 0	152 4 0	
8	Teakwood shutters with working gear.	40 0 0	320 0 0	
	Baling	...	450 0 0	
	Centering	...	50 0 0	
	Sundries	...	114 13 1	
				4,440 0 0

Proceedings of the Madras Government, Public Works Department.
20th June 1867.

DETAILED ESTIMATE No. 4.
PENNAIR DELTA.
Constructing Regulating Sluice at the Idagali Tank.

Particulars of Work.	MEASUREMENT.				Cubical contents
	Length	Breadth.	Height or Depth	No.	
Concrete	Feet.	Feet.	Feet		Feet.
Concrete	37 1/2	6	1	2	426
Concrete	9	4 1/2	1	...	40 1/2
Concrete	12	12	3	...	108
Total	...	...	...	...	574 1/2
Foundation.—Body	1 1/2	4 1/2	3 1/2	...	21 1/2
Wings	33 1/2	4	5	...	1,340
Retaining wall	11	2 1/2	5	1	137 1/2
Above.—Abutments	3 1/2	2 1/2	7	...	110 1/2
Backing to arch	2 1/2	2 1/2	3	...	13 1/2
Wings	30	2 1/2	9	...	1,215
Coping	30 1/2	2	3	...	91 1/2
Flooring	12	12	1 1/2	...	180
Arch work	4 1/2	3	1 1/2	...	15 1/2
Avart	3 1/2	4	1 1/2	...	17 1/2
Total...	...	...	...	...	3,143 1/2
Rubble stone (laterite)	15	12	1 1/2	...	270
Rubble stone (laterite)	15	3	1 1/2	...	67 1/2
Rubble stone (laterite)	5 1/2	3	1 1/2	...	25 1/2
Or Cubic yards ..	...	...	...	...	363 1/2
Teakwood shutter	3 1/2	3	10	...	13 1/2
Pointing	...	...	...	...	8 1/2
Iron bar	...	...	...	...	10
Earth work	...	...	...	...	4 1/2
Centering	...	...	...	...	154
Sundries	...	...	...	...	...

ABSTRACT ESTIMATE No. 4.

Quantities	Description of Work	Rate	Amount	Total.
575	Cubic feet of concrete	RS. A. P.	RS. A. P.	
3,143	Do laterite in chunam	0 2 0	71 14 0	12. A. P.
10	Squares of pointing	0 2 8	52 13 4	
13 1/2	Cubic yards of rubble stone laterite.	2 0 0	20 0 0	
19 1/2	Do of earth-work	1 8 0	20 3 0	
4 1/2	R feet of iron bar	0 1 0	12 2 0	
4 1/2	Cubic feet of teakwood shutter	...	7 0 0	
	Baling	3 8 0	24 7 0	
	Centering and sundries	...	10 0 0	
		...	16 8 8	
				800 0 0

Proceedings of the Madras Government, Public Works Department,
20th June 1867.

ABSTRACT ESTIMATE No. 4.

Quantities	Description of Work.	Rate.	Amount	Total.
305	Cubic feet of concrete	0 2 0	38 2 0	
951	Do laterite in chunam	0 2 8	158 8 0	
5 1/2	Cubic yards of rubble stone (laterite).	2 8 0	13 12 0	
3	Squares of pointing	2 0 0	6 0 0	
129	Cubic yards of earth-work	0 1 0	8 1 0	
1 1/2	Cubic feet of teak beam	3 8 0	2 6 6	
1	Shutter with working gear	...	12 0 0	
	Baling	...	10 0 0	
	Sundries	...	11 2 6	
	Total Estimate	...	...	260 0 0

Specification to accompany the Plan and Estimate for the Ipuru and Pudiparty Branch Head Sluice.

The barrel to be oval and 1 1/2 feet in thickness, the upper diameter being 4 1/2 feet, and the lower 3 1/2 feet; the sides to be described with a radius of 9 feet; the length of the barrel to be 9 feet; it will rest on a bed of concrete one foot thick; and be backed up by masonry on each side, for a height of 7 1/2 feet above concrete level. The front wings at the abutments will be 9 feet in height, and at the extremities 4 feet; the rear wings will be the same height at the abutments, but 5 feet at the extremities. The front wings to be 13 1/2 feet in length measured at right angles to the face of the work, and to be set out with a splay of 10 feet at the extremities, which will be connected by a retaining wall. The rear wings to be described with a radius of 11 feet and to be 18 feet in length measured perpendicularly from the face; the extremities to be connected by a retaining wall 5 feet in depth, with an average breadth of 2 1/2 feet. The flooring between the retaining walls and vent to be of laterite 1 1/2 feet in thickness, resting on a bed of concrete one foot thick. The shutters will consist of planks 5 feet x 3 inches x 10 feet; to facilitate the working of these and retain them in position two iron bars well be fixed across the vent. The masonry to be of dressed laterite in chunam.

DETAILED ESTIMATE No. 4.
PENNAIR DELTA.

Constructing Head Sluice for Ipuru and Pudiparty Branch.

Particulars of Work.	MEASUREMENT				Cubical contents
	Length	Breadth.	Height or Depth.	No.	
Barrel	Feet	Feet.	Feet		Feet
Barrel	9	22	1 1/2	...	247 1/2
Sides	9	1 1/2	7	2	180
Foundation.—Front wings	16 1/2	3 1/2	5	2	598 1/2
Rear do	26	3 1/2	5	2	975
Front retaining wall	24	2 1/2	5	1	270
Rear do do.	19 1/2	2 1/2	5	1	219 3/8

Proceedings of the Madras Government, Public Works Department,
20th June 1867.

DETAILED ESTIMATE No. 4.—(Concluded)

Particulars of Work.	MEASUREMENT.				Cubical contents
	Length.	Breadth	Height or Depth.	No.	
	Feet.	Feet.	Feet		Feet
Above—Front wings	16½	2½	6½	2	442½
Coping	17	2½	¾	2	51
Rear wings	26	2½	7	2	773½
Coping	26	2	¾	2	78
Face wall	8	3	1½	1	35
Do	8	1½	1½	1	18
Blocking course	8½	1½	1	2	25½
Parapets	8	1	1	2	16
Front flooring	15	12½	1½	1	229½
Rear do	20½	18	1½	1	461½
Total cubic feet of laterite in chunam.					4,630½
Concrete	9	10	1	..	90
	27½	5½	1	2	316½
	18	5½	1	2	202½
	20	18	1	..	360
	15	12	1	..	180
Total cubic feet .					1,148½
Pointing Squares					12
Excavation Cubic yards ..					343
Iron bars Running feet ..					11½
Teak-wood shutters	5	3"	10		12½ C ft.
Baling					
Centering and sundries					

ABSTRACT ESTIMATE No. 4.

Quantities	Description of Work.	Rate	Amount	Total.
		RS. A. P.	RS. A. P.	RS. A. P.
1,149	Cubic feet of concrete	0 2 0	143 10 0	
4,631	Do. of laterite in chunam	0 2 8	771 13 4	
12	Squares of pointing	2 0 0	24 0 0	
343	Cubic yards of excavation	0 1 0	21 7 0	
11½	Running feet of iron bars	3 8 0	43 12 0	
12½	Cubic feet of teakwood shutters		50 0 0	
	Baling		31 13 8	
	Centering and sundries			
	Total Estimate...			1,100 0 0

Proceedings of the Madras Government, Public Works Department
20th June 1867.

ABSTRACT ESTIMATE No. 4.

PENNAIR DELTA.

Constructing fall in Idagaly Branch Channel, vide Plan No. 3.

Quantities	Description of Work.	Rate.	Amount.	Total.
		RS. A. P.	RS. A. P.	RS. A. P.
640	Cubic feet of concrete	0 2 0	80 0 0	
4,377	Do. of laterite in chunam	0 2 8	729 8 0	
10½	Squares of pointing	2 0 0	21 0 0	
19½	Cubic yards of rubble stone (laterite)	1 8 0	29 11 7	
280	Do. of earth-work	0 1 0	17 8 0	
4½	Running feet of iron bars		6 12 0	
5½	Cubic feet of teak-wood shutters	3 8 0	18 10 8	
	Baling		50 0 0	
	Sundries		16 13 9	
	Total Estimate...			970 0 0

DETAILED ESTIMATE No. 4.

PENNAIR DELTA.

Constructing fall to the Pudupatty Tank, vide Plan No. 2.

Particulars of Work.	MEASUREMENT.				Cubical contents.
	Length.	Breadth.	Height or Depth.	No.	
	Feet.	Feet.	Feet		Feet.
Concrete	7½	7	1	...	21½
	7½	8	1	2	112
	10½	6½	1	2	136½
	12½	7	1	2	175
	7½	6	1	2	90
	12	5	1	...	60
	12	12	½	..	108
Total...					684
Foundation—Body	2½	5	5	1	60½
Wings	7	6	5	2	420
Front returns	9½	4½	5	2	427½
Wings	13	5	5	2	650
Rear returns	6½	4	5	2	260
Retaining wall	12	3	5	...	180
Above—Body	3½	3½	7	...	83½
Wings	7	3½	13	2	591½
Coping	4	2	½	2	12
Returns	9	2½	10	2	450
Coping	9½	2	½	2	27½
Wings	13	2½	11	2	786½
Coping	13½	2	½	2	39½
Returns	6	2½	9	2	243
Retaining wall	12	2	3	1	72
Flooring	12	12	1½	.	180
String course	6½	½	½	...	1½
Arch-work	4½	2½	½	...	9½
Total.					4,514

Proceedings of the Madras Government, Public Works Department.
20th June 1867.

DETAILED ESTIMATE No. 4.—(Concluded.)

Particulars of Work.	MEASUREMENT				Cubical contents.
	Length.	Breadth.	Height or Depth.	No.	
Rubble stone (laterite) ... {	Feet. 12	Feet. 10	Feet. 1½	...	Feet. 180
	10	2	10	2	400
Teak-wood shutter					580 or 21½
Earth-work	3½	3'	6½	...	...
Iron bars ... Cubic yards	...	...	...	...	...
Pointing ... R feet.	...	...	...	...	300
Baling ... Squares.	...	...	...	...	5
Centering and sundries	...	...	...	...	11½

ABSTRACT ESTIMATE No. 4.

Quantities.	Description of Work.	Rate.	Amount.	Total.
684	Cubic feet of concrete	RS. A. P.	RS. A. P.	RS. A. P.
4,514	Do. of laterite in chunam	0 2 0	85 8 0	...
11½	Squares of pointing	0 2 8	752 5 4	...
21½	Cubic yards of rubble stone laterite.	2 0 0	23 0 0	...
300	Do. of earth-work	1 8 0	32 3 7	...
5	R feet of iron bars	0 1 0	18 12 0	...
6½	Cubic feet of teak-wood shutter	...	8 2 0	...
	Baling	3 8 0	23 10 0	...
	Centering and sundries	...	75 0 0	...
	Total Estimate...	...	21 7 1	1,040 0 0

DETAILED ESTIMATE No. 4.
PENNAIR DELTA.

Excavating Valluru Branch Channel.

Particulars of Work.	MEASUREMENT.				Cubical contents.	Rates per Cubic yard.
	Length.	Breadth.	Height or Depth.	No.		
Head sluice, vide separate Estimate.	Feet.	Feet.	Feet.		Feet.	RS. A. P.
Cutting ...	1,320	17	4	1	89,760	0 1 0
Banking ...	1,320	20	2	1	52,800	0 1 0
Turfing ...	1,320	23	...	1	60,720	0 0 4
Cutting ...	3,960	15	4	1	237,600	0 1 0
Banking ...	3,960	24	2	1	190,180	0 1 0
Turfing ...	3,960	23	...	1	182,160	0 0 4
2nd mile—Cutting	1,980	18½	5½	1	204,187½	0 1 1

Proceedings of the Madras Government, Public Works Department.
20th June 1867.

DETAILED ESTIMATE No. 4.—(Concluded.)

Particulars of Work.	MEASUREMENT.				Cubical contents	Rate per Cubic yard.		
	Length	Breadth.	Height or Depth.	No.		RS.	A.	P.
	Feet.	Feet.	Feet.		Feet.			
2nd mile—Cutting ...	1,320	17½	4½	1	107,800	0	1	0
... Cutting ...	1,980	18½	5½	1	204,187½	0	1	1
3rd mile—Cutting ...	2,640	17½	4½	1	204,930	0	1	0
... Cutting ...	2,640	13½	3½	1	130,680	0	1	0
... Banking ...	2,640	37	2	1	195,360	0	1	0
... Turfing ...	2,640	25	...	2	132,000	0	0	4
4th mile—Cutting ...	5,280	10	2½	1	132,000	0	1	0
... Banking ...	5,280	86½	2	1	913,440	0	1	2
... Turfing ...	5,280	32	...	2	337,920	0	0	4
5th mile—Cutting ...	2,640	8	2	1	42,240	0	1	0
... Banking ...	2,640	105	2	1	534,400	0	1	2
... Turfing ...	2,640	34	...	2	179,520	0	0	4
Fall ...	...	...	...	...	...	...	...	...
Cutting ...	2,640	24½	4½	1	272,250	0	1	0
6th mile—Cutting ...	1,980	25½	4½	1	235,620	0	1	0
Regulator ...	...	...	...	...	...	...	...	...
Irrigation Sluices (six) ...	...	...	...	...	...	...	...	...
Minor branch channels, aggregate length 6 miles ...	...	...	...	...	...	...	...	...
Compensation for land ...	...	...	...	...	...	...	...	...

ABSTRACT ESTIMATE No. 4.

Quantities.	Description of Work.	Rate.	Amount.	Total.
		RS. A. P.	RS. A. P.	RS. A. P.
1	Head-sluice, vide separate estimate	...	...	3,080 0 0
15,125	Cubic yards of cutting	0 1 1	1,024 1 5	...
53,810	Do. of do.	0 1 0	3,363 2 0	4,387 3 5
54,364	Do. of banking	0 1 2	3,964 0 8	...
16,235	Do. of do.	0 1 0	1,014 11 0	4,978 11 8
99,146	Square yards of turfing	0 0 4	2,065 8 8	2,065 8 8
1	Fall, vide separate estimate	...	...	3,100 0 0
1	Regulator do do	...	...	1,730 0 0
6	Irrigation sluices, vide Plan No. 1.	340 0 0	...	2,040 0 0
	Minor branch channels	...	...	2,640 0 0
1	Fall in Pantapollem branch channel, vide Plan No. 3	...	...	1,350 0 0
	Compensation for land	...	...	1,800 0 0
6	Distributing channels	100 0 0	...	600 0 0
	Sundries	...	...	68 8 3
	Total Estimate..	...	...	27,840 0 0

Proceedings of the Madras Government, Public Works Department.
20th June 1867.

DETAILED ESTIMATE No. 4.
PENNAIR DELTA.
Constructing Head Sluice for Valluru Branch Channel.

Particulars of Work.	MEASUREMENT.				Cubical contents.
	Length.	Breadth.	Height or Depth.	No.	
Concrete.—Abutments	Feet	Feet	Feet.		Feet.
Piers	7½	8½	3	2	98½
Front wings	11	17½	3	2	144½
Rear do.	31½	7½	3	2	345½
Front retaining wall	23½	7½	3	2	267½
Rear do. do	38½	5	3	2	144½
Below flooring	4½	5	3	2	167½
Front apron	15½	7½	4	3	169½
Rear do	26½	14½	3	2	338½
Spandril	12	14½	3	2	130½
	11	3½	4½	2	202½
Total cubic feet of Concrete	...	...	...	...	1,877½
Foundation.—Abutments	8½	5½	6	2	603½
Piers	15½	4½	6	2	777½
Front wings	30½	5	5½	2	1,730½
Rear do	21½	5½	5½	2	1,352½
Front retaining wall	40½	2½	6	2	611½
Rear do do	6½	2½	5½	2	111½
Superstructure.—Abutments	8½	3½	5½	2	369½
Piers	11½	3	5½	2	375½
Front portion	2½	3	14½	2	224½
Caps	2½	3	2½	2	40½
Skew backs	8½	3	2½	2	13½
Front wings	30	2½	9½	2	1,456½
Coping	30½	2	1	2	121
Rear wings	21	2½	10½	2	1,212½
Coping	21½	2	1	2	85
Front flooring	27½	17½	1½	2	854½
Rear flooring	13	18½	2	2	481
Flooring between arches	10½	2½	2	3	151½
Backing to arches	8½	4	1½	2	79
Spandril	12	8½	1½	2	157½
Face walls	17	2½	6½	2	471½
Do sides	4½	1½	4½	2	60½
Parapets	16½	1	1	2	33
Total cubic feet of Laterite in chunam	...	...	...	...	11,429½
Arch work	8½	5½	1½	3	216½
Pointing	...	...	...	...	31½
Rubble stone (laterite)	20	8	2½	...	400
Do. do.	20	9	2½	...	720
Total...	...	...	...	2	1,120
Or cubic yards.	...	...	...	...	411½
Excavation, Cubic yards	...	...	...	...	1,133
Metaling, Cubic yards	...	...	...	...	4

Proceedings of the Madras Government, Public Works Department,
20th June 1867.

DETAILED ESTIMATE No. 4 — (Concluded.)

Particulars of Work.	MEASUREMENT				Cubical contents
	Length	Breadth.	Height or Depth.	No	
	Feet	Fect.	Feet		Feet
Shutters	16½	1	1	...	16½ C feet
Teak beam	...	...	...	...	...
Baling	...	...	...	...	...
Centering	...	...	...	...	...
Sundries	...	...	...	...	...

ABSTRACT ESTIMATE No. 4.

Quantities	Description of Work	Rate.			Amount.			Total		
		RS	A	P.	RS	A	P.	RS	A	P.
1,898	Cubic feet of concrete	0	2	0	237	4	0			
11,410	Do. of laterite in chunam	0	3	1	2,204	9	4			
217	Do. of arch-work	0	3	4	45	3	4			
31½	Squares of pointing	2	0	0	63	0	0			
41½	Cubic yards of rubble stone (laterite)	1	2	0	46	11	0			
1,138	Do. of earth-work	0	1	0	71	2	0			
4	Do. of metaling	0	14	0	3	8	0			
3	Shutters with working gear...	40	0	0	120	0	0			
16½	Cubic feet of teakwood	3	8	0	57	12	0			
	Baling	...	...	...	150	0	0			
	Centering	...	...	...	15	0	0			
	Sundries	...	...	...	65	14	4			
	Total Estimate	...	...	...	...	...	...	3,080	0	0

Specification to accompany the Plan and Estimate for the Fall proposed for construction near the Bramadavum Tuti Tank.

The body wall to be 8 feet in height, the breadth at bottom and crest being 4½ and 3 feet respectively. The length of the body wall to be 4½, in rear of the body wall a cistern with curved flank and 15 feet in length and 16½ in greatest breadth to be constructed to retain a depth of 4 feet of water, the flooring of the cistern to consist of 1½ feet of laterite and 9 inches of concrete. The rear wings to be connected by a retaining wall 5 feet in depth, the breadth at bottom being 4½ feet, and 2 feet at the level of the flooring. The rear wings to be 16½ in height and the front 12 feet, the average breadth of the former being 4 feet 1½ inches, and that of the latter 3 feet. A foot-bridge to be thrown over the crest of the weir with a groove of 6 inches in it to admit of the shutters being worked, and to prevent these getting jammed during the working. Three iron bars will be built in, above the crest of the weir, at 1 foot 10 inches apart.

The masonry to be of dressed laterite in chunam.

*Proceedings of the Madras Government, Public Works Department,
20th June 1867.*

DETAILED ESTIMATE No. 4.
PENNAIR DELTA.

Constructing Fall near the Bramadavum Tutu Tank, in the Valluru Pranch Channel No 1

Particulars of Work.	Number	MEASUREMENT.			Cubical contents.
		Length	Breadth	Height	
		Feet.	Feet	Feet.	Feet.
Concrete ...	23 1/2	8 1/2	1	...	20 1/2
	23 1/2	8 1/2	1	...	406 1/2
	18 1/2	9 1/2	1	...	340 1/2
	7 1/2	8	1	...	120
	15	13 1/2	9	...	153
	13 1/2	5 1/2	1	...	72 1/2
Total ..		...	...	...	1,114 1/2
Foundation—Body ..	4 1/2	6	5	...	142 1/2
Front wings	11	8	5	...	880
Returns	12	8	5	...	960
Rear wings	18 1/2	6 1/2	5	...	1,283 1/2
Returns	7 1/2	5 1/2	5	...	431 1/2
Retaining wall	13 1/2	3 1/2	5	...	215 1/2
Above—Body ..	4 1/2	3 1/2	8	...	147 1/2
Front wings	11	4 1/2	16 1/2	...	1,497 1/2
Coping	7 1/2	2 1/2	13 1/2	...	23 1/2
Returns	12	4 1/2	13 1/2	...	1,336 1/2
Rear wings	18 1/2	3 1/2	14 1/2	...	1,895 1/2
Coping	1 1/2	2 1/2	12 1/2	...	56
Returns	7 1/2	3	12 1/2	...	540
Coping	7 1/2	3	12 1/2	...	23 1/2
Retaining wall	13 1/2	2	4	...	106 1/2
Flooring	15	18 1/2	1	...	255 1/2
Parapets	4 1/2	6	...	...	5 1/2
Arch-work ..	4 1/2	6	...	...	21 1/2
Total ..		...	...	...	9,819 1/2
Rubble stone (laterite) ...	18	15	2	...	540
	18	2	13	...	936
Pointing ...	...	...	...	...	1,476
Iron bar ...	...	...	...	...	54 1/2
Teak-wood shutter	...	...	...	...	2 1/2
Earth-work ...	5 1/2	3 1/2	...	...	18 1/2
Baling ..	...	...	...	...	12 1/2
Sundries ..	...	...	...	...	700

ABSTRACT ESTIMATE No. 4.

Quantities	Description of Work.	Rate	Amount.	Total
1,114	Cubic feet of concrete	Rs. A. P.	Rs. A. P.	Rs. A. P.
9,819	Do. of laterite in chunam	0 2 0	139 12 0	
23 1/2	Squares of pointing...	0 4 0	2,454 12 0	
54 1/2	Cubic yards of rubble stone (laterite)	2 0 0	47 0 0	
700	Do. of earth-work	2 8 0	136 10 8	
18 1/2	Running feet of iron bars	0 1 0	43 12 0	
12 1/2	Cubic feet of teakwood shutters	...	25 11 0	
	Baling...	3 8 0	42 7 0	
	Sundries	...	150 0 0	
		...	59 15 4	
	Total Estimate...	...	...	3 100 0 0

*Proceedings of the Madras Government, Public Works Department,
20th June 1867.*

Specification to accompany the Plan and Estimate for the Regulator proposed for construction near the Valluru Tanks.

The Regulator to consist of two vents one 4 feet span, the other 11 1/2 feet. The front wings to be 6 feet in height and 2 feet in breadth on the average; and returns to be 6 feet in height and 2 1/2 in breadth on the average, there will be two retaining walls on each vent. The two vents to be connected by a curved-wall as shown in plan. Each sluice will be adapted to carry a stone bridge for foot passengers. The planks for regulating the supply of water will be fitted immediately in front of the bridges; and two iron bars will be built in, across each vent, to guide the planks, and retain them in position. The masonry to be of dressed laterite in chunam. The front and rear aprons to be of packed rubble 1 1/2 feet and 2 feet thick respectively, with revetted slopes.

DETAILED ESTIMATE No. 4.
PENNAIR DELTA.

Constructing Regulator near Valluru Tank in the Valluru Branch Channel.

Particulars of Work.	MEASUREMENT.			Cubical contents
	Length	Breadth.	Height or Depth	
	Feet.	Feet.	Feet	Feet.
Concrete.—Wings	17 1/2	6	1	106 1/2
Do.	21 1/2	6	1	130 1/2
Curved portions	9 1/2	6 1/2	1	61 1/2
Returns	5	6 1/2	1	130
Abutments	11	7	1	154
Do.	11	6	1	132
Retaining wall	8	4 1/2	1	36
Do.	8	5	1	40
Do.	1/2	4 1/2	1	2 1/2
Do.	1/2	5	1	2 1/2
Do.	10 1/2	5 1/2	1	61 1/2
Flooring	3	5 1/2	1	17 1/2
Do	...	...	...	...
Total cubic feet...	...	...	...	874 1/2
Foundation—Wings	16 1/2	3 1/2	5	311 1/2
Do	20 1/2	3 1/2	5	386 1/2
Curved portions	9 1/2	4 1/2	5	201 1/2
Returns	5	4 1/2	5	425
Abutments	9 1/2	4 1/2	5	469 1/2
Do	9 1/2	3 1/2	5	370 1/2
Retaining wall	10 1/2	2 1/2	5	140 1/2
Do	10 1/2	2 1/2	5	115 1/2
Do	2 1/2	2 1/2	5	37 1/2
Do	2 1/2	2 1/2	5	30 1/2
Wings	16	2	6	192
Do	20	2	6	240
Curved portions	9 1/2	2 1/2	6	137 1/2
Returns	5	2 1/2	6	270
Abutments	8 1/2	3	4 1/2	214 1/2
Do.	8 1/2	2	6	204
Skew backs	8 1/2	2	2	25 1/2
Do	8 1/2	1	2	10 1/2
Backing to arch	8 1/2	4 1/2	2	28 1/2
Do	8 1/2	1 1/2	2	3 1/2
Face walls	16 1/2	1 1/2	1 1/2	80 1/2
Do	7	1 1/2	2	15 1/2
Blocking course	17	1 1/2	2	38 1/2
Do	7 1/2	1 1/2	2	16 1/2
Parapet	16 1/2	1	1	33
Do	7	1	2	14
Flooring	11 1/2	6 1/2	1 1/2	107 1/2
Do.	3 1/2	6 1/2	1 1/2	35 1/2
Arch-work	8 1/2	14 1/2	1 1/2	154 1/2
Do.	8 1/2	6 1/2	1 1/2	73 1/2
Total cubic feet of laterite in chunam...	...	...	...	4,386 1/2

*Proceedings of the Madras Government, Public Works Department,
20th June 1867.*

DETAILED ESTIMATE No. 4.—(Concluded).

Particulars of Work	MEASUREMENT.				Cubical contents.
	Length	Breadth.	Height or Depth	Number	
Pointing, squares	Feet.	Feet	Feet.		Feet.
Rubble stone for outer apron	16½	8	2	...	13
Do. inner do	7	8	2	...	20½
Do do.	11½	5	1½	...	11½
Do do.	5½	5	1½	1	10½
Revetment	10½	1	1½	1	43½
	5	5	1½	1	15½
				4	251½
Total cubic feet	...	...	...		793 or
Cubic yards	...	...	...		291½
Excavation, Cubic yards	295				
Teakwood shutters	12	3"	11	...	33
Do.	4½	3"	11	...	12½
Total cubic feet	...	...	...		45½
Running feet	...	...	...		37
Iron bars	...	...	...		
Baling	...	...	...		
Centering and sundries	...	...	...		

ABSTRACT ESTIMATE No 4.

Quantities.	Description of Work	Rate.	Amount	Total.
875	Cubic feet of concrete	RS 0 2 0	RS 109 6 0	RS
4,386	Do of laterite in chunam	0 4 0	1,096 8 0	
13	Squares of pointing	2 0 0	26 0 0	
29½	Cubic yards of rubble stone (laterite)	2 8 0	73 12 0	
295	Do of excavation	0 1 0	18 7 0	
45½	Cubic feet of teakwood shutters	3 8 0	158 13 0	
37	Running feet of iron bars		47 6 0	
	Baling		150 0 0	
	Centering and sundries		51 12 0	
	Total Estimate ..			1,730

Specification to accompany the Plan and Estimate for the Valluru Branch Head Sluice.
The front wings to be 14 feet 3 inches at the abutments, and 4½ feet at the extremities; the average breadth of the former being 3½ feet, and that of the latter 1½ feet. The front wings to be connected by a retaining wall 5 feet in depth, the breadth at bottom being 4 feet, and at floor level 1½ feet; between this retaining wall and the vents there will be a floor of laterite 1½ feet in thickness, and a bed of concrete 9 inches thick. The flooring in the bays to consist of 2 feet of laterite and 9 inches of concrete; the flooring between the bays and the rear retaining wall to be of like section. The sluice will have three vents of 2½ feet span; the height of the piers being 5½ feet. The face walls to be 6½ feet in height with an average breadth of 2½ feet; the space between the spandrels to be filled in with concrete. The rear wings to be 14 feet in height at the abutments, and 7 feet at the extremities, these will be connected by a retaining wall 6 feet in depth with an average breadth of 2½ feet. The side slopes of the channel in rear will be pitched for a length of 20 feet. Beyond the rear retaining wall there will be a rubble apron 20 feet x 8 feet x 2½ feet. The length of the floor to be 24.32 feet above mean tide.

*Proceedings of the Madras Government, Public Works Department,
20th June 1867*

The shutters to be worked by screws.
The masonry to be of dressed laterite in chunam.

DETAILED ESTIMATE No. 4.
PENNAIR DELTA.
Constructing an Irrigation Sluice as per Plan No 1.

Particulars of Work.	MEASUREMENT				Cubical contents.
	Length.	Breadth	Height or Depth	No.	
	Feet.	Feet.	Feet		Feet.
Concrete ..	6½	8½	1½	...	43½
	1½	4½	1	...	6½
	15	4½	1	2	142½
	12½	4½	1	2	112½
Total	...	...	...	...	305
Barrel ...	10	8	1½	1	100
Retaining wall...	2	2½	4½	1	20½
Do	1	2½	4½	1	10½
Foundation—Front wings	13	2½	4½	2	321½
Rear wings	10½	2½	4½	2	230½
Above—Front do.	12	1-5½	3½	2	120½
Rear do	9½	1½	4	2	11½
Front face wall	3-9½	1½	3½	1	17½
Rear do.	3-9½	1½	1½	1	8½
Parapet-	2-9½	1	1	1	2½
Total	...	...	...	...	951
Rubble stone (laterite)	10	7	1½	...	105
	7	3½	2	...	45½
Total	...	...	...	...	150½
Cubic yards.	...	...	...	...	5½
Squares	...	...	...	...	3
Pointing	...	...	...	...	129
Earth-work	...	...	...	...	1½
Teak beam	...	...	...	...	
Shutter with working gear	...	...	...	...	
Sundries ..	...	...	...	...	

ABSTRACT ESTIMATE No. 4.

Quantities	Description of Work.	Rate	Amount.	Total.
		RS. A. P.	RS. A. P.	RS. A. P.
305	Cubic feet of concrete	0 2 0	38 2 0	
951	Do. of laterite in chunam	0 4 0	237 12 0	
5½	Cubic yards of rubble stone (laterite)	2 8 0	13 12 0	
3	Squares of pointing	0 1 0	8 1 0	
129	Cubic yards of earth-work	3 8 0	2 6 6	
1½	Cubic feet of teak beam	...	12 0 0	
1	Shutter with working gear	...	10 0 0	
	Baling	...	11 14 6	
	Sundries	...		
	Total Estimate...	...	...	340 0 0

DETAILED ESTIMAE No. 4.

PENNAIR DELTA.

Constructing Fall in Pantapalem Branch Channel, vide Plan No. 3.

Particulars of Work	MEASUREMENT				Cubical contents
	Length	Breadth	Height or Depth.	Number	
	Feet	Feet	Feet		Feet
Concrete	7	8	1	2	112
	10½	6½	1	2	136½
	12½	7	1	2	175
	7½	6	1	2	90
	9	5	1		45
	12	9	1		81
Total cubic feet of Concrete .	...	...	...	...	694
Foundation—Body wall	12½	5	5	1	112
Wings	7	6	5	1	42
Front returns	9½	4½	5	2	127½
Wings	13	5	5	2	670
Rear returns	6½	4	5	2	260
Retaining wall	9	3	5	2	135
Above—Body wall	23	3½	7		65½
Wings	7	3½	13	2	591½
Coping	4	2	10	2	12
Returns	9	2½	10	2	450
Coping	9½	2	11	2	27½
Wings	13	2½	11	2	786½
Coping	13½	2	9	2	391
Returns	6	2½	9	2	243
Coping	6½	2	3	2	28½
Retaining wall	9	2	1½	1	54
Flooring	12	9	1½		135
String course	5½	1½			1½
Arch	4	2½			8½
Total cubic feet of laterite in chunam ..	...	...			4,376½
Pointing Squares	...	...			10½
Rubble Stone	9	10	1½		135
Do.	10	2	10	2	400
Total cubic feet					535
Or Cubic yards					191½
Excavation Cubic yards ..					280
Iron bars Running feet.					4½
Teak wood shutter	3½	3"	6½		5½ C. ft
Baling					
Sundries					

ABSTRACT ESTIMATE No. 4.

Quantities	Description of Work	Rate			Amount			Total		
		RS.	A.	P.	RS.	A.	P.	RS.	A.	P.
640	Cubic feet of concrete ...	0	2	0	80	0	0			
4,377	Do of laterite in chunam ...	0	4	0	1,091	4	0			
10½	Squares of pointing ...	2	0	0	21	0	0			
19½	Cubic yards of rubble stone (laterite)	2	8	0	49	8	7			
280	Do of earth-work ...	0	1	0	17	8	0			
4½	Running feet of iron bars ..	...	...	...	6	12	0			
5½	Cubic feet of teak-wood shutters	3	8	0	18	10	8			
	Baling	...	...	...	50	0	0			
	Sundries	...	...	...	12	4	9			
	Total Estimate	...	...	...				1350	0	0

Specification to accompany Plan No. 2 (General) for Irrigation Sluices.

The wings to be 7 feet in height, the breadth at bottom and top being 2½ and 1½ feet respectively. The barrel to be 6 feet in length, and 1½ feet in thickness, the inside diameter being 2 feet 6½ inches, it will rest on a bed of concrete 9 inches in thickness. The barrel will be backed with masonry, on each side to a height of 2 feet 6 inches above concrete level. The front wings to be 8, in length measured at right angles to the face of the arch and let out with a splay of 2½ at the extremities. The rear wings to be also 7½ feet in length, described with a radius of 4½ feet. There will be three retaining walls, one under the shutter, the second at the opposite end of the barrel, and the third at the extremities of the rear wings; the space between the second and third to be filled in with 2 feet of rubble stone carefully packed immediately in front of the first retaining wall; there will be a rubble apron 5 in length and 1½ feet in depth. The shutter to be worked by a screw. The masonry to be of dressed laterite in chunam.

Specification to accompany the General Plan for Bridges proposed for construction across the Sarvapully Main Branch Channel.

The bridge to consist of two arches of 15 feet span, the rise being 4 feet. The height of the pier and abutments to be 10 feet, the former being 3 feet and the latter 5 feet in breadth. The arches to be 2 feet in thickness at the springing line, 1½ at the crown. The floor to be an invert 1 foot in thickness with a versed sine of 1 foot; the invert will rest on a layer of concrete 9 inches thick. The wings to be 16 feet in height at the abutments, and 6 feet at the extremities. The depth of the foundation to be reduced by steps of 1 foot up and 2 feet or for a length of 16 feet, and carried on this level 7½, making the total length 23½ feet.

The road-way to be 12 feet in breadth with parapets of 3 feet in height.

The masonry to be of dressed laterite in chunam and pointed with chunam.

*Proceedings of the Madras Government, Public Works Department,
20th June 1867.*

SYNOPSIS showing the General state of the Pennair from 1861 to 1865 inclusive

Years.	Water 3 feet and upwards on Crest of Anicut	Water 2 feet on Crest of Anicut	Water 1 foot on Crest of Anicut	Water 1 foot on Crest of Anicut	Water 1 foot on Crest of Anicut	Water 1 foot on Crest of Anicut	Water 1 foot on Crest of Anicut	Water 1 foot on Crest of Anicut	Water 1 foot on Crest of Anicut	Water 1 foot on Crest of Anicut
1861	2	...	4	6	12	5	32	10	21	...
1862	10	2	11	5	12	2	40	7	11	...
1863	1	1	4	5	9	1	26	1	21	...
1864	11	1	4	4	5	5	25	21	12	...
1865	11	5	5	4	9	2	27	21	25	...
Total days	35	9	18	24	47	15	150	60	100	...
Average during the five years	7	1½	5½	4½	9½	3	30	12	20	...

Flush with or above Crest for 62 days only.

STATEMENT showing the number of days in each year, from 1861 to 1865, inclusive, in which the Pennair rose to three feet and upwards, above the Crest of the Anicut, and fell to one foot below it.

Years.	Months.	Water 3 feet and upwards on Crest	Water 2 feet on Crest	Water 2 feet on Crest	Water 1 foot on Crest	Water 1 foot on Crest	Water 1 foot on Crest	Water 1 foot on Crest	Water 1 foot on Crest	Water 1 foot on Crest
1861.	January	...	...	...	...	...	...	...	...	...
	February	...	...	...	...	...	...	...	...	...
	March	...	...	...	...	...	...	...	...	...
	April	...	...	...	...	...	...	...	...	...
	May	...	...	...	...	...	...	...	...	...
	June	...	...	...	...	...	...	...	...	...
	July	...	...	...	...	...	...	...	...	...
	August	...	...	...	...	...	...	...	...	...
	September	...	...	...	...	...	...	...	...	...
	October	...	...	...	...	...	...	...	...	...
	November	...	...	...	...	...	...	...	...	...
	December	...	...	...	...	...	...	...	...	...
1862.	January	...	...	...	...	...	...	...	...	...
	February	...	...	...	...	...	...	...	...	...
	March	...	...	...	...	...	...	...	...	...
	April	...	...	...	...	...	...	...	...	...
	May	...	...	...	...	...	...	...	...	...
	June	...	...	...	...	...	...	...	...	...
	July	...	...	...	...	...	...	...	...	...
	August	...	...	...	...	...	...	...	...	...
	September	...	...	...	...	...	...	...	...	...
	October	...	...	...	...	...	...	...	...	...
	November	...	...	...	...	...	...	...	...	...
	December	...	...	...	...	...	...	...	...	...
1863.	January	...	...	...	...	...	...	...	...	...
	February	...	...	...	...	...	...	...	...	...
	March	...	...	...	...	...	...	...	...	...
	April	...	...	...	...	...	...	...	...	...
	May	...	...	...	...	...	...	...	...	...
	June	...	...	...	...	...	...	...	...	...
	July	...	...	...	...	...	...	...	...	...
	August	...	...	...	...	...	...	...	...	...
	September	...	...	...	...	...	...	...	...	...
	October	...	...	...	...	...	...	...	...	...
	November	...	...	...	...	...	...	...	...	...
	December	...	...	...	...	...	...	...	...	...
1864.	January	...	...	...	...	...	...	...	...	...
	February	...	...	...	...	...	...	...	...	...
	March	...	...	...	...	...	...	...	...	...
	April	...	...	...	...	...	...	...	...	...
	May	...	...	...	...	...	...	...	...	...
	June	...	...	...	...	...	...	...	...	...
	July	...	...	...	...	...	...	...	...	...
	August	...	...	...	...	...	...	...	...	...
	September	...	...	...	...	...	...	...	...	...
	October	...	...	...	...	...	...	...	...	...
	November	...	...	...	...	...	...	...	...	...
	December	...	...	...	...	...	...	...	...	...
1865.	January	...	...	...	...	...	...	...	...	...
	February	...	...	...	...	...	...	...	...	...
	March	...	...	...	...	...	...	...	...	...
	April	...	...	...	...	...	...	...	...	...
	May	...	...	...	...	...	...	...	...	...
	June	...	...	...	...	...	...	...	...	...
	July	...	...	...	...	...	...	...	...	...
	August	...	...	...	...	...	...	...	...	...
	September	...	...	...	...	...	...	...	...	...
	October	...	...	...	...	...	...	...	...	...
	November	...	...	...	...	...	...	...	...	...
	December	...	...	...	...	...	...	...	...	...

*Proceedings of the Madras Government, Public Works Department,
20th June 1867.*

STATEMENT showing the number of days in each year, from 1861 to 1865, inclusive, in which the Pennair rose to three feet and upwards, &c — (Concluded.)

Years.	Months.	Water 3 feet and upwards on Crest	Water 2 feet on Crest	Water 2 feet on Crest	Water 1 foot on Crest	Water 1 foot on Crest	Water 1 foot on Crest	Water 1 foot on Crest	Water 1 foot on Crest	Water 1 foot on Crest
1863.	January	...	...	...	...	...	...	...	...	...
	February	...	...	...	...	...	...	...	...	...
	March	...	...	...	...	...	...	...	...	...
	April	...	...	...	...	...	...	...	...	...
	May	...	...	...	...	...	...	...	...	...
	June	...	...	...	...	...	...	...	...	...
	July	...	...	...	...	...	...	...	...	...
	August	...	...	...	...	...	...	...	...	...
	September	...	...	...	...	...	...	...	...	...
	October	...	...	...	...	...	...	...	...	...
	November	...	...	...	...	...	...	...	...	...
	December	...	...	...	...	...	...	...	...	...
1864.	January	...	...	...	...	...	...	...	...	...
	February	...	...	...	...	...	...	...	...	...
	March	...	...	...	...	...	...	...	...	...
	April	...	...	...	...	...	...	...	...	...
	May	...	...	...	...	...	...	...	...	...
	June	...	...	...	...	...	...	...	...	...
	July	...	...	...	...	...	...	...	...	...
	August	...	...	...	...	...	...	...	...	...
	September	...	...	...	...	...	...	...	...	...
	October	...	...	...	...	...	...	...	...	...
	November	...	...	...	...	...	...	...	...	...
	December	...	...	...	...	...	...	...	...	...
1865.	January	...	...	...	...	...	...	...	...	...
	February	...	...	...	...	...	...	...	...	...
	March	...	...	...	...	...	...	...	...	...
	April	...	...	...	...	...	...	...	...	...
	May	...	...	...	...	...	...	...	...	...
	June	...	...	...	...	...	...	...	...	...
	July	...	...	...	...	...	...	...	...	...
	August	...	...	...	...	...	...	...	...	...
	September	...	...	...	...	...	...	...	...	...
	October	...	...	...	...	...	...	...	...	...
	November	...	...	...	...	...	...	...	...	...
	December	...	...	...	...	...	...	...	...	...

(Signed) R. SMITH,
Executive Engineer, Nellore Range.

CAMP, NELLORE,
3rd April 1867.

(Signed) G. V. WINSOM, Lieut.-Colonel, R. E.,
Superintending Engineer, 2nd Division.

Proceedings of the Madras Government, Public

Estimated Acreage available as marked down by Department

No	Names of Villages.	DEDUCT.					
		Total area.	Area reserved for public purposes.	Area not fit for cultivation.	Wet and garden area irrigated under the existing irrigation sources.		Total.
					Koru or Government land on ordinary rates.	Inam or favourable tenure.	
	<i>Guduru Talook.</i>	Acres.	Acres.	Acres.	Acres.	Acres.	Acres.
1	Sarvapally...	22,364	3,887	71	2,793	419	7,200
2	Anikepally and Golagamudi	2,813	820	3	182	24	1,029
3	Idagaly and Kakarlapalem.	4,349	1,134	21	717	128	2,000
4	Ipuru ...	15,648	3,326	1,156	2,131	205	6,908
5	Pudiparty ...	5,113	82	...	568	147	797
6	Penubarty...	3,066	115	...	862	148	1,125
7	Brawhadam and Lingapalem	3,418	669	...	1,243	503	2,415
8	Tallapudy and Valluru ...	2,610	491	...	830	529	1,850
9	Narikelapally ...	2,113	160	...	620	166	846
10	Idiempalli ..	2,843	405	...	400	65	870
11	Kolavukyduru ..	4,447	1,031	...	675	197	1,903
		68,784	12,120	1,251	10,921	2,651	26,943
	<i>Nellore Talook.</i>						
	Kanapartipadu ...	3,840	254	...	658	284	1,196
	Kakapalli, Kolivelapalem, Madirazu Guduru.	4,497	1,746	...	1,450	293	3,494
		8,337	2,000	...	2,108	582	4,690
	Total ...	77,121	14,120	1,251	13,029	3,233	31,633

NELLORE,
15th April 1867.

Works Department, 20th June 1867.

Public Works under the Sarvapally Project.

REMAINDER AVAILABLE UNDER THE SARVAPALLY PROJECT							Remarks.
Ordinary rates.			Fovourable or Inam.		Total.		
Dry area.	Wet and garden area.	Probable assess-ment in average rates.	Dry area	Water rate at 4 Rs per acre.	Area.	Probable gross in-come of Revenue.	
Acres	Acres.	RS.	Acres .	RS.	Acres.	RS.	The Department Public Works will have to estimate the proba-ble irrigable area under the project, with reference to the level of the channel and the surrounding country. The Acting Collector has not suffi-cient details on the subject.
10,376	3,791	45,700	997	3,988	15,164	49,688	
1,336	444	11,662	4	16	1,784	11,678	
1,685	458	6,540	206	824	2,349	7,364	
7,641	615	24,768	484	1,936	8,740	26,704	
4,140	...	27,945	176	704	4,316	28,649	
1,399	542	12,880	...	...	1,941	12,880	
714	161	3,603	128	512	1,003	4,115	
220	164	868	376	1,504	760	2,372	
980	146	4,740	141	564	1,267	5,304	
1,371	585	6,539	17	68	1,973	6,607	
2,116	403	7,754	25	100	2,544	7,854	
31,978	7,309	1,52,999	2,554	10,216	41,841	1,63,215	
2,250	73	9,087	321	1,283	2,644	10,370	
537	322	10,322	144	574	1,003	10,896	
2,787	395	19,409	465	1,857	3,647	21,266	
34,765	7,704	1,72,408	3,019	12,073	45,488	1,84,481	

(Signed) J. A. C. BOSWELL,
Acting Collector.

(Signed) G. WINSOM, Lieut.-Colonel, R. E.,
Superintending Engineer, 2nd Division.

Proceedings of the Madras Government, Public Works Department.
20th June 1867.

No. 441.

ORDER THEREON, 20th June 1867, No. 1,844.

IRRIGATION, No. 21.

1. With the above letter the Superintending Engineer of the 2nd Division forwards plans and estimates, aggregating Rupees 4,12,100, connected with a project for further developing irrigation in the Nellore District under the Pennair anicut, by the enlargement, improvement, and extension of the main channel and some of its branches, and by adding to the capacity of the Sarvapully tank to enable it to contain water sufficient to supplement the supply of the channels during those periods of the cultivating season when, the river failing, the channels are low.

2. The Government observe that, by the proposed improved arrangements of the head works, a maximum supply will be secured in low freshes, or when the water in the river is below the crest of the anicut, and a perfect command be obtained over all the main irrigating ducts of the delta, and that the enlarged reservoir at Sarvapully will be made capable of holding upwards of 52 millions of cubic yards, which, with additions, from time to time when the river is high, will it is calculated, suffice to make good any deficiency of direct supply from the channels.

3. The project recommends itself as likely to be not only highly beneficial, but also most remunerative. The area stated to be commanded by the extension of the channels and under the influence of the tank is given in round numbers at 77,000 acres. Of this, after making what appears to the Government to be an extremely liberal deduction for land already under wet cultivation, and for waste and uncultivable tracts, about 25,500 acres will, it is confidently expected, be irrigated, yielding, at an assessment of Rupees 4 per acre as water-rate, a sum of Rupees 1,02,000 per annum. This is equivalent to a return of nearly 25 per cent.

4. Under these circumstances, the Superintending Engineer is authorized to proceed with the works from the allotment of Rupees 25,000 provided for the purpose in the Budget, and the Government will have much pleasure in recommending the project to the Government of India for sanction.

5. His Lordship in Council considers the manner in which the project has been prepared in a short time highly creditable to Mr. R. Smith.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the

- 1b. Cont. Superintending Engineer, of the 2nd Division.
- .. Accountroller of Public Works Accounts.
- .. Revenue Department.

Exd. S. T. Augustin.

PUBLIC WORKS DEPARTMENT,
FORT SAINT GEORGE,
20th June 1867.

No. 1,845.

No. 442.

To

THE SECRETARY TO THE GOVERNMENT OF INDIA,
PUBLIC WORKS DEPARTMENT.

SIR,

IRRIGATION, No. 22.

* Item No. 148.

1. I am directed to forward herewith plans and estimates, relating to the project for which a sum of Rupees 25,000* is provided in the current year's Budget, and having for its object a further development of irrigation in the Nellore District under the Pennair Anicut.

2. The estimates provide for the following works :—

Enlargement of head sluice near the anicut, construction of an auxiliary sluice, and deepening main feeder to the head of the Sarvapully channel	Rs. 15,300
Construction of regulating sluices at the heads of the Jaffer Saib and Kistnapatam channels	4,720
Deepening Sarvapully New Cut, and enlarging and improving the old Ramareddy channel and masonry works as far as the 6th mile from head sluice	90,300
Construction of a new channel from 6th mile to the reservoir at Sarvapully	1,26,500
Conversion of the present Sarvapully tank into a main reservoir	1,14,000
Construction of branch channel from Sarvapully channel to the Idagally tank	33,440
Construction of channel to Wolluru tank	27,840

3. It will be observed that, by the proposed improved arrangements of the head works, a maximum supply of water from the river will be secured in low freshes or when the water is below the crest of the anicut, and a perfect command be obtained over all the main irrigating ducts leading into the delta, and that the enlarged reservoir at Sarvapully, being made capable of holding upwards of 52 millions of cubic yards, will be useful to maintain the supply of the channels when, the river being low, they would be in want of water.

4. The project now submitted, being a continuation of one which has fully realized the great expectations which were formed of it, offers fair promise of being highly useful and reproductive. It is expected to bring under wet cultivation 25,500 acres of land, which, at an assessment of Rupees 4 per acre as water rate, will yield Rupees 1,02,000 per annum, or a return of nearly 25 per cent. The details of the project have been very carefully considered, and as it is most desirable that

the execution of the work should be proceeded with without delay, His Lordship in Council has authorized its commencement from the Budget grant of Rupees 25,000. In expressing a hope that this proceeding will meet with the approval of the Government of India, I am to request the early sanction of that Government to the estimates, amounting to Rupees 4,12,100, in the aggregate.

I have the honour to be,

Sir,

Your most obedient servant,

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

17.

Superintending Engineer
Masonapatam
3rd May 1867.

From Lieutenant Colonel G. V. Winscom R.E.
Superintending Engineer
To Colonel Charles A. Orr R.E.
Secretary to Government
D. P. W. R. O.
Madras.

Sir I have the honor to forward

plans and Estimates as per Margin, relative to a project for extending the irrigation from the Aricut across the Pennair at Nellore. Amounting to Rs. 4,12,100-

2 The Surveys and levels were commenced last year under my direction by Mr. Smith Esq^r Executive Engineer at Nellore, to whose able assistance I am indebted for much the greater portion of the labour involved in bringing forward the project. The arrangement of the details, the calculations of the dimensions and discharges of the channels, and the designs of the masonry works are his entirely. The Surveys and levels were made by Officer C. Appoosamy Raju

Enclosures
4 Surveys and Plans
as per list attached.
7 Details Estimates
0 Abstract do
5 Specifications
Reports
2 Abstract Estimates
Synopsis of the general
state of Pennair River
from 1861 to 1865.
1 Statement of Rise of Do
1 Revenue Return.

x by baughy.

who has proved himself a very efficient Surveyor.

3 As I considered that the Channels hitherto executed in the Bellare District had been designed too much on the supposition that the Pennair was a constant flowing river, instead of an uncertain stream, having the character of a mountain torrent rather than of an even flowing river, I requested Mr. Smith to make the Channels considerably in excess of what would have been necessary had it been otherwise. I enclose a synopsis and statement of the general state of the Pennair from 1861 to 1865 inclusive, from which it appears that on an average for only 61 days per annum the water was flush with, or above the Crown of the Stream. It is therefore evident that to fill the numerous tanks in the Delta so as to receive sufficient to supply 2 Crops per hour per acre, the Channels should be capable of conveying a very large quantity during the freshes, and those now projected accordingly have capacity sufficient to carry from 5 to 6 times the water which would be necessary if the lands were cultivated direct from the Channels.

4 The principal features in the present scheme are -

1st The enlargement of the Head sluice by lowering the existing sluice 2 ft. for 4 ft. of their breadth, and the construction of an auxiliary sluice of 6 Vents of $3\frac{1}{2}$ ft. each at the site of the old head, which was closed some years ago. This is desirable, as otherwise the loss of head during low freshes by contracted head gates would considerably affect the supply.

220 ft. per minute

2nd The deepening of the main feeder 2 ft. in preference to widening it. The velocity generated will entail the necessity of pitching the side slopes with stone for about 3600 yds. where sand is traversed, but on account of the close proximity of the heavy banks already formed by the excavation of the Channels and the desirability of obtaining a maximum supply in low freshes or when the water is below the Crest of the Stream, this has been considered the expedient course to adopt. The Estimate for these two improvements amount to Rs. 15300-0-0.

3rd The construction of Regulating sluices at the heads of the Saffersails and Kistnapatam Channels. By the aid of these structures and the regulating

who shire for the Sumapully and Wolur
off branches in the 6 mile perfect Command
3 our all the main irrigating ducts of the
his Delta will be obtained within a radius
had of 3 1/2 miles from Bellare.

4 The deepening of the Sumapully Reser-
voir, and the enlargement and improving
the Old Ramessay Channel, and the
the drainage works connected with it as far
the 6 mile from the 1st shire.

5 The construction of a new Channel
from the 6 mile, skirting the high ground by
Pulloomully, Bonnichetty & Gogumise
to supply the Sumapully Reservoir with
the necessary irrigation and drainage works.

6 The construction of a main Reservoir
at Sumapully, by the enlargement of the
present tank, which shall contain
52,580,000 Cys of water. Mr Smith
calculates that after supplying all
demands when the water is flush with

the Crown of the Aricut, the Channels will
be found sufficiently capacious to pro-
vide 1836400 Cys daily which would
enable the Reservoir to be filled in 28 1/2

days excluding loss by Evaporation
and remarks that as the direct daily
supply can only be depended on for 61 days
annually and as the Reservoir must
supply

Est. Rs 90,500

Est. Rs 126,700

" supply any deficiency that may arise
" during the other 89 days. the total quantity
" during the period would be 95639400 Cys of
" water or 9520600 Cys less than the
" Reservoir would contain on being filled
" a second time each season.

7 The abandonment of the Yeapier
Kamini Poddaparti and Tulli Tanks
which after the construction of the Sumapully
Reservoir and the Wolur Channel respectively
will no longer be needed. Their beds
can then be cultivated and the irrigated area
considerably increased.

Estimate Rs 33460

8 The construction of a Channel from
the Sumapully Channel to the Nagally
Tank so that when water is available
the opportunity may be taken to fill
it in a short time by allowing its Channel
to flow 7 ft deep. A sluice has been
provided for it to regulate the supply and
prevent the water returning into the Channel.

Estimate Rs 27,840.

9 The construction of an irrigation
Channel from the 6 mile to Wolur Tank
and in continuation to near Gudiving
the Ramolair's river, irrigating the lands
as far as the main drainage Channel.

10 The conversion of the present supply
Channel of the Sumapully Tank into a
main drainage, which on being extended

will effectually take off the water from
the irrigable fields under the Surasapully
tank and the Mollusee Channel and relieve
a considerable tract of land now swamped.

Para 5 It may eventually be found that
the supply is insufficient to justify any
extension of the Channel from the Kasagali
Tank in the direction of Trunk Road No 6.
At first it was intended to construct
a high level Channel from near the
present head of the Surasapully branch
which should have supplied all the
tanks in the neighbour hood of Puddur,
Puduhali, Kullivapullu &c but as those
tanks already generally receive a fair
supply from the Potbella and the expense
would have been very great, I decided
that the idea should not be further
entertained as regards the present project.

6 In explanation of the necessity
of the principal masonry works which
I have not yet noticed, I beg to add
that the new Bridge proposed at
Stanhope Pitt is rendered imperative
owing to the impossibility of lowering
the floors of the present structure. An
attempt was made some years ago to
do this and the result was that the Arch
became considerably raised.

7 The surplus water in the 6th mile
is designed to pass off into the main drains
(alluded as the 10th Chief feature of the scheme)
the local drainage of 18 square miles of
Country that falls into the Surasapully
Channel at its junction with the old Namerooy.

8 The falls adjacent to the Pudiarti
Yasura Kamini and Pulli Tanks are
designed to adjust the difference between
the slopes of the Channel and the Country
when the tanks are abandoned, otherwise
the banks would suffer severely from
Erosion.

9 The Rates tendered for the masonry works
have been carefully fixed by the Executive
Officer with reference to the distance the
materials have to be carried, and the style
of work proposed.

10 The irrigable area under the present
project, as shown by the Collector's statement
attached, is ^{Acres} 77121 of which, 31633 are either
watered already or are not fit for cultivation.
From the Remainder (45488 acres) however it is
difficult in the absence of specific
information to deduct a very large amount
on account of land that, from various
causes, may not be available and I
therefore propose estimating the receipts
on 25500 acres only. Allowing Rs. 100 per
acre for water cess and excluding

71
The very first which would be based on waste
to be brought under cultivation, the Expendi-
-ture now contemplated would secure a
Revenue of 102000 Rs. per Annum i.e. 2 1/2 %
per Cent on the outlay. Under these circum-
-stances, I therefore lay the project
before Government with great confidence.

11 Rs. 25,000 have been allotted in the
current year's Budget / Item 148 / and
pending the formal sanction of the Govt.
of India to the scheme. I request per-
-missions for the Executive Officer to
spend a portion of the money in collection
of materials ~~see so~~ that the present
working season may not be lost.

I have the honor to be
Sir
Your most Obedt. Servant

Geo. T. Milford V. A. R. E.
Superintendent Engineer

From
The Duke & Duchess
28 June

To Mr. Mackenzie
West 28th St
Madison

Recd 30 May/69

Recd

Post 10/10/69

Recd 10/10/69

Forwarded from
"The Duke & Duchess"
and to be included in
letter to Mr. Mackenzie.
- Lady's Progress for
the evening of 10/10/69
from Mr. Mackenzie
Cincinnati/Amsterdam
to West 28th St
Madison 10/10/69

271

49

(12)
 The following is taken
 from the 30th Nov 1867
 to the 1st Dec 1867
 from the 1st Dec 1867

San Francisco, Calif.

Estimated Average
 available as to
 marked down by
 Department of Public
 Works, under the
 San Francisco, Calif.

1867. The
 at a dock from
 the Dept. of Public
 Works, to the
 Executive Eng.
 Bureau, dated 15th
 April 1867. No. 89.
 1867 1905/6

Synopsis showing the General state of the Domain from 1861 to 1865 inclusive.

Year	Water 3 feet on Crest of Dam	Water 2 1/2 feet on Crest of Dam	Water 2 feet on Crest of Dam	Water 1 1/2 feet on Crest of Dam	Water 1 foot on Crest of Dam	Water 1/2 foot on Crest of Dam	Water with flood on Crest of Dam	Water 1/2 foot on Crest of Dam	Water 1 foot on Crest of Dam	Water 1 foot on Crest of Dam	Water 1 foot on Crest of Dam
1861	2	.	4	6	12	5	32	10	21	21	21
1862	10	2	11	5	12	2	40	7	11	11	11
1863	1	1	4	5	9	1	26	1	21	21	21
1864	11	1	4	4	5	5	25	21	22	22	22
1865	11	5	5	4	9	2	27	21	25	25	25
Total days average during the 5 years	35	9	28	24	47	15	150	60	100	100	100
	7	1 1/2	5 3/5	4 4/5	9 2/5	3	30	12	20	20	20

First taken
 at cut for
 12 days only

Ex Engineer's Office
 Camps, N. Y.
 30th April 1867

San Francisco, Calif.
 1867 1905/6

San Francisco, Calif.
 1867 1905/6

Enclosure in

Letter No 17 of 38

May 1865 to the

Secretary of

War.

Wm. H. Wood

Special Agent in Charge
of the Secret Service
of the Treasury
from 1861 to 1865
included

Enclosure in letter
 No 17 of 3rd May 1867
 to the Secy to Govt
 D. P. W.

27/1965/67
 20th June 1867

Statement showing
 the number of days in
 each year from 1861
 to 1865 inclusive
 in which the
 River rose to
 3 feet and upwards
 above the crest
 of the Amich &
 fell to 1 foot
 below it

List of surveys. Plans &c. of the Surapally Project.
 to accompany Superintending Engineer's letter No. 17 of 3rd May 1867
 to the Secretary to Govt D. P. W.

- | | |
|--|---|
| ✓ Survey of main feeder: Surapally Reservoir and | 1 |
| portion of the old Prameswar Channel | |
| ✓ Survey of the Surapally Reservoir and Channel | 1 |
| connected with it | |
| ✓ Survey of the Vallur Branch Channel | 1 |
| ✓ Sections of the present & proposed bed of the Surapally Tank | 1 |
| ✓ Sketch Map of the Delta | 1 |
| ✓ Plan of Auxiliary Head sluice | 1 |
| ✓ Plan of Regulating sluice at the head of | |
| Jaferwadi Channel | |
| ✓ Plan of Bridge across Surapally Channel | 1 |
| Near Stanhouse Pitt | |
| Plan of Iron Aqueducts | 1 |
| ✓ Plan of H. sluice for Vallur Branch | 1 |
| ✓ Plan of Fall No 1 | 1 |
| ✓ Plan of Reg. & Stand. H. Tank | 1 |
| ✓ Plan of H. sluice for Surapally Branch | 1 |
| ✓ Plan of Surplus sluice | 1 |
| ✓ Plan of Aqueduct for Surapally Branch Channel | 1 |
| ✓ General Plan of Bridges | 1 |
| ✓ Plan of Irrigation sluice No 1 | 1 |
| Do Do No 2 | 1 |
| ✓ Plan of H. sluice for Dozali Branch | 1 |
| ✓ Plan of Falls No 2 | 1 |
| ✓ Plan of Fall No 3 | 1 |
| ✓ Plan of Regulating sluice at the Dozali Tank | 1 |
| ✓ Plan of H. sluice for J. and P. Branches | 1 |
| ✓ Plan of Escape for Surapally Reservoir | 1 |

Superintendent
 M. A. P. C. M.
 3rd May 1867.

Accepted
 Superintending Engineer

83
 Quad Abstracts
 were taken by G. M. B.
 3rd July 73.
CPO

No 17 of 30 Aug 1873
 to the Secretary
 of the A. S. C.

18 19 20 21 22 23 24
 25 26 27 28 29 30 31
 1 2 3 4 5 6 7 8 9 10 11 12

List of Plans
 & drawings of
 the buildings
 provided

W. B. 11-20
June 17
1864

3
Specification to accompany the Plan and Estimate for Constructing the Auxiliary Head Sluice. 85

The Sluice will consist of 6 Vents $10 \times 3\frac{1}{2}$ feet. The front wings to be 26 in height for a length of 10 feet, and then decrease, by steps of a foot, for 16 feet measured horizontally which will reduce the height to 10. The face walls to be $13-7\frac{1}{2}$ in height, the breadth at bottom and top being 5 and 2 respectively. The space between the face walls to be filled in with concrete.

The latitude at the site to be cut down to the required depth 29.49 feet, above the mean tide and the superstructure built on it; no masonry is necessary in the foundation.

The wings in rear to be built on the surface of the latitude, the height being on the average 10 and the mean breadth $3\frac{1}{2}$.

The Vents to be provided with Leath Shuttles $1\frac{1}{2} \times 3 \times 11\frac{1}{2}$ these will have a margin of iron $3 \times \frac{1}{2}$ on the inner face to reduce friction; the working gear will consist of a screw $\frac{1}{8}$ inch pitch, a horizontal Leath Beam 1 foot square laid over the piers, through which the extremity of the screw will pass and project 6" under the nut for elevating or depressing the screw. An iron plate $9 \times 9 \times 1$ will be let into the beam to a depth of $\frac{1}{2}$ an inch. The nut to be worked by a moveable lever 24 inches in length. The Beam will be retained in its position by iron ties built into the masonry.

The masonry to be of dressed

Latviti in Phumam.

55

Camp. Hallou

3rd April 1867

Agmito

Engraving 1st or 2nd Hallou Camp

Comm. Hallou
Capt. Engineer 2nd Bn.

Dr. Hallou

Enclosure in letter
No 17 of 31 May 1871
to the Secretary
to Govt. D. J. W.

3.

19 May 1871

Constructing an
Auxiliary Head
Sluice & enlarging
Old Channel
& deepening the
Main feeder from
the existing 42 Sluice
to the head of the
Larapully Channel
Rs 15300

Specification to accompany the
Plan and Estimate for the Regulating
sluice at the head of the Jaffersaidi Channel.

The sluice to consist of 5 Vents
of 6' span. The front wings to be 13' 6" in
height, the breadth at bottom and top
to be 5' 4" and 1' 6" respectively. The
foundations of pier to be laid at a
depth of 4' the average breadth being
4' 3" and of abutments 6'. The rear
wings to be 13' in height at the abutments & 9'
at the Returns. The Average section at the
former point being $3\frac{1}{4}$ and $2\frac{1}{2}$ at the latter,
the foundation will have an uniform
depth of 6', but the section will vary from
an average thickness of 6' 2" at the abutments
to 5' at the Returns.

The flooring in the bays to be
inverts of 1' 2" in thickness resting on
Concrete 1' foot thick. The flooring
from the bays to the front and rear
retaining walls will be 1' 2" in depth
with a bed of Concrete 1' in thickness.
The piers on the up stream side will
project 3 ft. to admit of small arches
being turned to facilitate the working of the
Shutters; these will consist of teak
Planks.

planks $6\frac{1}{2} \times 3 \times 13\frac{1}{2}$. From iron bars
varying from $\frac{1}{2}$ " to $2\frac{1}{4}$ " in diameter to be
fixed in each vent to strengthen the shutters
and enable them to be worked easily.

The Rubble apron in rear to be $35 \times 20 \times 2\frac{1}{2}$
that in front $58 \times 12 \times 1\frac{1}{2}$. The side slopes
of the Channel, in rear of the sluice
to be protected for a length of 20 by Rubble
pitching. The whole of the masonry
to be built of dressed laterite in
Chenani. The floor of the sluice
to be 29.05 feet above mean tide; the level
of this has been fixed 2' below the
head of the Channel, to enable it to be
lowered 2' at any future time, should it
be desirable to increase the discharge
in the Jaffer sails branch.

Suppl. Engr. Office
Calcutta.
30 April 1867.

W. H. M. Cole Vis. Engr. &
Supt. Engineer 2d Div.

Enclosure in letter
No 17 of 3rd May 1867
to the Secretary
to Govt. P.W. D.
Madras -

2.

Constructing a
Regulating Wall
at the Heads of
Suffer Sali's &
Vidya-puram
Channels -
No 1720

17/1965/67

Specification to accompany the Plan and Estimate for
Constructing a Bridge, over the Sarrapah Channel,
near Stonehousepetta.

93

The Bridge to consist of 2 Arches of
30' span, the rise being 7½ feet; the flooring to be an
inverted with a vertical sine of 1½ feet; the masonry will rest
on a bed of concrete 6" in thickness, the pier to be 5'
in breadth at bottom with a batter of 6" on each side -
the abutment to be 6' in thickness and 12' in height - The
thickness of the Arch to be 2¼ at the springing line,
and 1½ at the crown - The wings to be 22' in height - The
breadth at bottom being 8', which will be reduced
by offsets, on the inside, to 2' 2" at the top - The foundations
of the wings to be 6' in depth the average breadth
10'. The foundations of the abutments and pier to be 6'
in depth also - the average breadth of the former will be
8½ and that of the latter 7½. The foundations throughout
to rest on a bed of good concrete 1' in thickness. The wings
to be set out with a radius of 66 feet. The whole of the
masonry to be of dressed laterite in Chumam.

Ex. Engrs Office
Camp Bellary
3rd April 1867

Agnew
Executive Engineer
1st of Bellary Range
W. H. M. S. S. S.
Superintendent

95
Specification to accompany the Plan and
Estimate for the surplus sluice proposed
for constructing across the old Ramersdy
Channel, adjacent to the Surra pulley
Branch Head sluice.

This sluice will consist of 5 Tents
of $2\frac{1}{2}$ span, the height of the piers being
7'. This work has been designed to dis-
charge the local drainage, brought in to the
Surra pulley Channel, by the old Ramersdy,
as this would be great in heavy rain, in the
event of the Bellare Tank being full,
provisions has been made for dealing
with a considerable surplus. The level
of the floor to be the same level as the bed
of the old Ramersdy at the site of the sluice,
which is about 19.32 feet above mean
tide, or 5' below the level of the bed of the
Main Channel, immediately in front of it.
The sluice when required to act will discharge
with a considerable velocity, as the head
will never be less than 6 or 7 feet. The
front wings to be $17\frac{1}{2}$ in height the average
breadth being $4\frac{1}{2}$, the foundations to be $5\frac{1}{2}$
deep, with an average breadth of $8\frac{1}{2}$. The
rear wings to be 10' in height the breadth
at bottom and top being $3\frac{1}{2}$ and $1\frac{1}{2}$ respec-
tively. The foundations to be 6' deep with
an average breadth of $5\frac{1}{4}$. The span rails

821 1966/19

to be filled in solid and a course of
masonry in thickness to be built over
these and the arches. The face of wall
to be 6' 3" in height. The breadth at bottom
and top being 3' and 1 1/2' respectively.
The space between the face walls to
be filled in with concrete. The retaining
walls will connect the wings front and
rear. The section between the former will
be as follows. depth 5 1/2' breadth at
bottom 6' and top 1 1/2'. The rear retaining
wall to be 6' ft. with an average breadth
of 3 1/4'. The front flooring between the
vents and retaining walls to be 1 1/2' in
thickness, resting on a bed of concrete
9" in thickness. The rear apron and
the flooring between the vents to be 2' in
thickness, the concrete under the former to
be 9" thick. The space under the flooring
of the vents to be filled in with concrete.
The shutters will be worked by a screw,
the general arrangement being the same
as the working gear for the shutter of the
auxiliary discharge. The whole of the masonry
to be built of pressed latite in Chumam.
The side slopes of the channel in rear
will be protected for a length of 20 yards
by rubble pitching. Beyond the rear retaining wall
there will be a rubble apron 16-6" x 20 x 3.

Suprs Office 2074
Maulabratam
30 April 1867
W. T. Mason
Supt. Engineer 2074

Enclosure in letter
No 17 dated 3 May 1867
to the Secretary to
Govt P. W. D.

8.

21 1905/1864

Deepening the
Sarnapilly new cut
and improving
Old Ramiredi
Channel & the
Masonry work
connected with it
PL 90300

Specification to accompany the
Plan and Estimate for the Repair
& Improvement of the Sarnapilly Branch Channel.

The sluice to consist of 8 Vents
6' span. The front wing is to be 15' in height
the breadth at bottom and top $6\frac{1}{2}'$ & $7\frac{1}{2}'$
respectively; the foundation is to be laid
at a depth of $5\frac{1}{2}'$ the average breadth the
being 7'. The rear wing is to be $14\frac{1}{2}'$ in height
at the abutments and 10' at the Return.
The average section at the former point
being $3\frac{3}{8}'$ and $2\frac{1}{2}'$ at the latter. The foundation
will have the depth of $5\frac{1}{2}'$ at abutments
and front wing & $4\frac{1}{2}'$ at pier & and 6 feet
at rear wing and return. but the section
will vary from an average thickness
of $6\frac{3}{4}'$ at the abutments to $6\frac{1}{2}'$ at the Return.
Piers $4\frac{1}{4}'$ at bottom $2\frac{1}{2}'$ at top on a bed
of Concrete $6\frac{1}{4}'$ in breadth and $\frac{3}{4}'$ in depth.
The flooring in the bays to be inverts
of $1\frac{1}{2}'$ in thickness resting on concrete 9" thick.
The flooring from the bays to the front
and rear retaining walls will be $1\frac{1}{2}'$
in depth with a bed of Concrete 9" in thick-
ness. The piers on the up stream side
will project $2\frac{1}{2}'$ to admit of small
arches being turned to facilitate the
working of the shutters, these will consist

Supp Dugis Oppre^d Du
Masulipatam
30 April 1864

Comm. Recd. 4/10/66
Supt Engineer 2d Div

Specification to accompany the
Plan and Estimate for the Aqueduct pro-
posed for Construction near Kannpartipadu.
This structure will carry the
Iravapally Branch Channel over the
drainage, from the land in the vicinity of
Kannpartipadu, and the surplus from
the Kannpartipadu Tank. It will
contain 4 Vents of 4' span, the piers
being 3' in height, and $2\frac{1}{2}$ in breadth.
The abutments to be 3' in height with an
average breadth of $3\frac{1}{2}$ '. The foundations
of the Piers and abutments to be 4' deep.
The breadth of the former at top and bottom
 $2\frac{1}{2}$ ' & $4\frac{1}{2}$ ' respectively the dimensions of the
latter at the same points being $3\frac{1}{2}$ ' & $5\frac{1}{2}$ '.
At the abutments the Wings will be 18' in
height the breadth at bottom being 9' and
at top 3'. This will be increased by a Carbel
of 1' on each side to form a roadway.
The Wings will be reduced in height by
steps of 1' up and 2' on to 11' 6" and be
carried at this height 11 feet making the
total length $23\frac{1}{2}$ feet. The outer faces
of the side walls to be plumb. The inner
to be described with a radius of $14\frac{1}{2}$ ft.
The floor of the Aqueduct to be 20 in breadth
at the level of the bed of the Channel and
28 at the maximum water mark. The floor

of the Aqueduct and the inner face
of the side wall for a height of 7' measured
on the curve will have a coat of asphalt
 $\frac{1}{2}$ " thick

The masonry to be of dressed latite
in Chunar.

Supr Engr Office at D. H.
Masulipatam. }
30th April 1867 } Geo. T. Miscoe Comm. of the C.
Supr Engineer at D. H.

7 28 19 65/67

Specification to accompany the Estimate for con-
verting the Sarvapalli Tank into the main Reservoir,
for the Southern portion of the Pennar Delta.

The Embankment to be raised to 6' above
future Tank level; the breadth at top being 6' with
side slopes of 2 to 1; the interior to be protected,
for a length of 5270 yards, by a Revetment of
roughly dressed latite, carefully packed at right
angles to the slope; the thickness of the revetment
at bottom to be 2', and at top (i.e. two feet above proposed
full Tank level) 1' foot; in rear of the revetment there will
be a gravel backing 6" in thickness.

The exterior slope of the work, and the portion
of the interior, above the revetment to be well turfed.

The present Salingula to be closed and a
new one constructed, adjacent to the village of Ani-
Kappalli; the Crest being 2' below Tank High water mark.

The four existing sluices to be lengthened and
improved. On the completion of the proposed new
supply channel the old one will be closed by
continuing the Tank bund to the high land at
AniKappalli. In the event of the revetment, as
planned, being considered too expensive a reduction
of Rs 27,248 might be made by altering the interior
slope of the bank from 2 to 1 to 1 to 1.

Executive Engineer
Campellore
3rd April 1867

A. Smith

Executive Engineer
1st or 2nd Vellore Range

Geo. T. Miscoe Comm. of the C.
Supr Engineer at D. H.

Specification to accompany the Estimate
and Plan for the Escape proposed for the Panapallo
Reservoir.

The length of the body to be 170' and
flush with the Apron, the surface being 2' below
the future Santa high water mark, to retain
the water to this level, the body will be finish-
ed with 33 Cast Iron Posts 2' in height, and
68 Leaf Shutters (i.e. two for each vent) The
front wings and Returns to be 6 1/2' in height,
the breadth at floor level being 2 1/6, and at
top 1 1/2; the batter being on the outer faces.
The Rear Returns to be 3' in height with
a breadth of 1 1/2 at floor level, and 1 1/4 at top,
the batter being also on the outer faces. The
Rear Returns to be connected by a retaining
wall, 4' in depth, the breadth at bottom being
2'-3" and ^{The apron} at top to be 12'-0 in breadth and to
consist of Slatings on edge 1 in thickness,
resting on a bed of concrete 6" thick, it will
cover the entire space between the Body, Rear
Wings, and Retaining wall.
In Rear of the Slatings apron there will
be one of Rubble 19 1/2 feet in length, 10 in
breadth, and 1 1/2 in thickness.
The foundations of the whole structure to
be

7-21 1905/6

be 2' in depth, with the exception of those
of the Retaining wall and Rear returns;
these will be laid at 4' below floor level.
The masonry to be of dressed Lathis
in Chumam -

Smith

Esq. Engineer 10th St. Tellore
Puz

Common. V. 10th St. Tellore
Supr. Engineer 2d St.

Esq. Engineer
Chief Engineer
24th September 1866
Despatches
3rd April 1867

59. 101
Specification to accompany the Plan and
Estimate for the Coagaling Branch Channel near
Shree

This work to be constructed
at the southern extremity of the Surapalli
Reservoir, adjacent to the site of the
present Lingula, it will consist
of 8 Vents of 3' span, the height of the
piers to be 4' and the breadth $2\frac{1}{2}$ -
The front Wings to be $1\frac{1}{4}$ in height; the
breadth at bottom and top being
 $5\frac{1}{2}$ and 2' respectively. The rear Wings
to be 8 ft in height with an average
breadth of $2\frac{2}{3}$. The Wings in rear
and in front to be connected by a
retaining wall; the rear one to be 5'
in depth with an average breadth
of $2\frac{1}{2}$. The front retaining wall to be
the same breadth but only $\frac{3}{4}$ in
depth. The flooring throughout
to be $1\frac{1}{2}$ in thickness with a bed of
Concrete 1' thick. The face walls
to be $7\frac{1}{2}$ in height. The bottom breadth
being $3\frac{1}{2}$ and the top $1\frac{1}{2}$. The space
between the face walls to be filled
in with gravel. The floor of the sluice

to be 11.59 ft. above mean tide. This
sluice is designed to be capable
of discharging the required quantity
of water when there is but comparatively
a small supply in the Reservoir.

The shutters to be worked
by screws. The general arrangement
being the same as detailed for the
Auxiliary Sluice.

The masonry to be of dressed
laterite in Chungan and pointed
with Chungan.

Asst. Commr. C. S. D. C.
Supr. Engr. D. D. C.

Supr. Engr. Office D. D. C.
Maulipatam
30th April 1867

27/19/67

Specification to accompany the General
Plan for Bridges proposed for
Construction across the Surasully Branch
Channel.

The Bridge to consist of 2
Arches of 15' span, the rise being 4'. The
height of the pier and abutments to be 10', the
former being 3' and the latter 5' in breadth.
The Arches to be 2' in thickness at the
springing line, and 1 1/4' at the Crown. The
floor to be an invert 1' in thickness with
a raised sine of 1/4", the invert will rest on
a layer of concrete 9" thick. The Wings
to be 16' in height at the abutments and 6'
at the extremities. The depth of the founda-
tion to be reduced by steps of 1' up and
2' or for a length of 16' and carried on this
level 7 1/2' making the total length 23 1/2'.

The road way to be 12' in breadth
with Parapets of 3' in height.

The masonry to be of dressed laterite
in Chungan and pointed with Chungan.

Supr. Engineer's Office D. D. C.
Maulipatam.
30th April 1867

Asst. Commr. C. S. D. C.
Supr. Engineer D. D. C.

Specification to accompany Plan
No 2 / General / for Migration sluice-

The Wings to be 7' in height,
the breadth at bottom and top being
 $2\frac{1}{2}$ and $1\frac{1}{2}$ respectively. The barrel
to be 6' in length, and $1\frac{1}{4}$ in thickness,
the inside diameter being $2' - 6\frac{1}{2}"$ it
will rest on a bed of Concrete 9" in
thickness. The barrel will be
backed with masonry on each side
to a height of $2' - 6"$ above concrete level.
The front Wings to be 8 in length, measured
at right angles to the face of the arch,
and set out with a splay of $2\frac{1}{2}$ at the
extremities. The rear Wings to be also
 $7\frac{1}{2}$ in length, described with a radius of
 $4\frac{1}{4}$. There will be three retaining walls
one under the shutter, the second at the
opposite end of the barrel, and the
third at the extremities of the rear Wings
the space between the second and third
to be filled in with 2' of Rubble stone
carefully packed immediately in front
of the first retaining wall there
will be a rubble Apron 5 in length and
 $1\frac{1}{2}$ in depth. The shutter to be

worked by a screw. The masonry to
be of dressed granite in Chunan

Chief Engineer's Office

Harshpatau

30th April 1867

Commissioner General
Superintendent

21/19/67

66

Specification to accompany the
Plan and Estimate for the 2nd pier
and Redipate Branch Head & sluice.

The barrel to be oval, and $1\frac{1}{4}$ '
in thickness, the upper diameter being
 $4\frac{1}{2}$ ' and the lower $3\frac{1}{4}$ '; the sides to
be described with a radius of 9';
the length of the barrel to be 9';
it will rest on a bed of concrete 1'
thick, and be backed up by masonry
on each side, for a height of $7\frac{1}{4}$ feet
above concrete level - The front
wings at the abutments will be 9'
in height and at the extremities 4';
the rear wings will be the same height
at the abutments but 3' at the
extremities. The front wings to be
 $13\frac{1}{2}$ ' length measured at right

angles to the face of the work, and
to be set out with a ~~radius~~ of
10' at the extremities, which will
be connected by a retaining wall.
The rear wings to be described
with a radius of 11' and to be
18' in length measured perpendicularly
from the face; the extremities to be
connected by a retaining wall 3'
in depth, with an average breadth
of $2\frac{1}{4}$ feet. The flooring between
the retaining walls and vent to be
of laterite $1\frac{1}{4}$ ' in thickness, resting
on a bed of concrete 1' thick.
The shutters will consist of planks
 $5' \times 3" \times 10'$; to facilitate the working
of these and retain them in position
2 iron bars will be fixed across
the vent - The masonry to be

of dressed laterite in ⁶⁷chemam -
115

Camp Hallor
2nd April 1867

Smith
Co Engineer Hallor River

~~Commissioner~~ ^{Wm H. H. H.}
Super Engineer D. D.

79 117

Specification to accompany the Plan and
Estimate for the Fall proposed for
Construction near the Dramadurum Intake Tanks

The body wall to be 8' in height,
the breadth at bottom and crest being
 $4\frac{3}{4}$ and 3' respectively. The length of the
body wall to be $4\frac{3}{4}$ in rear of the body
wall a Cistern with curved plan N V 15'
in length and $16\frac{1}{2}$ in greatest breadth to be
constructed to retain a depth of 4' of water,
the flooring of the Cistern to consist of $1\frac{1}{4}$ '
of Laterite and 9" of Concrete. The rear
Wings to be connected by a retaining wall
5' in depth, the breadth at bottom being
 $4\frac{1}{2}$ ', and 2' at the level of the flooring. The
rear Wings to be $16\frac{1}{2}$ in height and the front
12' the average breadth of the former being
 $4-1\frac{1}{2}$ ', and that of the latter 3'. A foot-
bridge to be thrown over the Crest of the
weir with a groove of 6" in it to admit
of the shutters being worked, and to
prevent these getting jammed, during
the working. 3 Iron bars will be
built in, above the Crest of the Weir,
at 1-10' apart.

The masonry to be of dressed

22/19/85/84

laterite in Chemam

Supr Engineer's Office
Maulapatam
30th April 1867.

Geo. M. M. M. M.
Supr Engineer's Office

2nd 28 1965/67

Specification to accompany the Plan and Estimate
for the Regulator proposed for construction near
the Vallur Tanks.

The Regulator to consist of 2 Vents
one 4' span, the other 11 1/2' - The front wings
to be 6'-0" in height and 2' in breadth on
the average; and returns to be 6' in height
and 2 1/4' in breadth on the average. There will
be two retaining walls, on each Vent. The
two vents to be connected by a curved wall
as shown in plan. Each shore will be
adapted to carry a stone bridge for
foot passengers. The plan for
regulating the supply of water
will be fixed immediately in front of
the bridges; and two iron bars will
be built in, across each Vent. to guide
the planks, and retain them in position.
The masonry to be of pressed laterite
in Chemam. The front and rear aprons
to be of packed rubble 1 1/2' & 2' thick,
respectively with the proper slopes.

Supr Engineer's Office
Maulapatam
30th April 1867

Geo. M. M. M. M.
Supr Engineer's Office

Specification to accompany the Plan and Estimate
for the Vallur Branch Head Sluice 191

The front wings to be $14-3'$ at the abutments and $4\frac{1}{4}'$ at the extremities, the average breadth of the former being $3\frac{1}{2}'$ and that of the latter $1\frac{1}{2}'$. The front wings to be connected by a retaining wall $5'$ in depth, the breadth at bottom being $4'$ and at floor level $1\frac{1}{2}'$; between this retaining wall and the vents there will be a floor of laterite $1\frac{3}{4}'$ in thickness, and a bed of concrete $9"$ thick. The flooring in the bays to consist of $2'$ of laterite and $9"$ of concrete; the flooring between the bays and the rear retaining wall to be of like section. The sluice will have 3 vents of $2\frac{1}{2}'$ span; the height of the piers being $5\frac{1}{2}'$. The face walls to be $6\frac{1}{6}'$ feet in height with an average breadth of $2\frac{1}{4}'$; the space between the piers to be filled in with concrete. The rear wings to be $14'$ in height at the abutments, and $9'$ at the extremities, these will be connected by a retaining

1905/04

wall 6' in depth with an average breadth of $2\frac{3}{4}$. The side slopes of the channel in rear will be pitched for a length of 20 feet. Beyond the rear retaining wall there will be a rubble apron $20 \times 8 \times 2\frac{1}{2}$. The length of the floor to be 24.32 feet above mean tide -

The shutters to be worked by screws.

The masonry to be of dressed laterite in chancem.

Camp Nellore
22 April 1867

Agatha
Engineer Nellore
Commence
Sup Engineer

22/1906/64
20th June/67 No. 1844 & 1845

1st or Nellore Range.

District Nellore - Taluk

Work Constructing an Auxiliary Road by enlarging & changing and deepening the main river from the existing old channel to the head of the navigable channel

PARTICULARS OF WORK.	Measurement.				Cubical Contents	Value per cu ft.
	Length.	Breadth.	Height or Depth.	Number		
Earthwork	Feet	Feet	Feet		Feet	
Enlarging old channel						
Latent cutting	30	42	2	1	2520	1-8
Clearing silt	30	31	$2\frac{3}{4}$	1	3410	1-6
Latent cutting	26	42	2	1	2184	1-8
do do	27	23	2	1	1242	1-8
do do	26	11	$1\frac{3}{4}$	1	5070	1-8
Earthwork	26	11	8	1	2288	1-1
Clearing silt	53	23	$3\frac{3}{4}$	1	4467	1-1-6
Removing & depositing latent cuttings	27	$1\frac{1}{2}$	8	1	324	1-8
Latent cutting	45	$24\frac{1}{4}$	2	1	2182	1-8
do do	45	$1\frac{3}{4}$	$4\frac{1}{2}$	1	1220	1-8
Earthwork	45	$1\frac{3}{4}$	$10\frac{1}{4}$	1	807	1-1
Clearing silt	45	$24\frac{1}{4}$	3	1	3273	1-1-6
Removing & depositing latent cuttings	45	$1\frac{1}{2}$	$10\frac{1}{4}$	1	691	1-8
Latent cutting	45	26	2	1	2340	1-8
do do	22	$17\frac{1}{2}$	$\frac{1}{2}$	1	192	1-8
Clearing silt	45	26	$3\frac{3}{4}$	1	4587	1-1-6
Latent cutting	90	26	2	1	4680	1-8
Clearing silt	90	27	$3\frac{3}{4}$	1	8910	1-1-6
Latent cutting	145	26	2	1	7540	1-8
Clearing silt	145	27	$3\frac{3}{4}$	1	14385	1-1-6
Removing & depositing	27	9	$13\frac{3}{4}$	1	34362	1-1-6

Demolishing Bridge over old Supplying Channel and
 clearing the latter out more nearly to
 Connecting existing and proposed Head sluices
 by a Parapet wall

Foundation	276	2 1/2	3	2070
Wall above	276	1 1/2	3	1242

Total Cubic feet of Patents in Channel 33 1/2

Lowering floor of Head sluice

Patents Cutting 83 1/4

Altering shutters

Deepening main feeder

Patents Cutting

Earthwork 1000 52 2 102000 1.81

do 1000 20 1 1/2 20000 1.16

do 1000 34 1 34000 1.16

do 1000 40 1 40000 1.16

do 900 70 3 22500 1.16

do 900 30 1 1/2 40500 1.16

do 900 20 1 1/2 62100 1.16

do 900 20 1 2 44000 1.81

Gravel pitching

Gravel backing

Compensation for land

28/1965/1/1

Detailed Estimate No. 4. - of 186 -6-

1st or Nellore Range.

District Nellore—Taluk

Work *Constructing an Auxiliary Head Sluice adjacent to the Arikat.*

PARTICULARS OF WORK.	Measurement.				Cubical Contents
	Length.	Breadth.	Height or Depth.	Number.	
Concrete to	35 1/2	14	12 3/8	1	6215 1/24
					Total 6215 1/24
Abutments	23 1/2	4	10	2	1840
Piers	27 1/3	2 1/2	10	5	3416 1/3
Caps	2 1/2	2 1/2	2 1/2	5	67 1/24
Shew-backs	23	2 1/2	1/2	5	143 3/4
— 1/2 —	23	1	1/2	2	92
Spanndril	41 1/2	23	3/4	1	710 7/8
Face walls	41 1/2	3 1/2	13 5/8	2	3958 1/2
— 1/2 —	41 1/2	2	13 5/8	1	1130 7/8
Side Walls	23 1/2	3 1/2	12 5/8	2	1879 1/2
Portions of full water	26	26	16	5	375 7/8
Front Wings	10	6 1/2	26	2	3380
— 1/2 —	15	5	18	2	2700
— 1/2 —	10	3 1/2	10	2	700
Rear Wings	26	3 1/2	10	2	1820
Sliding Course	124	1/4	3/4	1	23 1/4
Parapet	200	1 1/2	3	1	900
Arch Wall	23	5 3/4	1 1/2	6	1190 1/4
					Total 24373 1/2

Painting	87
Earth Work	1248
Metalling	66 2/3

Seal Wood Beam Cft. 35 1/2
 Seal Wood Shutter with working gear - 1
 Centering _____
 Sundries _____

127

2 27 1965-66

Particulars of Work

Particulars of Work
for the purpose of the work and improving the old dam and
for the purpose of the work and improving the old dam and

Particulars of Work	Measurements				Work to be executed				Total
	Length	Breadth	Height	Volume	Cutting	Throwing	Gravel	Gravel	
Cutting	600	68	10	448,800					
Deduct present work	600	73	5	240,900	207,900				
Cutting	600	25	1		16,500				
do	600	14	2		18,480				
Cutting	600	25							
do	600	14							
Gravel pitching	600	23	1 1/2						
Gravel backing	600	23	1						
Cutting	1020	68	10	897,600					
Deduct present work	1020	77	5	508,200	389,400				
Cutting	1020	13	3		51,480				
Cutting	1020	13							
Gravel pitching	1020	23	1 1/2						
Gravel backing	1020	23	1						
Cutting	1020	68	10	897,600					
Deduct present work	1020	57	4	511,520	386,080				
Gravel pitching	1020	23	1 1/2						
Gravel backing	1020	23	1						
Cutting	165	68	10	112,200					

Cutting	1105	68	10	785,400						
Deduct present work	1020	77	4 1/2	457,280	410,220					
Gravel pitching	1290	23	1 1/2							
Gravel backing	1290	23	1							
Cutting	462	68	10	314,160						
Gravel pitching	858	68	10	583,440						
Cutting	1020	74	4 1/2	897,600	403,620					
Deduct present work	1020	15	2		39,600					
Cutting	1020	13	1 1/2		25,740					
Cutting	1020	15								
Gravel pitching	1020	13	1 1/2							
Gravel backing	1020	23	1							
Cutting	814	63	10	512,820						
Gravel pitching	506	63	10	318,780						
Cutting	1020	70	3 1/4	831,600	485,800					
Deduct present work	1020									

14,29

1st or Nellore Range.

District Nellore—Taluk

Work *Constructing a Bridge of 2 arches across the Curumpalli Channel near Stonehousepet—*

PARTICULARS OF WORK.	Measurement.				Cubical Contents
	Length.	Breadth.	Height or Depth.	Number.	
<i>Concrete to Abutments—</i>	35 $\frac{1}{2}$	11 $\frac{1}{2}$	1	2	808 $\frac{5}{8}$
<i>Piers—</i>	35 $\frac{1}{2}$	10 $\frac{1}{2}$	1	1	369 $\frac{1}{4}$
<i>Wings—</i>	31	13	1	4	1612
<i>Retaining wall—</i>	26	6	1	4	624
<i>Inverts—</i>	28 $\frac{1}{2}$	28	$\frac{1}{2}$	2	798
<i>Spandril—</i>	16 $\frac{2}{3}$	18	2	1	600
				<i>Total</i>	<i>4812 $\frac{1}{2}$</i>
<i>Foundations— Abutments—</i>	32 $\frac{1}{2}$	8 $\frac{1}{2}$	6	2	3281
<i>Piers—</i>	32 $\frac{1}{2}$	7 $\frac{1}{2}$	6	1	144 $\frac{1}{2}$
<i>Wings—</i>	31	10	6	4	7440
<i>Retaining wall—</i>	28	3 $\frac{1}{2}$	5 $\frac{1}{2}$	4	2156
<i>Superstructure— Abutments—</i>	29 $\frac{3}{4}$	6	12	3	4272
<i>Piers—</i>	29 $\frac{1}{2}$	4 $\frac{1}{2}$	12	1	1515
<i>String Courses—</i>	124	$\frac{1}{4}$	$\frac{1}{2}$	"	15 $\frac{1}{2}$
<i>Capls—</i>	3 $\frac{5}{6}$	4	3 $\frac{5}{6}$	2	117 $\frac{5}{6}$
<i>Do—</i>	4 $\frac{1}{3}$	5	4 $\frac{1}{3}$	2	187 $\frac{1}{3}$
<i>Skew backs—</i>	21	4	1	1	84
<i>Do—</i>	21	5	1 $\frac{5}{6}$	2	385
<i>Backing to arches—</i>	21	10	1 $\frac{1}{2}$	2	630
<i>Wings—</i>	31	5 $\frac{1}{12}$	22	4	1086 $\frac{1}{3}$
<i>Spandril—</i>	21	6	2 $\frac{1}{2}$	1	315
	30	2 $\frac{1}{6}$	2 $\frac{1}{2}$	"	162 $\frac{1}{2}$
<i>Face Wall—</i>	14	3 $\frac{1}{3}$	4 $\frac{1}{2}$	"	210
	66	3 $\frac{1}{3}$	4 $\frac{1}{2}$	"	990
	144 $\frac{2}{3}$	1 $\frac{1}{2}$	1 $\frac{3}{4}$	2	759 $\frac{1}{2}$
<i>Parapets—</i>	144 $\frac{2}{3}$	1	1 $\frac{3}{4}$	2	506 $\frac{1}{3}$
	2	2	3 $\frac{1}{2}$	4	56
				<i>Total</i>	<i>38454</i>
<i>ornice Work—Running feet—</i>					300

R. W. 1965/14

Arch Work

39	21	17	2	307 1/2
31	27	1	2	167 1/4
				Total 474 5/8

Pointing	Sq. ft.	102.2
Excavation	Cy.	1540
Metalling	Cy.	15
Guard Stones		4
Carting		
Walling		
Shoring		

22/1965/64

Detailed Estimate No. 43 of 186-5

1st or Nellore Range.

District Nellore—Taluk

Work I propose to do for the purpose of building New Cut and improving the old Ramreddy Channel —
Masonry Works —

PARTICULARS OF WORK.	Measurement.				Cubical Contents
	Length.	Breadth.	Height or Depth.	Number.	
Demolishing and Rebuilding Iron Aqueduct Piers					
Foundations to Piers	17	5	5	4	1700
Piers above	16	3	11	4	2112
Total Cubic feet of masonry work					3812
Demolishing existing Piers					
Reaffording, shoring & bracing					
Walling water					
Substituting Iron Aqueduct for Pipe-line No. 1					
Foundations to Abutments	7	4	3	2	168
Do to Wings	17 1/2	4	3	4	840
Do to Piers	9 1/4	4	3	4	444
Abutments above	7	2 1/2	11	2	140
Wings do	17 1/2	2 1/2	6	4	1050
Piers do	8 1/4	3	11 5/8	4	1171 1/2
String Course	3 1/2	3 1/2	2 3/4	8	655
Between beams	1 1/3	3	2 3/4	4	10 2/3
Joists	3	2 5/8	2	8	126
Shoe blocks	7 1/2	2	1/4	4	30
Bracing to arches	2	1/2	1/4	4	1
Face walls	7	1	1/2	4	14
Parapets	7	3/4	3/4	4	15 3/4
Arches	7 1/2	4	3/4	2	45
Total Cft. of masonry work in channel					4121 1/4
Running feet of sheet iron trough complete					80
Pointing	15 1/3	4	8 1/2	6	12 1/2
Leath. Girders	15 1/3	4	8 1/2	4	21 3/8
do do					14 1/2
Total Cft. of Leath. Wood					36

Total Cft. of Leath. Wood

Detailed Estimate No. 4 of 186 -6 -

1st or Nellore Range.

District Nellore—Taluk

Work *Permanent Delta*
Constructing an Irrigation. Duices Vies
Plan No. 1

PARTICULARS OF WORK.	Measurement.				Cubical Contents
	Length.	Breadth.	Height or Depth.	Number	
Concrete—	$6\frac{17}{24}$	$8\frac{1}{2}$	$\frac{3}{8}$	1	$43\frac{57}{192}$
	$1\frac{1}{2}$	$1\frac{1}{2}$	1	1	$6\frac{3}{4}$
	15	$4\frac{3}{4}$	1	2	$142\frac{1}{2}$
	$12\frac{1}{2}$	$4\frac{1}{2}$	1	2	$112\frac{1}{2}$
			Total		305
Marble—	10	8	$1\frac{1}{4}$	1	100
Retaining Wall	2	$2\frac{1}{4}$	$4\frac{1}{2}$	1	$20\frac{1}{4}$
Front—100—	1	$2\frac{1}{4}$	$4\frac{1}{2}$	1	$10\frac{1}{8}$
Foundations—Front Wings—	13	$2\frac{3}{4}$	$4\frac{1}{2}$	2	$321\frac{3}{4}$
"—Rear—100—	$10\frac{1}{2}$	$2\frac{1}{2}$	$4\frac{1}{2}$	2	$236\frac{1}{4}$
Chase—Front—100—	12	$1\frac{5}{8}$	$3\frac{1}{2}$	2	$120\frac{3}{4}$
"—Rear—100—	$9\frac{1}{2}$	$1\frac{1}{2}$	4	2	114
Front Face wall	$3\text{--}9\frac{1}{2}$	$1\frac{1}{4}$	$3\frac{3}{4}$	1	$17\frac{3}{4}$
"—Rear—100—	$3\text{--}9\frac{1}{2}$	$1\frac{1}{4}$	$1\frac{3}{4}$	1	$3\frac{1}{4}$
Parapets—	$3\text{--}9\frac{1}{2}$	$\frac{3}{4}$	$\frac{3}{4}$	1	$2\frac{1}{8}$
			Total		951
Venable stones—(Antients)—	10	7	$1\frac{1}{2}$	1	105
	7	$3\frac{1}{4}$	2	1	$45\frac{1}{2}$
					$150\frac{1}{2}$
			Cyph.		$5\frac{1}{2}$
Painting—Lyd.					3
Excavation—Cyph.					129
Leat & Beam—Cyph.					16
Shutter with working gear—					
Dialing—					
Landris—					

Detailed Estimate No 4

1st or Yellow Pages

District Yellow Pages

Pennair Datta

Work Constructing a Surplus sluice adjacent to the Surapullei
much Head sluice, across the old Frameddy Channel.

Particulars of Work	Measurement					Cubical Contents
	Length	Breadth	Height or Depth	Thickness		
Concrete						
Abutments	10 $\frac{3}{4}$	7	$\frac{3}{4}$	2		112 $\frac{7}{8}$
Piers	24 $\frac{1}{2}$	20	$\frac{3}{4}$	1		367 $\frac{1}{2}$
Front Wings	41	10 $\frac{3}{4}$	$\frac{3}{4}$	2		361 $\frac{1}{8}$
Rear Do	21	9	$\frac{3}{4}$	2		283 $\frac{1}{2}$
Returns	19	7 $\frac{1}{2}$	$\frac{3}{4}$	2		213 $\frac{3}{4}$
Rear Retaining wall	12 $\frac{1}{2}$	6	$\frac{3}{4}$			56 $\frac{1}{4}$
Front Do	36 $\frac{1}{2}$	5	$\frac{3}{4}$			136 $\frac{7}{8}$
Front Flooring	26 $\frac{1}{4}$	7 $\frac{1}{4}$	$\frac{3}{4}$			142 $\frac{47}{64}$
Rear Do	20 $\frac{3}{4}$	17	$\frac{3}{4}$			264 $\frac{9}{16}$
Below floor between piers	16	$\frac{3}{4}$	3	5		180
Spanvil	29 $\frac{1}{2}$	$\frac{6}{8}$	5 $\frac{2}{3}$			1023 $\frac{43}{48}$
Total						3143 $\frac{13}{192}$
Foundation						
Abutments	10 $\frac{3}{4}$	5 $\frac{3}{4}$	6	2		741 $\frac{3}{4}$
Piers	24 $\frac{1}{2}$	17 $\frac{3}{4}$	6			2609 $\frac{1}{4}$
Front Wings	39 $\frac{7}{8}$	8 $\frac{1}{2}$	5 $\frac{1}{2}$	2		3728 $\frac{5}{16}$
Rear Do	22 $\frac{1}{8}$	6 $\frac{3}{4}$	6	2		1792 $\frac{1}{8}$
Returns	16 $\frac{3}{4}$	5 $\frac{1}{4}$	6	2		1055 $\frac{1}{4}$
Rear Retaining wall	14 $\frac{3}{4}$	3 $\frac{1}{4}$	6			287 $\frac{5}{8}$
Front Do	38 $\frac{3}{4}$	2 $\frac{3}{4}$	5 $\frac{1}{2}$			586 $\frac{3}{32}$
Superstructure						
Abutments	10 $\frac{3}{4}$	4 $\frac{1}{2}$	7	2		677 $\frac{1}{4}$
Piers	14 $\frac{1}{4}$	3	7	4		1197
Caps	1 $\frac{3}{4}$	3	1 $\frac{3}{4}$	4		36 $\frac{3}{4}$
Skew backs	10 $\frac{3}{4}$	3	$\frac{1}{4}$	4		32 $\frac{1}{4}$
Front Wings	39	4 $\frac{1}{8}$	17 $\frac{1}{2}$	2		5630 $\frac{5}{8}$
Coping	39 $\frac{1}{4}$	2	1	2		157

22/19/05/67

1st or Nellore Range.

District Nellore—Taluk

Work Executing the Narraipally Channel and Constructing the necessary irrigation and drainage works connected with it.

Pear Wings	25	3 1/2	13 3/4	2	2234 3/8
Coping	25	2	1	2	100
Return	15	2 1/2	10	2	750
Coping	15 1/2	2	1	2	62
Backings to Arches	10 3/4	3 3/4	2 1/2	2	201 7/8
Spanvil	10 3/4	3	1 3/4	4	225 1/4
Flooring over Arches	32 1/2	10 3/4	5 1/2	"	349 3/8
Cise walls	32 1/2	2 1/4	8 3/5	2	975
do	16 1/2	1 1/2	5 1/5	2	124 5/8
Front flooring	33 1/2	13 1/2	1 1/2	"	678 3/4
Pear do	24 3/4	20	2	"	1138 1/2
Flooring between Piers	10 3/4	2 1/2	2	5	268 3/4
Parapets	28	1	1	2	56
					25675 3/8
Demol. for Vents	16	3/4	3	5	180
					25495
Arch work	10 3/4	5 1/2	1 1/2	5	443 7/8
Pointing Squares					56
Double stone / Latentite /	16 1/2	20	3	4	990
	20	17	2	2	1360
					2350
					87 1/2
Carvations					959
Installing					8
Teak wood Beams	28	1	1	"	28
Buttons	3	3	9	5	
Waling					
Centering					
Summers					

p 28 1965/64

PARTICULARS OF WORK.	Measurement.				Cubical Contents	Rate.	per cu. yd.
	Length.	Breadth.	Height or Depth.	Number.			
	Feet	Feet	Feet		Feet		
Abut. of Nellore							
Cutting	1320	56 1/2	8 1/4	1	242885	"-1-	
Backings	1320	115 1/2	2	2	609800	"-1-3	
Surfing	1320	56	"	2	147840	"-1-4	
Backings	264	64	1	2	33792	"-1-	
Cutting	264	32 3/4	5-8	1	49793	"-1-	
Aqueduct							
Cutting (partly gravel)	3696	34 1/2	7 1/2	1	981057	"-2-	
2nd mile Cutting Gravel & Loam	683	34 1/2	8	1	188508	"-3-	
Cutting do do	1297	42 1/2	7 1/2	1	386623	"-3-	
Bridge of 2 arches							
Cutting Latentite, Gravel & Loam	2310	56 1/2	9 1/2	1	825311 1/2	"-3-	
Cutting do do do	990	36 1/2	9 1/2	1	363705	"-3-	
3rd mile Cutting do do do	5280	40	8	1	1816320	"-3-	
4th mile Cutting	1620	43 3/4	8 1/2	1	613080	"-2-	
Bridge of 2 arches							
Cutting	3660	43 3/4	8 1/2	1	1335106 1/2	"-1-6	
5th mile Cutting	2310	42 1/2	7 1/2	1	726708 1/2	"-1-9	
Cutting Loam & Gravel	2970	41 1/4	6 3/4	1	836983	"-1-6	
6th mile Cutting stiff clay & Latentite	2310	43 1/2	8 1/2	1	804473 1/2	"-3-	
Bridge of 2 arches							
Cutting stiff clay & Latentite	1650	43 1/2	8 1/2	1	574624	"-3-	
Cutting Latentite & hard Gravel	660	37 1/2	11	1	272250	"-4-	
Cutting do do	660	38	11 1/2	1	288420	"-4-	
7th mile Cutting	1290	36	8 1/2	1	127627 1/2	"-4-	

Bridge of 2 arches					
Cutting ditches and hard drains	990	36	8 1/2	1	2,145.26 " 4
8" mls Cutting ditches and drains	2012	35 1/4	8 3/4	1	620,576 1/4 " 4
do do	1100	31 1/2	4 1/2	1	212,022 3/4 " 4
12 Distributing Channels					
Compensation for land					
11 Irrigation sluices as per Plan No 1					
1 do do as per Plan No 2					
Band across neck of alluvial fan					
supplying Channel and Valley					
Drainage Channel from Chubab					
Old Drainage Channel					
Drainage Channel from near Ankapally					
to Pottampadu Swamp					
Cutting	2640	36 3/4	8 1/2	1	824,670 " 1/2
do	1620	37 1/2	9	1	448,500 " 1
do	1640	34 1/2	7	1	376,060 " 1
Total Feet of Cutting					1,649,230
or Gravel					617,12 1/2
Deepening & Improving old drain					
from the Pottampadu Swamp to near					
the Village of Darbala metta					
Cutting	3260	33	6	1	645,480 " 1
do	3360	30	4	1	403,200 " 1
do	3060	28 1/2	3	1	260,775 " 1
Total Feet of Cutting					1,309,455
or Gravel					48,498 1/2
Surplus Channel from Ankapally					
Reservoir Escape to Main Drain					

7 M 19/5/54

Detailed Estimate No 4
 14 or 15 Meters Drainage
 District Mellore Taluk
 Pennair Delta

Work Constructing a Head sluice for Irrigating Drainage

Particulars of Work		Measurements				
		Length	Breadth	Height	Number	Cubical Content
Concrete	Abutments	11	8 1/4	3/4	2	136 1/8
	Piers	19 1/4	6 1/4	3/4	7	631 5/8
	Front Wings	29	8 1/4	3/4	2	358 7/8
	Rear do	29	9 3/8	3/4	2	307 13/16
	do Returns	11	8	3/4	2	132
	Front Retaining Wall	94	5	3/4	1	352 1/2
	Rear do	58 1/2	5	3/4	1	208 1/8
	Inverts	9 1/2	5 1/2	2/4	8	313 1/2
	Front flooring	73 1/2	19 1/2	3/4		1074 15/16
	Rear do	64	21 1/2	3/4		1032
	Spandril	29 3/4	5 1/2	1 1/2		245 7/8
	Total					4792 15/16
Foundation	Abutments	11	5 1/4	6	2	693
	Piers	12 1/2	3 5/8	4 1/2	7	1378 5/8
	do Front portions	4 3/8	3 5/8	4	7	444 1/8
	Front Wings	28	5 1/4	5 1/2	2	1617
	Rear do	29	5 7/8	6	2	2046 1/2
	do Returns	10 1/2	5	6	2	630
	Front Retaining wall	95	2 1/2	5 1/2	1	1187 1/2
Superstructure	Rear do	54	2 1/2	6		810
	Abutments	11	3 3/4	10	2	825
	Piers	11 1/2	2 1/2	9	7	1811 1/4
	do Front portion	4	2 1/2	9 1/2	7	665
	Caps	31 1/2	2 1/2	2 3/8		187
	do Keen backs	11	2 1/2	4 3/4	7	48 1/8
	Front Wings	28	2 7/8	9 3/4		1541

Coping	28 $\frac{1}{4}$	2 $\frac{1}{2}$	1	2	141 $\frac{1}{4}$
Rear Wings	29	3 $\frac{1}{8}$	12 $\frac{1}{2}$	2	2210 $\frac{5}{16}$
do Returns	10 $\frac{1}{2}$	2 $\frac{1}{2}$	10	2	525
Coping with returns	38	1 $\frac{1}{2}$	1	2	114
Front flooring	73 $\frac{1}{2}$	19 $\frac{3}{4}$	1 $\frac{1}{2}$	"	2177 $\frac{1}{16}$
Rear do	64	22	1 $\frac{1}{2}$	"	2112
Face walls	66	2 $\frac{3}{4}$	1 $\frac{1}{2}$	2	544 $\frac{1}{2}$
Backing to arches	11	3	$\frac{1}{2}$	2	33
Blocking Courses	70	1 $\frac{1}{4}$	1	2	175
Parapets	69 $\frac{1}{2}$	$\frac{3}{4}$	1	2	104 $\frac{1}{4}$

Total 22028 $\frac{7}{16}$

Arch Work	9 $\frac{1}{2}$	9	1 $\frac{1}{2}$	8	1026
	1	9	1 $\frac{1}{2}$	8	108
	9 $\frac{1}{2}$	6 $\frac{1}{2}$	1 $\frac{1}{2}$	8	741

Total 1875

Painting Squares					75 $\frac{1}{4}$
Pebble stone Cauter	51 $\frac{1}{2}$	20	2 $\frac{1}{4}$	1	2317 $\frac{1}{2}$
	20	17	2	2	1360

3677 $\frac{1}{2}$

Cyos 136 $\frac{54}{100}$
1650

Earth Work Cyos

Face wood shutters	6 $\frac{1}{2}$	3"	15	8	195
--------------------	-----------------	----	----	---	-----

Metalling	Cyos				16 $\frac{1}{3}$
-----------	------	--	--	--	------------------

Iron bars	Rfl				240
-----------	-----	--	--	--	-----

Painting
Cauter
Sunrise

1065/167

Detailed Estimate No 4
1 $\frac{1}{2}$ or Millers Range
District Millers Range
Punjab Delta

Work Constructing an irrigation sluice vice
Plan No 2

Particulars of Work	Measurement				Cubical Contents
	Length	Breadth	Height Depth	Number	
Concrete	4 $\frac{3}{4}$	8 $\frac{1}{4}$	$\frac{3}{4}$	"	28-7 $\frac{1}{2}$
	9 $\frac{1}{2}$	5 $\frac{1}{8}$	1	2	97-4 $\frac{1}{2}$
	8 $\frac{1}{2}$	4 $\frac{3}{4}$	1	2	80-9
	4	4 $\frac{1}{2}$	1	1	18-0
Total					224-9
Panel	6	12	1 $\frac{1}{4}$	1	90-0
Front retaining wall	2	1 $\frac{3}{4}$	3 $\frac{1}{2}$	1	12-3
Rear do	1 $\frac{3}{4}$	1 $\frac{3}{4}$	3 $\frac{1}{2}$	1	10-9
do	4	2	4 $\frac{1}{2}$	1	36-
Foundation Front Wings	8 $\frac{1}{2}$	2 $\frac{3}{4}$	4 $\frac{1}{2}$	2	210-4 $\frac{1}{2}$
Rear do	7 $\frac{1}{2}$	3 $\frac{1}{8}$	4 $\frac{1}{2}$	2	210-11
Above Front Wings	8	1 $\frac{1}{2}$	4 $\frac{1}{2}$	2	108-0
Coping	8 $\frac{1}{4}$	2	$\frac{3}{4}$	2	24-9
Rear Wings	7	1-9 $\frac{3}{4}$	5 $\frac{1}{2}$	2	139-7
Coping	7 $\frac{1}{4}$	2	$\frac{3}{4}$	2	21-9
Face wall	5 $\frac{1}{4}$	1 $\frac{1}{2}$	3 $\frac{1}{2}$	2	52-11
Parapets	5 $\frac{1}{4}$	1	1	"	5-0 $\frac{1}{2}$
Total					922-4
Demolition for retaining walls	2 $\frac{3}{4}$	$\frac{1}{2}$	1 $\frac{1}{4}$	"	1-9
Total					920-6

Counting Squares
Pebble stone Lateral.

5	4 1/4	1 1/2	3 1/4
4 1/4	6	2	51
Total			83
Total			3 2/7

Earth from 12 yds
Teak wood Planks
Shutting with working gear etc.
Balancing
Lenses.

100
2 1/2
1

Detailed Estimate No 4
1st or Yellow Range
District Yellow Range
Punjab Delta

Work Constructing an Aqueduct near Kaurpatti Road

Particulars of Work	Measurement				Cubic Content
	Length	Breadth	Height	Number	
Concrete	34	3	9"	4	306
			Total Cft		306
Foundation Abutments	39 1/2	4 1/2	4	2	1416
do to Piers	39 1/2	3 1/2	4	3	1652
do to Wings	11	9 1/2	4	4	1613 1/3
do to do	11 1/2	8	4	4	1493 1/3
Abutments above	35 1/2	3 1/4	3	2	692 1/4
Piers do	37	2 1/2	3	3	832 1/2
Abutment	34	2 1/2	1/2	3	127 1/2
do	34	3	1/2	2	102
Packing to Anchors	34	5 1/2	1/4	2	467 1/2
Spanvil	34	6 1/2	3/4	3	497 1/4
Caps	2 1/2	1 1/2	1 1/2	6	33 3/4
Wings do	11 1/2	8	3 3/4	4	1380
Wing Walls	75 1/2	4 1/2	10 1/2	2	6971 1/2
do Top Courses	75 1/2	4	1/2	2	300 2/3
do do	75 1/2	5	1/2	2	375 5/8
Arch Works	34	6 2/3	2	4	1813 1/3
Concrete	34	4 3/4	1 1/4	4	807 1/2
Total Cft					20576 5/12

28 1905/06

Painting ————— Squares
 Excavating foundations —————
 Asphalt —————

Painting —————
 Centing & Surveys —————

				692
				839
				10307
				10-1/2
	27 1/2	34		

Detailed Estimate No 4

1st or Mellone Range

District Mellone Taluk

Pennair Delta

Work Constructing Bridge of 2 Arches 15' span
 across the Surrafully Channel.

Particulars of Work		Measurement					Cubical Contents
		Length	Breadth	Height	Depth	Number	
Concrete —————		18	12	1 1/4		1	270
		14	14 1/2	3/4		2	304 1/2
		Total					574 1/2
Foundation	Abutments —————	21 2/3	6	5		2	1300
	Pier —————	21	4 1/4	5		1	446 1/4
	Wings —————	23	6 1/2	5		4	2798 1/2
	Pilaster to the end —————	2	1/4	5		4	10
Above	Retaining Wall —————	28	2 1/2	4		2	560
	Abutments —————	28 1/2	1 1/2	10		2	84
	Pier —————	18 1/2	3	10		1	555
	Caps —————	3	2	2		4	48
	String Course —————	84	1/4	1/2			10 1/2
	Wings —————	23	3' 3 1/2"	11 1/8		4	3369 1/8
	Pilaster —————	2	3"	6		4	12
	Face wall —————	18	1 1/2	1 1/4		2	67 1/2
		25	1 1/2	2 3/8		2	178 1/8
	Spanonil —————	14 1/2	8	1 1/3			154 2/3
	Skew backs —————	14 1/2	3	9/16		1	24 15/32
	Do —————	14 1/2	2 3/4	1/2		2	39 7/8
	Backing to arches —————	14 1/2	2 3/4	1/2			39 7/8
	Do —————	14 1/2	7	7/16		2	88 13/16
	Parapets —————	90	1 1/2	3		2	607 1/2
	Blocking Course —————	43	1 1/2	1		2	129
	Pedestals —————	1 3/4	1 3/4	3		4	36 3/4
		Total					12054 25/48

R W 1965/64

Arch Works	14½	19½	15½	2	911
Imnts	14½	11½	1	2	333

Notes off 1252

Cornice Work	Rifle	194
Pointing	Syr	55
Earth Work	Gos	666
Metalling	Cyos	52
Guard Poles	2	
Centum		
Plating		
Summaries		

18th 1905/64

Detailed Estimate
District Bellora Talig Jidura
North converting Tarnepalli East into an Reservoir
for the Southern portion of the Pennair Delta

Particulars of Work	Measurements				Cubic Contents
	Length	Breadth	Height	Volume	
Banking from Station 2 to Station 6	1650	23.68	8.84	.	345,396.4800
Banking from Station 6 to present Canal	525	34.94	14.47	.	265,430.4450
Banking side of Calingula	255	36.02	15.01	.	137,868.3510
Banking Transverse Section No 1	1200	40.88	17.44	.	855,536.6400
do do 2	1320	38.14	16.07	.	809,040.9360
do do 3	1140	42.46	18.23	.	882,412.2120
do do 4	1500	41.22	17.61	.	1088,826.3000
do do 5	1320	38.62	16.31	.	831,457.7040
do do 6	1320	38.00	16.00	.	802,560.0000
do do 7	1320	38.92	16.46	.	845,622.6240
do do 8	1800	39.98	16.99	.	1222,668.3600
do do 9	660	38.02	16.01	.	401,742.1320
do do 10	1500	35.08	14.54	.	765,094.8000
do do 11	1260	35.62	14.81	.	664,690.5720
Banking from Station 52 to Station 55	720	35.62	14.82	.	380,293.0560
Banking from Station 55 to Station 56	465	33.44	13.72	.	213,340.5120
Banking in Channel	30	39.44	16.72	.	19,783.1040
Banking from Station 56 to 60	1600	31.34	12.67	.	635,324.4800
do from 60 to 62	800	26.40	10.20	.	215,424.0000

Banking from station 62 to 65	1200	12.98	5.49	-	54,360.2400
<u>Total</u>	21,585				11,436.9400
<u>Deduct for existing Bonds as follows</u>					
From station 66 present Calmugula	525	18.50	8.50	-	82,556.2500
Excavation section No 1	1200	47.25	5.78	-	327,726.0000
do " 2	1320	55.00	5.97	-	587,545.4000
do " 3	1140	54.00	5.76	-	354,585.6000
do " 4	1500	75.25	5.21	-	588,078.7500
do " 5	1320	54.25	5.92	-	280,711.2000
do " 6	1320	60.75	3.62	-	290,287.8000
do " 7	1320	60.75	4.67	-	374,487.3000
do " 8	1800	56.00	4.73	-	476,784.0000
do " 9	660	73.00	3.79	-	152,602.2000
do " 10	1500	47.00	2.62	-	184,710.0000
do " 11	1260	31.50	1.98	-	78,586.2000
From station 62 to station 66	720	31.50	3.13	-	70,988.4000
From station 66 to station 66	465	15.75	1.64	-	12,010.9500
<u>Total</u>					5,691,660.0000
Balance of cubic feet					7,745,212.894
or cubic yards					286,857.
Surfing Earthwork	5,270	3 5/8	1/8	-	2,388
<u>Total Yards of Earthwork</u>					289,247
Gravel & Rockwork	5,270	8 1/8	1/2	-	21,409 7/8
Deduct for existing Rockwork	640	1 1/2	1/2	-	480
	640	1/2	1/2	-	160
<u>Total</u>					640.
<u>Total Yards of Gravel & Rockwork</u>					20,769 1/8
Gravel & Backing Yards	5,270	8 1/8	1/6	-	7,136 1/2

Surfing

Total square yards of Surfing 99,634 7/8

Camp Miller
3rd April 1867

Smith
Engineer
New House St. D.C.
Westminster Virginia
Superintendent D.C.

725	16	1360.
85	16	1360.
400	16 3/4	6700
440	16 3/8	7205
380	17 1/4	6555.
500	17 3/8	8812 1/2
440	15 7/8	6985
440	15 7/8	6985.
440	15 7/8	6985
600	16 1/2	9900
220	15 5/8	3437 1/2
500	13 1/2	6750.
420	14 1/2	6090
240	14 7/8	3570.
155	13 3/4	2131 1/4
10	13 3/4	137 1/2
533	14 1/8	10193 3/8
267	14 3/4	3938 1/4.
400	4 3/4	1900

Particulars of work	Measurements				Cubical Content
	L	B	D	H	
	64	7½	9	"	360
	23-9	6¾	9	"	120 7/8
	20-9	5¾	9	"	83 8/12
	26	3	9	"	58 ½
	8	2-6	6	"	10
Concrete	9	11-6	6	"	51 ¾
	21	3-9	9	"	59 1/8
	17	3-9	9	"	47 1/8
	4	4-6	9	"	13 ½
	Total Feet of Concrete				804 ½
Deduct for existing work	50	7½	9	"	281 ½
	Total Feet of Concrete				523
Foundation	20	5	4½	"	450
Wings	20-9	3¾	3½	2	551 ¾
Rear Cistern Side walls	11	2-6	3	"	82 ½
Wings	15-6	2-6	4	"	155
Retaining walls	26	1-3	2-9	"	89 3/8
Sluice Abutment	64	6	2	"	768
Superstructure	64	1-9	2	2	448
Arch	64	5-3	1-6	"	504
Front Apron	8	2-6	9	"	16
Do Do	11-6	9	1-6	"	155 1/4
Rear	4-3	4-6	1-6	"	28 1/8
Side walls (at Head)	11-6	3	11	"	379 ½

3.78.1.75/64

Blocking course	3	2 5/8	7/6	59 1/2
Wings	20.9	2 3/4	6.6	2 5/29 1/2
Rear Cistern low wall	11-6	7.6	5	86 1/2
Wings	12	1.6	5	90
Rear Cistern Arch	4-6	1-6	1-3	8 1/2
Front low wall	3	1-6	3	15 1/2
	3	1-9	1	5 1/4
Parapet	6-6	1-6	1-6	14 3/4
	7-6	1-3	1	9 1/8
Total of top of latents in masonry				1,543
Deduct old work	50	6	2	600
	50	1-9	2 2	350
	50	5-3	1-6	373 3/4
Total				1,343 3/4
Total of top of latents in masonry				2,999 1/4
	8	3 1/2	3/4	21
	2 1/2	1 1/2	3/4	2 1/2
Cast Granite	3 3/4	4	1	18
	5 3/4	4	1	22
	1 3/4	4	3/4	5 1/2
	3 1/2	3/4	1	2 3/8
Total				69 1/16
Deduct	8	1	3/4	6
	7	3/4	3/4	3 1/8
Total of top of Granite				9 1/16
Pointing Squares				10
Excavation				
Summers				

For other same as above

14 1965/64

Detailed Estimate No. 4 of 1867-68

1st or Nellore Range.

District Nellore—Taluk

Work Excavating & laying out the main channel and constructing the required masonry works

PARTICULARS OF WORK.	Measurement.				Cubical Contents	Remarks
	Length.	Breadth.	Height or Depth.	Number		
	Feet.	Feet.	Feet.		Feet.	
Head sluice						
Cutting hard-gravel	2310	44 3/4	5 1/2	1	60,300	"-2-6
Cutting stiff clay	2640	41 3/4	3 1/2	1	122,800	"-1-2
Cutting latents	830	42 3/8	4 1/3	1	60,537	"-4-
Banking	330	17 1/2	5 1/2	1	32,413	"-1-6
2nd mile cutting latents	1320	39 1/2	5	1	260,700	"-4-
Banking	1320	16	5	1	105,600	"-1-6
Cutting stiff clay	2640	39 1/4	4 1/2	1	500,800	"-1-2
Cutting	1320	37 1/4	4 1/2	1	200,400	"-1-1
3rd mile cutting	1320	35 1/4	4 1/2	1	212,800	"-1-1
Cutting	462	30 1/2	1	1	14,091	"-1-
Cutting	3498	34 1/4	5 1/2	1	608,906	"-1-2
Spurs and side party branch takeoff						
4th mile cutting	660	17 3/4	6 1/2	1	76,147	"-1-2
Regulating sluice						
Cutting	1980	13 1/4	3 1/2	1	91,823	"-1-
6 Irrigation sluice as per plan						
6 Distributing Channels						
Minor branch Channel						
Compensation for lands						
Spurs and side party branch						
Head sluice						

Cutting	3960	25 1/2	5 1/3	1	338,860	1
do	2865	17 3/4	1 1/2	1	76,253	1
Banking	2865	27 1/4	2	2	312,285	1
Indepartly Branch take off						
Cutting	4185	13	4	1	217,620	1
Regulator and Fall						
4 Irrigation sluices as per Plan No. 1						
Compensation for land						
Minor Branch Channel						
Indepartly Branch						
Cutting	5710	12	2 1/3	1	125,120	1
Banking	940	31	2	2	116,560	1
Regulator and Fall						
2 Irrigation sluices as per Plan No. 1						
Minor Branch Channel						
Compensation for land						

22 M 19/65/67

Detailed Estimate of 4 of 567/58.
 12 or 12000 Rupees
 District Melloo Taluk
 Pennair Delta
 Work. Constructing a Head sluice for Mangali
 Branches

Particulars of Work	Measurement					Cubical Contents
	Length	Breadth	Height or Depth	Number		
Concrete	50	15 1/2	3/4	"		581 1/4
	44 1/4	15 1/2	3/4	"		514 19/32
	16	1 1/8	2	8		416
				5	Atal.	1511 21/32
Foundation						
Abutments	10 1/2	5 1/2	5	2		577 1/2
Piers	15	3 1/2	3 1/2	7		1286 1/4
Front Wings	28	4 3/4	4 3/4	2		1263 1/4
Rear Wings	18	5 2/3	5	2		1020
Returns	15	4 1/3	5	2		650
Front Retaining Wall	69	2 1/2	4 3/4	"		819 3/8
Rear do	40 1/2	2 1/2	5	"		506 1/4
Superstructure						
Abutments	10 1/2	3 3/4	4	2		315
Piers	12 2/3	2 1/2	4	7		886 2/3
Caps	2 1/2	2 1/8	2 1/8	7		82 11/32
Anti water o	2 1/2	2 1/8	14 1/4	7		540 5/16
Skew backs	10 1/2	2 1/2	1/4	7		45 1/16
do	10 1/2	3	1/4	2		15 3/4
Span rail	41 1/2	10 1/2	3/4	"		326 13/16
Face walls	45 1/2	2 1/2	7 1/2	2		1706 1/4
Side walls	3 1/2	2 1/8	6 1/2	2		98 7/12
Front Wings	28	2 7/8	9 1/4	2		1489 1/4
Coping	28 1/4	2 1/2	1	2		141 1/4
Rear Wings	18	3 1/3	11	2		1320
Coping	18 1/4	2 1/2	1	2		91 1/4

Retums	15	2 $\frac{2}{3}$	8	2	640
Coping	15 $\frac{1}{4}$	2 $\frac{1}{2}$	1	2	76 $\frac{1}{4}$
Blacking Course	46	1 $\frac{1}{2}$	1	2	138
Parapets	45 $\frac{1}{2}$	1	2	2	182
Flooring	50	18	1 $\frac{1}{2}$	..	1350
Do	44 $\frac{1}{2}$	18	1 $\frac{1}{2}$	..	1201 $\frac{1}{2}$
Do	10 $\frac{1}{2}$	2 $\frac{3}{4}$	1 $\frac{1}{2}$	8	346 $\frac{1}{2}$
Arch Work	10 $\frac{1}{2}$	6	1 $\frac{1}{2}$	8	956
					Total 17872 $\frac{49}{144}$
Samped grouting for Spandrels	41 $\frac{1}{2}$	3 $\frac{1}{2}$	6 $\frac{1}{2}$	..	944 $\frac{1}{8}$
					Gr 35
Painting					63 $\frac{1}{4}$
Earth Work					940
Leak Wood Plank Cpl					43 $\frac{1}{2}$
Leak Wood Shutter with working					8
Gear					
Drum					
Rolling					
Centering					
Surveys					

22/1905/64

Detailed Estimate No. 4 of 1867-68
 1st or Nellore Range.
 District Nellore—Taluk
 Work *Constructing Regulating Sluice at the Drayalis Santh*

PARTICULARS OF WORK.	Measurement.				Cubical Contents
	Length.	Breadth.	Height or Depth.	Number.	
	35 $\frac{1}{2}$	6	1	2	126
Concrete	9	4 $\frac{1}{2}$	1	"	40 $\frac{1}{2}$
	12	12	$\frac{3}{4}$	"	108
				Total	574 $\frac{1}{2}$
Foundation Body	13 $\frac{3}{8}$	4 $\frac{1}{4}$	3 $\frac{3}{4}$	"	21 $\frac{11}{128}$
Wings	33 $\frac{1}{2}$	4	5	2	1340
Plating wall	11	2 $\frac{1}{2}$	5	1	137 $\frac{1}{2}$
Abutments	3 $\frac{1}{2}$	2 $\frac{1}{4}$	7	2	110 $\frac{1}{4}$
Bricking to Arch	27 $\frac{3}{8}$	3 $\frac{1}{2}$	$\frac{2}{3}$	2	13 $\frac{5}{12}$
Wings	30	2 $\frac{1}{4}$	9	2	1215
Coping	30 $\frac{1}{2}$	2	$\frac{3}{4}$	2	91 $\frac{1}{2}$
Flooring	17	12	1 $\frac{1}{4}$	"	180
Arch Wall	4 $\frac{3}{4}$	3	1 $\frac{1}{2}$	"	15 $\frac{3}{8}$
Inverted arch	3 $\frac{1}{2}$	4	1 $\frac{1}{4}$	"	17 $\frac{1}{2}$
				Total	3142 $\frac{3}{8}$
Rubble Stone (Kutab)	15	12	1 $\frac{1}{2}$	"	270
	15	3	1 $\frac{1}{2}$	"	67 $\frac{1}{2}$
	5 $\frac{3}{4}$	3	1 $\frac{1}{2}$	"	25 $\frac{3}{8}$
					363 $\frac{3}{8}$
				Cpl	13 $\frac{11}{24}$
Leak Wood Shutter	3 $\frac{1}{4}$	3	10	"	8 $\frac{1}{8}$
Painting					10
Iron bar					4 $\frac{1}{4}$
Earth Wall					194
Centering					
Surveys					

1st or Nellore Range.

District Nellore Talug

Work *Constructing Head Office for Spinn and*
Indiparty Branch

PARTICULARS OF WORK.	Measurement.				Cubical Contents
	Length.	Breadth.	Height or Depth.	Number.	
<i>Base</i>	9	22	1 1/2	"	247 1/2
<i>Sides</i>	9	1 1/2	7	2	189
<i>Foundation Front Wings</i>	16 1/2	3 3/8	5	2	598 1/8
<i>Rear Wings</i>	26	3 3/4	5	2	970
<i>Front Retaining wall</i>	24	2 1/4	5	1	270
<i>Rear Retaining wall</i>	19 1/2	2 1/4	5	1	249 3/8
<i>Abacus Front Wings</i>	16 1/2	2 1/8	6 1/2	2	442 13/32
<i>Coping</i>	17	2	3/4	2	51
<i>Rear Wings</i>	26	2 1/8	7	2	773 1/2
<i>Coping</i>	26	2	3/4	2	78
<i>Face wall</i>	8	3	1 1/2	1	36
<i>Do</i>	8	1 1/2	1 1/2	1	18
<i>Blocking course</i>	8 1/2	1 1/2	1	2	25 1/2
<i>Parapets</i>	8	1	1	2	16
<i>Front Flooring</i>	15	12 1/4	1 1/4	1	229 1/4
<i>Rear do</i>	20 1/2	18	1 1/4	1	461 1/4
<i>Total Cub of Concrete in Chimney</i>					4,630 13/32
	9	10	1	"	90
	27 1/2	5 3/4	1	2	316 1/4
<i>Concrete</i>	18	5 5/8	1	2	202 1/2
	20	18	1	"	360

22/19/65/69

Concrete	15	12	1	180
Stable Cake for				1140
Painting				12
Excavation				340
Iron bars				11 1/2
Fakwood shutters	8	5	10	12 1/2
Baling				
Centering and Scaffolding				

20 1905/06

Detailed Estimate No. of 1867-68

1st or Nellore Range.

District Nellore—Talug

Work *Repairing Dellia*
Constructing Tall to the
Vides Plan No. 2

PARTICULARS OF WORK.	Measurement.				Cubical Contents
	Length.	Breadth.	Height or Depth.	Number	
Concrete	5 1/2	7	1	1	2 1/2
	7	8	1	2	112
	10 1/2	6 1/2	1	2	136 1/2
	12 1/2	7	1	2	175
	7 1/2	6	1	2	90
	12	5	1	1	60
	12	12	3/4	1	108
Total					684
Foundation Body	2 5/12	5	5	1	60 5/12
" Wing	7	6	5	2	120
" Front Returns	9 1/2	4 1/2	5	2	427 1/2
" Wings	13	5	5	2	650
" Rear Returns	6 1/2	4	5	2	260
" Retaining wall	12	3	5	1	180
Abore Body	3 5/12	3 1/2	7	1	83 1/4
" Wings	7	3 1/4	13	2	591 1/2
" Coping	4	2	3/4	2	12
" Returns	9	2 1/2	10	2	450
" Coping	9 1/4	2	3/4	2	27 3/4
" Wings	13	2 3/4	11	2	786 1/2
" Coping	13 1/4	2	3/4	2	39 3/4
" Returns	6	2 1/4	9	2	243
" Retaining wall	12	2	3	1	72
" Flooring	12	12	1 1/4	1	180
" String Course	6 5/6	7	1/2	1	11 1/4

Arch Wall — $1\frac{1}{2}$ $2\frac{1}{2}$ $\frac{5}{6}$ " $9\frac{1}{2}$

Total 4514

Pubble stone (Katerite) — $\left\{ \begin{array}{l} 12 \\ 10 \end{array} \right.$ 10 $1\frac{1}{2}$ " 180
 10 2 10 2 400

580

Cyds — $21\frac{13}{2}$

Shut Wood Shutter — $3\frac{11}{12}$ 3" $1\frac{3}{4}$ " $6\frac{3}{4}$

Earth Wall — Cyds 300

Iron Bars — Rft 5

Pointing Ego — 112

Baling —

Centering 11 Sundries —

22/1965/64

Detailed Estimate No. 4 of 1867-68

1st or Nellore Range.

District Nellore—Talug

Work Excavating Vallur Branch Channel

PARTICULARS OF WORK.	Measurement.				Cubical Contents	Remarks
	Length.	Breadth.	Height or Depth.	Number.		
Head Sluice (separate estimate)						
Cutting	1320	17	4	1	89760	1-1
Banking	1320	20	2	1	52800	1-1
Surfing	1320	23	"	2	60720	1-4
Cutting	3960	15	4	1	237600	1-1
Banking	3960	24	2	1	190180	1-1
Surfing	3960	23	"	2	182160	1-4
2 nd mile Cutting	1980	18 $\frac{3}{4}$	5 $\frac{1}{2}$	1	204187 $\frac{1}{2}$	1-1
Cutting	1320	17 $\frac{1}{2}$	4 $\frac{3}{4}$	1	107800	1-1
Cutting	1980	18 $\frac{3}{4}$	5 $\frac{1}{2}$	1	204187 $\frac{1}{2}$	1-1
3 rd mile Cutting	2640	17 $\frac{1}{4}$	4 $\frac{1}{2}$	1	204930	1-1
Cutting	2640	13 $\frac{1}{2}$	3 $\frac{3}{4}$	1	130680	1-1
Banking	2640	37	2	1	195360	1-1
Surfing	2640	25	"	2	132000	1-4
4 th mile Cutting	5280	10	2 $\frac{1}{2}$	1	132000	1-1
Banking	5280	86 $\frac{1}{2}$	2	1	913440	1-2
Surfing	5280	32	"	2	337920	1-4
5 th mile Cutting	2640	8	2	1	42240	1-1
Banking	2640	105	2	1	554400	1-2
Surfing	2640	34	"	2	179520	1-4

Fall
 Cutting 2640 24 1/4 4 1/2 1 27 3/4 250
 6 1/2 mile cutting 1980 25 1/2 4 3/4 1 236 1/2 20

Regulator
 Irrigation sluices 184 1
 Minor Branch Chamels aggregate
 Length 6 miles
 Compensation for land

100. 28 1965/64

1st or Nellore Range.

District Nellore—Taluk

Work Constructing Regulator Sluices for Vallur
 Branch Chamel

PARTICULARS OF WORK.	Measurement				Cubical Contents
	Length.	Breadth.	Height or Depth.	Number	
Concrete Abutments	7 1/2	8 3/4	3/4	2	98 7/8
Piers	11	17 1/2	3/4	"	144 3/8
Front Wings	31 3/4	7 1/2	3/4	2	346 3/2
Rear Wings	23 3/4	7 1/2	3/4	2	267 3/16
Front Retaining wall	38 1/2	5	3/4	"	144 3/8
Rear Retaining wall	14 1/2	5	3/4	"	16 7/8
Below Flooring	15 1/4	7/8	1/4	3	160 8
Front Apron	26 1/2	14 1/2	3/4	"	388 3/16
Rear Apron	12	14 1/2	3/4	"	1030 1/2
Spandrel	11	3 1/4	5 1/8	"	241 1/2
Total Cubic feet of Concrete					1936 7/8
Foundation Abutments	8 3/4	5 3/4	6	2	603 3/4
Piers	15 1/4	4 1/4	6	2	777 3/4
Front Wings	30 7/8	5	5 3/4	2	1760 1/8
Rear Wings	21 7/8	5 1/4	6	2	1362 3/8
Front Retaining wall	40 3/4	2 3/4	5 3/4	"	644 3/4
Rear Retaining wall	6 3/4	2 3/4	6	"	111 3/8
Superstructure Abutments	8 3/4	3 3/4	5 1/2	2	360 1/8
Piers	11 3/8	3	5 1/2	2	375 3/8
Front Portins	2 7/8	3	14 1/4	2	224 7/8
Caps	2 5/8	3	2 7/8	2	40 1/2
Shew backs	8 3/4	3	1/4	2	13 1/8

Front Wings	30	2 1/8	9 1/4	2	146 5/8
Coping	30 1/2	2	1	2	127
Rear Wings	21	2 3/4	10 1/2	2	121 1/2
Coping	21 1/2	2	1	2	80
Front flooring	27 1/2	17 3/4	13 1/4	"	804 1/2
Rear flooring	15	18 1/2	2	"	1481
Flooring between Arches	10 3/4	2 1/2	2	3	161 1/4
Backing to Arches	8 3/4	4	1	2	70
Hand rails	12	8 3/4	1 1/2	"	157 1/2
Face walls	17	2 1/4	6 1/8	2	471 3/4
D. Sides	4 1/2	2 1/4	5 1/4	2	60 3/8
Parapets	16 1/2	1	1	2	33
Stat. Gachap	11 1/2	11 1/2	11 1/2	11 1/2	11 1/2
Arch work	8 3/4	5 1/2	1 1/2	3	216 3/8
Painting of squares					31 1/2
Public Room (District)	20	8	2 1/2	"	400
do do	20	9	2	2	720
Slab					1120
Garden					41 1/2
Excavation Garden					1138
Metalling Garden					4
Shutters					
Teak Beam	16 1/2	1	1	"	16 1/2
Baling					
Centering					
Undries					

8 W 1965/67

DETAILED ESTIMATE No. 4 of 1867/68,

80

173

District

Nellore

Work

Constructing Fall near the Bramanadavum Tuti Tank in the Valluru Branch Channel N.1.

Particulars.	Number.	Measurement.			Cubical Contents.
		Length.	Breadth.	Height.	
Concrete	2 1/2	8 1/4	1	"	20 5/8
	23 1/4	8 3/4	1	2	406 7/8
	18 2/3	9 1/2	1	2	340 2/3
	7 1/2	8	1	2	120
	15	15 5/8	9	"	153
	13 1/4	5 1/2	1	"	72 7/8
				Total	1114 1/2
Foundation & Dory	4 3/4	6	5	"	142 1/2
" Front Wings	11	8	5	2	880
" Returns	12	8	5	2	960
" Rear Wings	18 2/3	6 7/8	5	2	1283 1/3
" Returns	7 1/2	5 3/4	5	2	431 1/4
" Retaining Wall	13 1/4	3 1/4	5	"	215 5/16
Above Dory	4 3/4	3 7/8	8	1	147 1/4
" Front Wings	11	4 1/8	16 1/2	2	1497 3/8
" Coping	7 3/4	2	3/4	2	23 1/4
" Returns	12	14 1/2	13 1/2	2	1336 1/2
" Rear Wings	18 2/3	3 7/8	14 1/4	2	1895 1/4
" Coping	18 2/3	2	3/4	2	56
" Returns	7 1/2	3	12	2	540
" Coping	7 3/4	2	3/4	2	23 1/4
" Retaining wall	13 1/4	2	4	1	106
" Flooring	15	13 5/8	1 1/4	"	255 15/32
" Parapets	4 3/4	3/4	3/4	2	5 1/2
" Arch work	4 1/4	6	5/6	"	21 1/4
				Total	9819 1/3

Particulars .	Number.	Measurement.			Cubical Contents.
		Length.	Breadth.	Height	
Rubble Stone / Vateneta /	18	15	2	"	540
	18	2	13	2	936
					1476
Pointing					54 $\frac{2}{3}$
Iron Bars					28 $\frac{1}{2}$
Teak wood shutter					18 $\frac{3}{4}$
Carth Wood	5 $\frac{1}{4}$	3	9 $\frac{1}{4}$		12 $\frac{1}{8}$
Walting					700
Unrice					

22/1965/64

Detailed Estimate No 4, 1910, 1911
 1 $\frac{1}{2}$ or Kallura Range
 District & Kallura Taluk
 Ponnai Delta
 Constructing Regulator near Vallur Sank in the Vallur Branch Channel

Particulars of work	Measurement					Cubical Contents.
	Length	Breadth	Height	Depth	Number	
Concrete						
Wings	17 $\frac{3}{4}$	6	1	1		106 $\frac{1}{2}$
do	21 $\frac{3}{4}$	6	1	1		130 $\frac{1}{2}$
Curved portion	9 $\frac{1}{2}$	6 $\frac{1}{2}$	1	1		61 $\frac{3}{4}$
Retains	5	6 $\frac{1}{2}$	1	4		130
Abutments	11	7	1	2		154
do	11	6	1	2		132
Retaining wall	8	4 $\frac{1}{2}$	1	1		36
do	8	5	1	1		40
do	$\frac{1}{2}$	4 $\frac{1}{2}$	1	1		2 $\frac{1}{4}$
do	$\frac{1}{2}$	5	1	1		2 $\frac{1}{2}$
Flooring	10 $\frac{3}{4}$	5 $\frac{3}{4}$	1	1		61 $\frac{13}{16}$
do	3	5 $\frac{3}{4}$	1	1		17 $\frac{1}{4}$

Total of 874 $\frac{9}{16}$

Foundation Wings	16 $\frac{5}{8}$	3 $\frac{3}{4}$	5	1		311 $\frac{25}{32}$
do	20 $\frac{5}{8}$	3 $\frac{3}{4}$	5	1		388 $\frac{25}{32}$
Curved portion	9 $\frac{1}{2}$	4 $\frac{1}{4}$	5	1		201 $\frac{7}{8}$
Retains	5	4 $\frac{1}{4}$	5	4		425
Abutments	9 $\frac{7}{8}$	4 $\frac{3}{4}$	5	2		469 $\frac{1}{16}$
do	9 $\frac{7}{8}$	3 $\frac{3}{4}$	5	2		370 $\frac{5}{16}$
Retaining wall	10 $\frac{1}{4}$	2 $\frac{3}{4}$	5	1		140 $\frac{15}{16}$
do	10 $\frac{1}{4}$	2 $\frac{1}{4}$	5	1		115 $\frac{5}{16}$
do	2 $\frac{3}{4}$	2 $\frac{3}{4}$	5	1		37 $\frac{13}{16}$
do	2 $\frac{3}{4}$	2 $\frac{1}{4}$	5	1		30 $\frac{15}{16}$

1st or Nellore Range.

District Nellore—Taluk

Work—Constructing an Irrigation sluice, as per
Plan No. 1.

PARTICULARS OF WORK.	Measurement.				Cubical Contents
	Length.	Breadth.	Height or Depth.	Number	
Concrete	6 $\frac{19}{24}$	8 $\frac{1}{2}$	3 $\frac{1}{4}$	1	43 $\frac{17}{24}$
	12	4 $\frac{1}{2}$	1	1	6 $\frac{1}{2}$
	15	4 $\frac{3}{4}$	1	2	14 $\frac{21}{8}$
	12 $\frac{1}{2}$	4 $\frac{1}{2}$	1	2	11 $\frac{7}{2}$
					Total 30 $\frac{5}{8}$
Parapet	10	8	1 $\frac{1}{4}$	1	100
Retaining Wall	2	2 $\frac{1}{4}$	4 $\frac{1}{2}$	1	20 $\frac{1}{2}$
	1	2 $\frac{1}{4}$	4 $\frac{1}{2}$	1	10 $\frac{1}{8}$
					Total 32 $\frac{1}{4}$
Foundation—Front Wings	13	2 $\frac{3}{4}$	4 $\frac{1}{2}$	2	32 $\frac{1}{4}$
" " " " " " " "	10 $\frac{1}{2}$	2 $\frac{1}{2}$	4 $\frac{1}{2}$	2	23 $\frac{1}{2}$
" " " " " " " "	12	1 $\frac{5}{8}$	3 $\frac{1}{2}$	2	120 $\frac{3}{4}$
" " " " " " " "	9 $\frac{1}{2}$	1 $\frac{1}{2}$	1	2	11 $\frac{1}{4}$
Front Face Wall	3 $\frac{9}{16}$	1 $\frac{1}{4}$	3 $\frac{3}{4}$	1	17 $\frac{3}{4}$
Rear " " "	3 $\frac{9}{16}$	1 $\frac{1}{4}$	1 $\frac{3}{4}$	1	8 $\frac{1}{4}$
Parapet	3 $\frac{9}{16}$	2 $\frac{1}{4}$	3 $\frac{1}{4}$	1	2 $\frac{1}{8}$
					Total 95 $\frac{1}{8}$
	10	7	12	1	105
Rubble stone (Latite)	7	3 $\frac{1}{4}$	2	1	45 $\frac{1}{2}$
					Total 150 $\frac{1}{2}$
					Cy 5 $\frac{1}{2}$
					3
Painting—Spt.					129
Earth Work—Cpt.					11
Scall Beam—Cpt.					16
Shutter with working gear					
Lundries					

Wings	16	2	6	1	
do	20	2	6	1	24
Curved portions	9 $\frac{1}{2}$	2 $\frac{5}{12}$	6	1	73 $\frac{7}{12}$
Return	5	2 $\frac{1}{4}$	6	1	270
Abutments	8 $\frac{1}{2}$	3	4 $\frac{5}{24}$	2	214 $\frac{5}{8}$
do	8 $\frac{1}{2}$	2	6	2	204
Shen backs	8 $\frac{1}{2}$	2	6	2	25 $\frac{1}{2}$
do	8 $\frac{1}{2}$	1	5	2	10 $\frac{5}{8}$
Packing to Arch	8 $\frac{1}{2}$	4 $\frac{1}{2}$	2	2	28 $\frac{11}{16}$
do	8 $\frac{1}{2}$	1 $\frac{3}{4}$	1 $\frac{5}{8}$	2	3 $\frac{23}{32}$
Face walls	16 $\frac{1}{2}$	1 $\frac{1}{2}$	1 $\frac{5}{8}$	2	80 $\frac{7}{8}$
do	7	1 $\frac{1}{2}$	3 $\frac{1}{4}$	2	15 $\frac{3}{4}$
Blacking course	17	1 $\frac{1}{2}$	3 $\frac{1}{4}$	2	38 $\frac{1}{4}$
do	7 $\frac{1}{2}$	1 $\frac{1}{2}$	3 $\frac{1}{4}$	2	16 $\frac{7}{8}$
Parapets	16 $\frac{1}{2}$	1	1	2	33
do	7	1	1	2	14
Flooring	11 $\frac{1}{4}$	6 $\frac{3}{8}$	1 $\frac{1}{2}$	1	107 $\frac{37}{64}$
do	3 $\frac{3}{4}$	6 $\frac{3}{8}$	1 $\frac{1}{2}$	1	35 $\frac{55}{64}$
Arch door	8 $\frac{1}{2}$	14 $\frac{1}{2}$	1 $\frac{1}{2}$	1	154 $\frac{1}{8}$
do	8 $\frac{1}{2}$	6 $\frac{1}{2}$	1 $\frac{1}{2}$	1	73 $\frac{3}{8}$
					Total 438 $\frac{1}{8}$
Painting—Squares					13
Rubble stone for Center of piers	16 $\frac{1}{2}$	2	2	1	264
do	7	8	2	1	112
do—Inner—do	11 $\frac{1}{4}$	5	1 $\frac{1}{2}$	1	106 $\frac{1}{4}$
do	5 $\frac{3}{4}$	5	1 $\frac{1}{2}$	1	42 $\frac{1}{2}$
do	10 $\frac{1}{2}$	1	1 $\frac{1}{2}$	1	15 $\frac{1}{2}$
Excavation	5	8 $\frac{1}{2}$	1 $\frac{1}{2}$	1	25 $\frac{1}{2}$
Teak wood shutters	10	3	11	1	33
do	4 $\frac{1}{2}$	3	11	1	12 $\frac{3}{4}$
Iron bars					12 $\frac{3}{4}$
Binding					37
Center & corners					

28/12/67

1st or Nellore Range.

District Nellore--Telug

Work - *Constructing Fall to the Indipertu Lake*
Vide Plan No 2.

179

Quantities	Description of Work.	Rate.	Amount.	Total.
681	Cft. of concrete	2	858	
4514	Cft. of Lateral in Chambers	2	75254	
11 1/2	Sq. of Painting	2	23	
21 1/2	Cy. of Rubble Stone Lateral	18	3237	
300	Cy. of Earth Work	1	1812	
5	Sq. of Iron Bars		82	
6 3/4	Cft. of Oak Wood butter	38	2310	
	Baling		75	
	Centering & Lardies		2171	
				1060

Commissioner. Local Works
Supl. Engineer D.

Engg's Office
Camp Nellore
3rd April 1871

Agmt
Executive Engineer
1st Nellore Range

8 or 1965/11

021965/11

17th Nov 1867
 By Order of the
 Works Commissioning and carrying out the Carapalla River
 151

Months	Particulars of work	Rate	Amount	Total
934 1/2	Cft of Concrete. ———	" 2 "	116 13 "	
5086	Cft of Limestone Churn. ———	" 2 3 "	708 3 "	
30 1/4	Spray Painting ———	1 8 "	45 6 "	
107 3/4	Cft of Paving ———	1 " "	107 12 5 "	
33	Cwt of Iron Posts. ———	12	396 " "	
18	Flat Board & Shuttles. ———	3 " "	204 " "	
	Excavation ———	" " "	25 " "	
	Sundries ———		66 13 7	
				Total Paper. 1670

By Order of the
 Camp. T. M. S. Hallam's
 24th September 1868
 1st of October
 3rd April 1867

By Order of the
 Camp. T. M. S. Hallam's
 24th September 1868
 1st of October
 3rd April 1867

Abstract Estimate No. 4, 1867-68

1st or Kellore Range

District Kellore Taluk

Perman Datto

155

Work Excavating the Surveypully channel and constructing the necessary irrigation and drainage works connected with it.

Quantities	Description of work	Rate	Amount	Total
1	Head sluice vide separate estimate			7340 0 0
109,781	Cubic yards of cutting	0 4 0	27445 4 "	
183,317	do of do	" 2 "	34371 15 "	
36,335	do of do	" 2 "	4541 14 0	
26,915	do of do	" 1 9	2943 13 3	
25,006	do of do	" 1 6	9844 5 "	
10,821	do of do	" 1 0	676 5 "	
				79823 8 3
22,585	Cyards of Banking	" 1 3	1766 7 3	
1,252	do of do	" 1 "	78 4 "	
				1845 11 3
16,427	Square yards of turping	" " 4	342 3 8	
				342 3 8
12	Distributing channels	200 0 0		2400 " "
	Compensation			3000 " "
11	Irrigation sluices vide Plan No 1	300 0 0		3300 " "
12	do do do			" "
	Vide Plan No 2			280 " "
	Band across Anikofulla Lake supplying channel and Vally			150 0 "
	Drainage channel from Aqueduct to old Ramerooy channel			770 " "
	Carried forward			99248 7 2

Brought forward						99248 1/2
Drainage channel from near						
Arikapally to Pottempudi						
swamp						
61,712	Cyarding of cutting	1	2	4499	13 1/4	4499 13 1/4
Deepening and Improving old						
Drain from Pottempudi						
swamp to near the Village						
of Sarkalanitto						
38,840	Cyards of cutting	0	1	0	2427 8 "	
9,658	do of do	"	"	10	503 1/4	
Sarrapally channel from						2930 8 1/4
Sarrapally Reservoir es-						
cape to Drain Drain						550 "
1	c. Aqueduct vide separate estimate					5000 "
4	Bridges of 2 Arches vide					
Separate estimate		3540	0			14160 "
Sundries						111 3/4
Total estimate Rupees.						126500 0 0

Supg Engineer's Office Sec
 Basulipatnam
 30th April 1867

Co. M. M. M. M. M.
 Supg Engineer 2nd Division

22/1965/64

Enclosure in letter
No 17 dated 3rd May 1894
to the Secretary
to Government
D. J. W. (1)

10.

222 195/11

Excavating the
Sarrapilly Channel
and Constructing
the necessary
regulation & drainage
works connected
with it.
No 155/510

Abstract Estimate No 4. 5 2
1st or Alluvial Range 189
District Alluvial Range
Punair Delta

Work. Excavating Sarrapilly Branch Channel and
Constructing the required masonry works.

Quantity	Description of Work	Rate	Amount	Total
1	Head sluice Vice Separate Estimate			4440 "
11898	Excavation of cutting	4 "	2974 8 "	
22333	" of "	2 6	3489 8 6	
64864	" of "	1 2	4726 12 "	
17140	" of "	1 1	1160 8 4	
522	" of "	1 "	32 10 "	12383 14 10
5111	" of Banking	1 6	479 2 6	479 2 6
1	Regulating sluice Vice Separate Estimate			800 "
6	Irrigation sluices as per Plan No 1	260 "	" "	1560 "
6	Distributing Channels	50 "	" "	300 "
	Minor Branch Channel			1760 "
	Compensation for land			1875 "
1	Spurs & Subordinate Branches			1100 "
22772	Excavation of cutting	1 1	1541 13 8	
8060	" of "	1 "	503 12 "	2045 9 8
11566	" of Banking	1 1	783 1 10	783 1 10
1	Fall Vice Plan No 3			970 "
4	Irrigation sluices as per Plan No 1	260 "	" "	1040 "

Amount for 29536 12 10.

Abstract Estimate No 4 of 1867-68

1st or Nellore Range

District Nellore Taluk

Pennicor Delta

193

Enclosure in letter
No 17 d / 3rd May 1867
to the Secretary
to Govt PWD

Work Excavating Valluru Branch channel

Quantities	Description of work	Rate	Amount	Total
1	Head sluice Vide separate estimate			3080
15,125	Cubic yards of cutting	" 1 1	1024 1 5	
53,810	do of do	" 1 0	3363 2 "	4,387
54,364	do of Banking	" 1 2	3964 8	
16,235	do of do	" 1 0	1014 11 0	4,978
99,146	Square yards of Surfing	" " 4	2065 88	2,065.88
1	Fall vide separate Estimate			3100
1	Regulator do do			1730
6	Irrigation Sluices Vide plan No 1	340 0 0		2040
	Minor branch channels			2640
1	Fall in Pantapottam branch ch ^{nl}			1350
	Vide Plan No 2 & 3			1800
	Compensation for lands			600
6	Distributing channels	100 0 0		600
	Sundries			68
Total Estimate Proper				27840

10.

22/19 65/67

Excavating the
branch channel
& constructing the
requisite masonry
works

No 334110

Suppl^y Office Secy
Muzulpattam
30th April 1867

Asst Comm^r Smt
Suppl^y 2^d Division

195

0211965/64

1st or Nellore Range

District Nellore--Talug

Work *Constructing an Irrigation Channel as per*
Plan No 1

Enclosure under
 No 17 dated 3rd
 May 1867 to the
 Secretary to the
 Govt W.D.

J.

822/1905/67

Excavating Vallam
 branch Channel
 and Constructing
 Masonry work
 connected with
 it

No 22/1867

Quantities	Description of Work.	Rate.	Amount.	Total.
305	Cft. of concrete	" 2 "	38 2 "	
951	Cft. of Laterite in Chumam	" 4 "	237 12 "	
5 1/2	Cy. of Rubble stone (Laterite)	2 8 "	13 12 "	
3	Sq. of Pointing	2 " "	6 " "	
129	Cy. of Earth Work	" 1 "	81 "	
16	Cft. of Teak Beam	3 8 "	2 6 6	
1	Shutter with working	" "	12 "	
	gear Complete	" "	10 " "	
	Lundries	" "	11 14 6	
- Total Estimate Rupees				340

Executive Engineer
 Office
 Camp. Nellore
 3rd April 1867

Approved
 Executive Engineer
 Commissioner Nellore Range
 Supr. Engineer & Dy.

Abstract Estimate No 4 of 1867
 1/2 or 1/4 of the
 District of the
 Pennair Delta

Work. Constructing Regulator near Valluram Tank in the Valluram
 Branch Channel.

Quantities Description of Work Rate Amount Total

875	Cft. of Concrete	2	109 6
4386	do of laterite in Chumam	4	1096 8
13	Squares of Pointing	2	26
29 1/2	Cy of Rubble stone / laterite	2.8	73 12
295	Cy of Excavations	1	18 7
45 3/8	Cft. of Teak wood shutters	3 8	158 13
37	Running cft. of Timber		45 6
	Waling		150
	Centring and Scaffolding		51 12

Total Estimate Rupees 730

Supr Engineer's Office at
 Kavalipattam
 20th April 1867

Commissioner Kavalipattam
 Supr Engineer at

W 1905/64

Abstract Estimate / 10407 10000

1st or Nollon Range

District Nollon - Talang

Pennair Delta

Work Constructing Fall near the Pkramadavum Inti
Tank in the Vallur Branch Channel.

Quantity	Description of Work	Rate	Amount	Total
1114	Cft of Concrete	" 2 "	139 12 "	
9819	Cft of Laterite in Chumam	" 4 "	2451 12 "	
23 1/2	Squares of Pointing	2 " "	47 " "	
54 2/3	Cy of Rubble Stone / Laterite /	2 8 "	136 10 8	
700	Cy of Earth Work	" 1 "	43 12 "	
18 3/4	Reft of Iron bar		25 11 "	
12 1/8	Cft of Teak wood Shuttering	3 8 "	42 7 "	
	Dalmig		150 " "	
	Sundries		59 15 4	
Total Estimate Rupees			3100 " "	

Supd Engineer (Official Seal)
Mavulapattam
30 April 1867

Commissioner
Supd Engineer (Official Seal)

1905/04

1st or Nellore Range.

District Nellore - Taluk

Work

Constructing Head & Race for Vallur Branch Channel

933

Quantities	Description of Work.	Rate.	Amount.	Total.
1909	Subje. feet of Concrete	" 2.	237 4 "	
11478	do. of Catering in Chumma	" 3 1	2204 9 4	
217	do. of Arch work	" 3 4	45 3 4	
31 1/2	feet of Painting	2.	63 .	
41 1/2	yards of Rubble Stone (Cater)	1 2.	46 11 .	
1138	yards of Earthwork	" 1 .	71 2 .	
4	yards of Metalling	" 11 .	3 8 .	
3	feet of wall with masonry	10 .	120 .	
	near Campsite			
16 1/2	feet of Earthwork	3 8 .	57 12 .	
	Baling		150 .	
	entering		15 .	
	Landries		65 14 4	
			53 11 2	
	Total Estimate Rs. 3080			

22/1985/4

Executive Engineer's Office
Camp. Nellore
32 April 1867.

Amits

Executive Engineer's Office

Comm. Nellore
Superintendent

1st or Nellore Range.

District Nellore--Taluk

Work

Constructing Fall in Pannair Delta
Vide Plan No 3. Adagaly Branch Channel

Quantities	Description of Work.	Rate.	Amount.	Total.
640	Cubic feet of Concrete	2.	80.	
4877	do of laterite in masonry	28	7298.	
10 1/2	Squares of Pointing	2.	21.	
19 22/27	Cyases of Rubble Stone of laterite	1 8.	29 17	
280	Cyases of Earthwork	1.	17 8.	
4-6	Trimming feet of embankment		6 12.	
5 1/8	Cyases of Earthwork Shuttles	3 8.	18 10 8	
	Baling		50.	
	Sundries		16 13 9	
Total Estimate Rupees				970

Executive Engineer's
Office
Camp Nellore
30. April 1867

[Signature]
Executive Engineer for
Nellore Range

[Signature] Lieut Colonel V. C.
Superintendent of D. A.

24 1965/64

Work

Constructing Road & fence for spin and
Pudipartij Branch

Quantities	Description of Work	Rate	Amount	Total
1149	Cubic feet of concrete	" 2.	143 10 "	
4631	do of latido in human	" 28	771 13 4	
12	Squares of Painting	2 "	24 "	
343	Cyads of Excavation	" 1 "	21 7 "	
11 1/2	Running of pipe how bars		13 8 "	
12 1/2	Feet of Sawnwood Shutter	8 "	13 12 "	
	Baling		50 "	
	Centering and Ladders		31 13 8	
	Total Estimate Rupees			1100

Executive Engineer's
OfficeCamp Nellore
22 April 1867Smith
Executive Engineer for
Nellore RangeResponsible
Superintendent

Abstract Estimate No. 4 of 1867-68

1st or Nellore Range

District Nellore--Talug

Work *Constructing Irrigation Schemes* *Pennari Delta* *Since Vice Plas. Bd.*

Quantities	Description of Work	Rate	Amount	Total
305	Labour feet of concrete	2	38 2	
951	Feet of concrete in channel	2 8	158 8	
5 1/2	Cyars of Public stone (concrete)	2 8	13 12	
3	Square of Painting	2	6	
127	Cyars of Earthwork	1	8 1	
1/16	Feet of Oak Beam	3 8	2 66	
1	Shutter with working gear		12	
	Baling		10	
	Indies		11 2 6	
Total Estimate Rupees				260

27 1965/67

Executive Engineer
Office
Camp. Nellore
3rd April 1868

[Signature]
Executive Engineer
Nellore Range

[Signature]
Commr. Nellore
Supr Engineer

Abstract Estimate No. 4. of 1867-68

1st or Nellore Range.

District Nellore--Taluk

Work

Constructing Regulating Sluices at the Sugali Tank

Quantities	Description of Work.	Rate.	Amount.	Total.
575	Cft. of Concrete	2 "	71 14 "	
3143	Cft. Lateral in Churnam	28	523 13 4	
10	Sq. of Pointing	2 "	20 "	
13 1/4	Cys. of Rubble Stone Lateral	180	203 "	
194	Cys. of Earth Work	1 "	122 "	
4 1/4	Pft. of Iron bar		7 "	
8 1/8	Cft. of Scab Wood Shutter	380	287 "	
	Barling		100 "	
	Centering & Scaffolding		1688	
				800

Ex: Engr's Office. Nellore
3rd April 1867

*Communicated to the
Superintendent*
S. J. N. S.
Executive Engineer
1st Nellore Range

Abstract Estimate No 4 of 1867/68

1st or Kallam Range

District Kallam Taluk

Ponnair Delta

Work Constructing a Road & bridge for Jagali
Branch

Quantity	Description of work	Rate	Amount	Sub
1511 ²¹ / ₃₂	Cft. of Concrete	" 2 "	188 15 4	
17872 ⁴⁹ / ₁₆₄	Cft. of Lignite in Chumam	" 2 8	2978 11 7	
35	Yds. Tamped graveling	" 2 "	4 6 -	
63 ¹ / ₄	Sqrs. of Pointing	2 " "	126 8 "	
940	Yds. of Earth work	" 1 "	58 12 "	
43 ¹ / ₂	Cft. of Teak wood	3 8 "	152 4 "	
8	Teak wood shutters	40 " "	320 " "	
	with working gear			
	Dalings		450 - -	
	Centing		50 - -	
	Timber		114 13 1	
				4440 - -

27/1/1868

Supr Engrs Office
Kavalipattam
30th April 1868

Commissioner
Super Engineer

Abstract Estimate 1864

1st or Yellow Range

215

Work Lengthening and Improving the Kapalem Sluice in the
Sawapalli Reservoir

Quantity	Description of work	Rate	Amount	Total
523	Cubic feet of concrete	2	65	6
3199 1/4	feet of latents in human	26	499	141
59 3/4	feet of lat. grand	180	89	80
10	Squares of painting	180	15	00
	Excavation		30	00
	Landre		3	11
Total Estimate Paper				700
Four others same as above				2800
Grand Total Estimate Paper				3500

W 1965

Executive Engineer
Office
Camp Righting Bellam
22nd September 1866

Despatched
3rd April
1867

Agnew
Executive Engineer 1st or
Yellow Range A.D.C.

Quommo
Supt. Engineer & Secy

1st or Nellore Range.

District Nellore--Taluk

Work ^{Agumam Deltu} (Converting Sarvapally Tank into main Reservoir for the Southern portion of the Pennar Delta.)

Enclosure with Nos
Nos 17 of 3rd May 1864
to the Secretary to
Govt of P.W.

Quantities	Description of Work.	Rate.	Amount.	Total.
289,247	Cubic Yards Earthwork inclusive of tamping	1 6	2746 14 6	
20,769	Cu yds of Laterite Stone Revetment	3	62307	
7136	do Gravel backing	9	4014	
99,634	Square Yards of Surfing	4	2075 11 4	
640	Cu yds of Removing and reconstructing old revetment	6	240	
1	New Calingula		1670	
	Lengthening and improving 5 Irrigation Sluices	700	3500	
	Compensation for land			
165	Acres	40	6600	
165	do	5	825	
478	do	8	3824	
477	do	1	477	
	Compensation for houses &c in the hamlet of Nappaturu			
1	Chuttram, with thatched roof,		100	
10	Fluts		200	
1	Bourie		150	
1	do		300	
6	Wells	40	240	
1	do belonging to the village of Nagalaram		40	

Carried over

113679-9-10

p 22 1905/06

Converting the
Sarvapally Tank
into main Reservoir
for the Southern
portion of the
Pennar Delta
Rs. 1,14,000

Reduct value of old materials

Sanderson

Total Estimate Rupees.		114,000
------------------------	--	---------

Executive Engineer's
Office
Camp Nelson
3rd April 1867

Amitho
Creative Engineer
1st or Below Range

Commissioner. Lambell R. C.
Super Engineer ad D^u

113,679	9	10
500	.	.
113,179	9	10
820	6	2
Rupers	114,000	

Abstract Estimate 112 1/4
12th or Tellone Range
District Tellone Taluk
Ponnair Delta

Dear Pennair Delta
Constructing an Aqueduct. Dear Kampartipanda

[illegible]

Super Engineer's Office 2nd Div
Maulipatam
30th April 1867

Geo. Morris. Comdr of RE
Supt Engineer 2d Div

Abstract Estimate No 4
 1st or Kalline Range
 District Kallore Taluk
 Pennar Delta

Work Constructing Bridge of 2 Arches 15' ft span
 across the Surrafulli Branch Channel-

Quantity	Description of Work	Rate	Amount	Total
575	Cft of Concrete	2	71 14	
121 1/4	Cft of Lignite in Chumam	3 4	2530	
1253	Cft of Arch Work	3 7	280 9	
55	Square Pointing	2	110	
194	Running ft of Cornice Work	4	48 8	
666	Cy of Earth Work	1	41 10	
52	Cy of Metalling	1 1/4	45 8	
4	Guard stones	4	16	
	Cartung		200	
	Baling		100	
	Summies		95 14 1	
				3540

22/19/5/64

Supr Engineer's Office 20th
 Manipalpet
 30th April 1867.

Geometrician V. S. R. R.
 Supr Engineer 20th

Donk Constructing an Irrigation Scheme No 2 Pennair Delta

Supr Ingt Office of Dr.
Washington
30th April 1867

Notwithstanding Verbal Dec.
Superior & District

22 1954/69

1st or Nellore Range.

District Nellore - Taluq

Work *Constructing and Repairing Dams* *and Irrigation* *See Vide Plans 1.*

Quantities	Description of Work.	Rate.	Amount.	Total.
3005	Labie feet of Concrete	2	38 2.	
951	Feet of laterite in Chimanu	3 4	198 2.	
3	Squares of Painting	2	6	
5 1/2	Gards of Rubble stone (Laterite)	1 2	6 3.	
129	Gards of Excavation	1	8 1.	
46	Feet of Oak woods	3 8	2 6 6	
1	Shutter with working gear		12	
	Baling		10	
	Lundries		19 1 6	
<u>Total Estimate Paper</u>				300

10/5/1965/64

Executive Engineer
Office
Camp Nellore
23rd April 1867

Leo Mincorn
Supr. Engineer

Ag. Mincorn
Executive Engineer
Nellore Range

Abstract Estimate of 1867/68.
 1st or Kallor Kallu
 Kallor District.
 Pennair Delta.

Work Constructing P. Shie for Surapully Branch

Quantities Description of Work Rate Amount Total

4790	Cft. of Concrete	2	599	2	
22028 $\frac{1}{2}$	Cft. of Lignite in Chumam	3	14245	1	3
1875	Cft. of Arch Work	3	4390	10	
95 $\frac{1}{4}$	Sq. of Pointing	2	190	8	
136 $\frac{11}{54}$	Cu. of Rubble stone / Lignite	1	2	153	3 8
1650	D. of Earth Work	1	103	2	
16 $\frac{1}{3}$	D. of Metalling	14	14	4	8
195	Cft. of Teak wood Shutter	3	8	682	8
240	Cft. of Iron bars			295	
	Poling			250	
	Centring			240	
				7163	7 7

Sumoies

176 8 5 7040

Sup. Engineer's Office 2nd Div.
 Masulipatam
 30th April 1867

Quot. Incom. Visa. of Mr.
 Sup. Engineer 2nd Div.

Abstract Estimate No 4
1st or Mellon Drainage
District Mellon Taluq
Punnair Delta

Work Constructing a surplus sluice adjacent to the Surra:
- palli Branch Head sluice across the old Frameddy
Channel -

Quantity	Description of Work	Rate	Amount	Total
3143	Cft of Concrete	" 2 "	392 14 "	
25495	Cft of Latite in Chunan	" 3 1/4 "	4913 1 7	
443	Cft of Arch work with latite in Chunan	" 3 4 "	92 4 8	
56	Squares of Pointing	2 " "	112 " "	
87	Cys of rubble stone/Latite	1 2 "	97 14 "	
959	Cys of Excavation	" 1 "	59 15 "	
8	Cys of Metalling	" 14 "	7 " "	
28	Cube feet of Oak wood Beam	3 8 "	98 " "	
5	Buttons with working gear	49 " "	245 " "	
	Boaling		200 " "	
	Centum		90 " "	
	Summies		161 14 9	
				6470 " "

Supr Engineer's Office D.D.
Masulipatam
30 April 1867

Geometrician
Supr Engineer D.D.

22/19/67

1st or Nellore Range.

District Nellore--Taluk

Work *Pennair Delta*
Constructing an Irrigation sluice
Order Plan No 1

Quantities	Description of Work.	Rate.	Amount.	Total.
305	Cft. of concrete	2 "	28 2 "	
951	Cft. of Lateral in Channel	29 "	157 33 "	
3	Sq. of Pointing	2 "	6 "	
5 1/2	Cy. of Rubble stone (Lateral)	12 "	63 "	
129	Cy. of Earth Work	1 "	81 "	
16	Cft. of Teak Wood	38 "	266 "	
1	Shutter with working gear		12 "	
	Malting		10 "	
	sundries		10 " 3	
				250

Superintendent
21/4/86

By: Engr's Office
 Lamp & Bell
 3rd April 1867

Agmista
 Executive Engineer
 1st or Nellore Range

22/1/86

(4)

1st or Nellore Range.

District Nellore - Taluq

Work *Deepening the Ramarapalli New Cut & Improving the Old Ramarapalli Channel*
Classey Works

Quantities	Description of Work.	Rate.	Amount.	Total.
	<i>1) demolishing and rebuilding</i>			
	<i>Iron Aqueduct Piers</i>			
3 8 1/2	<i>Cft. of Latite in Chumam</i>	2 9	655 3 "	
	<i>Demolishing existing Piers</i>		40 "	
	<i>Scaffolding, Shoring & Sundries</i>		50 "	
	<i>Building water weirs</i>		3 1/3 "	
	<i>Substituting iron Aqueduct</i>		7 80	680 0 0
	<i>for Siphon No 1</i>			
4 12 1	<i>Cft. of Latite in Chumam</i>	2 9	708 4 9	
12 1/2	<i>Sq. of Pointing</i>	2 "	25 "	
80	<i>Sq. of Iron trough</i>	15 "	1200 "	
	<i>Complete</i>			
36	<i>Cft. of Soft Wood</i>	3 8 "	126 "	
	<i>Excavating foundations</i>		20 "	
	<i>Building Weirs</i>		20 1/3 "	2100 0 0
	<i>Siphon No 2 Same as No 1</i>			2100 0 0
	<i>Lowering floor of Krishnapatnam</i>			
	<i>Road Bridge</i>			
13 7	<i>Cy. of Rock Cutting</i>	8 "	108 8 "	
	<i>Sundries</i>		18 "	70 0 0
	<i>Siphon No 3 Same as No 1</i>			2100 0 0
	<i>Converting Bridge across head of Krishnapatnam Channel into a Head Sluice for that Branch</i>			
3 5 2 7	<i>Cft. of Latite in Chumam</i>	2 9	606 3 3	
13 1/4	<i>Sq. of Pointing</i>	2 "	26 8 "	
5 1/4	<i>Cft. of Iron bars</i>		71 4 "	
			703 6 3	703 6 3

Brought forward

69	Cft. of Earth Work	38	241	8	703	153	705
95	Cy. of Excavation	1	5	15			
	Realing		10				
	Centering & Sundries		28	99			
Total Estimate Rs.					990		8040

Ch. Engr's Office
Camp & Bellur
3rd April 1867

[Signature]

Executive Engineer
1st or Nellore Range

Commissioner
Supt. Engineer & Co.

22 1965

Abstract Estimate No. 4 of 186 -6

1st or Nellore Range.

District Nellore--Taluk

Work - *Permanent* *Dellis*
Constructing a Bridge of 2 Arches across
the Saranapalli Channel near Stone houses

Quantities	Description of Work.	Rate.	Amount.	Total.
4812	Cft. of concrete	2	601	8
38454	Cft. of Castings in Channel	27	6609	46
4165	Cft. of Arch Work with Castings in Channel	3	889	11
1027	Sq. of Paving	2	205	
300	Rft. of Cornice	4	70	
1540	Cy. of Excavation	1	764	
15	Cy. of Breasting	6	510	
4	Guard Stones	4	16	
	Centering		370	
	Realing		200	
	Sundries		236	106
			9300	
Deduct Value of Old Materials			1000	
				8300

Ch. Engr's Office
Camp & Bellur
3rd April 1867

Commissioner
Supt. Engineer & Co.

[Signature]

Executive Engineer
1st or Nellore Range

1st or Nellore Range.

District Nellore--Taluk *Nellore**Perumaji Delta.*Work *Deepening the Laranapalli New Cut, and improving Old Kommedu Channel -*

Quantities	Description of Work.	Rate.	Amount.	Total.
60,439	Cyts of Cuttings	" 4 "	15109 12 "	
1956	" of Gravel Do	" 2 6 "	305 10 "	
49,133	" of " Do	" 2 "	6141 10 "	
137,961	" of " Cuttings	" 1 6 "	12933 13 6 "	
10,853	" of " Do	" 1 4 "	904 6 8 "	
51,277	" of " Do	" 1 3 "	4002 19 "	
1650	" of " Do	" 1 2 "	120 5 "	
8311	" of " Do	" 1 "	519 7 "	10037-11
321,530				
11,244	" of " Banking	" 1 3 "	878 7 "	
12027	" of " Do	" 1 2 "	876 15 6 "	
8213	" of " Do	" 1 1 "	556 1 5 "	
685	" of " Do	" 10 "	35 10 10 "	
32,169				1247-79
15,072 3/4	" of Rubble Pitching	1 2 "	18956 12 "	16956-12
10,048	" of Gravel Backing	8 "	5026 "	5026--
4767	Cyts of Surfing	" 1 6 "	397 4 "	
4107	" of " Do	" 10 "	213 14 6 "	
71866	" of " Do	" 4 "	1497 3 4 "	2108-5-10
80,740				
	Compensation for Land			200--
2	Distributing Channels			200--
	Masonry Works Vide Separate Estimates			
1	Bridges of 2 Arches across the Laranapalli Channel near Stonehousepet			8301--
1	Demolishing & rebuilding the Iron Aqueduct pier			680--
	Carried forward			7553-6-6

21/2/1906

Brought forward

1	Substituting Iron Aqueduct for Syphon No 1	2100	7553-6-6
1	100 100 No 2	2100	
1	Lowering floor of Krishna Patnam Road Bridge	70	
1	Substituting Iron Aqueduct for Syphon No 3	2100	
1	Constructing Bridge across Head of Krishna Patnam Channel into a Head sluice for that branch	990	
2	Irrigation Sluices Vise. Plan No 1	300	
1	Constructing a surplus sluice adjacent to the Saravapalli Branch Head sluice across the Old Ramreddi Channel	6470	
	Sundries	116-9-6	
Total Estimate		90300	

Abstract Estimate No. 4 of 1867-68

1st or Nellore Range.

District Nellore - Taluk

Work *Constructing an Auxiliary Head Sluice adjacent to the Anilbat*

Quantities	Description of Work.	Rate.	Amount.	Total.
6,216	Cft. of Concrete	2	777 0	
24,373	Cft. of Laterite in Channel	29	4189 19	
87	Sqrs. of Pointing	2	174	
1248	Sqrs. of Earth Work	4	312	
66 3/4	Cybs. of Metalling	1	16 10 8	
35 1/2	Cft. of Teak Wood Beam	3 8	124 4	
6	Teak Wood Shutter with Working joint	78	468	
	Centering		150	
	Sundries		138 15 7	
				6350

At: Engg's Office
Camp Nellore
3rd April 1867

[Signature]
Executive Engineer
1st or Nellore Range

Communicate to
Superintendent of
27 1965/6

At: Engg's Office
Camp Nellore
3rd April 1867

[Signature]
Communicate to
Superintendent of
27 1965/6

[Signature]
Executive Engineer
1st or Nellore Range

1st or Nellore Range.

District Nellore--Taluq

Nellore -- Taluk
P. Srinair Datta

—Work (Constructing an Auxiliary Head Race; enlarging Old Channel and deepening the Main Feeder from the existing Head Race to the head of the Carcassally Channel)

Quantities	Description of Work.	Rate.	Amount.	Total.
1	Gravel Sluice & Vase & separate Estimate			6,350 -
	Enlarging old Channel			
1118	Labie yards of Latent Cutting	8	559	
2710	do of Clearing Sub.	16	2521	
114	do of Earthwork	1	72	
	Demo. existing Bridge over old Sluicing			820 - 8 - 0
	Channel and clearing the latter out			125 - - -
	underneath it			
	Connecting existing and proposed			
	Gravel Sluices by a Parapet wall			
5812	Labie feet of Latent in Channel	27	569	
	do do of old Materials		216	353 - 4 - 0
	Lowering Slope of Gravel Sluice			100 - - -
	do of Shutters			216 - - -
	do of Pumping House Feeder			
3852	Labie yards of Latent Cutting	8	1926	
12852	do of Earthwork	16	1204	
29300	do of Rubble Pitching	2	2587	
15333	do of Gravel backing	8	76610	
	Compensation for one tied iron			6485 - 4 - 8
	and a small compound			800 - - -
	Sundries			50 - 8 - 4
	Total Estimate			16,300

Executive Engineer's
Office
Camp, Ballou
3rd April 1867

Commissioner
Public Engineer

Smith
Executive Engineer of
Ballou Range.

Public Works Department.

1867
No 184
PROCEEDINGS of the MAJRAS GOVERNMENT.

Under date the 20 June/67

Read the following

Proceedings of the Board of Revenue

(Here enter No. 3141 dated 21st May 1867 -

With the above letter
the Superintending Engr.
of the 2nd Div. forwards
plans and estimates, ag-
gregating Rs. 4,12,100, con-
sisting with a project for
further developing irrigation
in the Nellore District under
the Purna Cement,
by the enlargement, im-
provement, and extension
of the main channel
and some of its branches,
and by adding to the
capacity of the Sumpully
tank to enable it to con-
tain water sufficient
to supply the subli-

N.
W.

of the Channels during those periods of the cultivating season when, the river falling, the Channels are low.

The Govt observe that, by the proposed improved arrangements of the head works, a maximum supply will be secured in low freshes, or when the water in the River is below the crest of the Anicut, and a perfect command be obtained over all the main irrigating ducts of the Delta, and that the enlarged reservoir at Survasully will be more capable of holding up to 52 millions of Cubic yards, which, with additions

additions from time to time when the river is high, will, it is calculated, suffice to make good any deficiency of direct supply from the Channels.

The project recommends itself as likely to be not only highly beneficial, but also most remunerative. The area stated to be commanded by the extension of the Channels and under the influence of the Tank is given in round numbers at 77000 acres. Of this, after making what appears to the Govt to be an extremely liberal deduction from land already under cultivation, and for waste and uncultivable tracts, about 25500 acres will, it is confidently expected

he irrigated, yielding at
an assessment of Rs.
4 per acre as water
rate, a sum of Rs. 102,000
per annum. This is
equivalent to a return
of nearly 25 per cent.

Under these cir-
cumstances, the Sup-
t. Engr is authorized to pro-
ceed with the works from
the allotment of Rs. 25,000
provided for the purpose
in the Budget, and the
Govt. will have much
pleasure in recommending
the project to the Govt.
of India for sanction.

This Local Board
in Council consi-
ders the manner in which
the

249
the project, has been
prepared in a short-
time highly creditable
to Mr. ^A Smith.



To
The Supt. Engr of the 2nd Div. ✓

Construction of a new channel from 6 mile to the
Reservoir at Surrapully _____ } Rs. 1,25,000
Conversion of the present Surrapully Tank into a
main Reservoir _____ } " 1,14,000
Construction of branch channel from Surrapully
Channel to the Idagally Tank _____ } " 33,440
Construction of channel to Nollur Tank _____ " 27,800

It will be observed
that by the proposed im-
proved arrangements of the
head works, a maximum
supply of water from the
River will be secured in low
floods or when the water is
below the crest of the weir,
and a perfect command be
obtained over all the main
irrigating ducts leading into
the Delta, and that the en-
larged reservoir at Surra-
pully being made 30' high
of holding.

is

the

when, the river being low,
they would be in want of
water.

The project now sub-
mitted, being a continuation
of one which has fully real-
ized the great expectations
which were formed of it,
offers fair promise of being
highly useful and reproductive.
It is expected to bring under
wet cultivation 25,500 acres
of land, which, at an assess-
ment of Rs. 4 per acre as water
rate, will yield Rs. 1,02,000
per annum or a return of
nearly 25 P Cent. The details
of the project have been very
carefully considered, and as
it is most desirable that
the execution of the work
should be proceeded
with without delay
His Lordship in Council
has authorized its commence-
ment from the Budget
grant of Rs. 25,000. In
expressing

P

expressing a hope that
this proceeding will
meet with the approval
of the Govt. of India,
I am to request the early
sanction of that Govt
to the estimates, amount-
ing to Rs. 4,12,100. in
the aggregate.



For Secy. 20 June 1867

Recd. 22/6/67 with copy of
G.O. 1844 of 1867.

14th Nov. 1867

C. 25 June 1867 P. 75