

(1) Number of pages 6

(2) Date of repair 21-1-43

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public works DEPARTMENT.

G.O. No. 2458	Press Mis.
286-97	
Dated 12. 8	1867.

Not to be folded or roughly handled

1

*Proceedings of the Madras Government, Public Works Department,
12th August 1867.*

No. 296. Read the following Proceedings of the Madras Government in the
Military Department:—

Approving of an estimate of Rupees 825 for the }
construction of a latrine for the use of the } (Here enter 7th August 1867, No. 2,908.)
Artillery School at Bellary.

No. 297. ORDER THEREON, 12th August 1867, No. 2,458.

MILITARY WORKS, No. 22.

1. Communicated to the Superin-
tending Engineer of the 3rd Division.

2. As no funds are at present available, the execution of the work must be
deferred.

(True Extract.)

(Signed) J. H. M. SHAW STEWART, Major, R. E.,

Under Secretary to Government.

To the Superintending Engineer, 3rd Division, with one Specification.

.. Accountant General.

.. Controller of Public Works Accounts.

ABSTRACT ESTIMATE.

Bellary District.

Work for by Major General Commanding Division No. 642, dated 14th March

Quantities.	Description of Work.	Rate.	Amount.	Amount of each part.
450 3/4	Coff. Stone in Chunar. — Coff.	2.	306 56	
33 1/2	D. Bricks in do. — do.	3.	66 10 6	
160	Sph. Flooring Squared Granite Slabs. — } Sph.	9.	14 64	
75	Sph. Cornice Work. — Sph.	4.	18 2 3	
1116 3/8	Sph. Pointing with Chunar. — Sph.	2.	24 5 4	
887 1/4	Sph. Plastering 2 Coats of Chunar. — } do.	3 8.	31 1.	
24	Coff. Flak. Anchwork over Doors. — } Coff.	3.	4 8.	
60	Sph. of Slabs. — Sph.	6.	22 8.	
2.	Plaster Doors 3 x 6 1/2. — each	25.	50.	
8.	Ventilators Standing Venetian 2 1/2 x 2 do.	7 8.	60.	
15.	Sph. Dring Seats Top & front. — Sph.	1.	15.	
2.	Wicket Gates 3 x 4. — each	10.	20.	
4.	Iron (Sheet) Ground Ventilators 1 x 3 1/4. — } do.	6.	1 8.	
13 9/16	Coff. Joists to roof 18- Teakwood Coff.	4.	75 4 8	
202 1/2	Sph. Terracing Units on edge, walling Course, 3 inches Lily 2 Courses of flat tiles & plastering. — } Sph.	25.	50 10.	
325.	Sph. Wood piling Doors & Woodwork. — do.	2.	6 8.	
783	Coff. Excavation. — Coff.	3.	5 7 6	
4.	Painted Tin Water Spouts. each	2.	8.	
Surplus at 5 per cent				785 5 2
Total Estimate R.				709 12 4
				35 3 8
				39 6 1/2
				745 2 1/2
				825 1/2

Bellary
15 April 1887

Mr. W. H. D. S. S. S.

Supdt. Engineer 34 D.

Asst. Engineer

PROCEEDINGS OF THE MADRAS GOVERNMENT.

From the Superintending Engineer, 1st Division, Bellary, 19th July 1867,
No. 1140; to the Secretary to Government, Public Works Department, Fort
Saint George.

I have the honor to forward, for the sanction of Government, the accompanying plan, specification and estimate, amounting to Rupees 825, for constructing a latrine for the use of the Artillery School, Bellary.

2. The estimate was prepared at the request of the local Military authorities, and has received the approval of His Excellency the Commander-in-Chief.

3. There is no money available from the head of "minor new works, Military," to carry out the work at once, if sanctioned.

Referred to the Military Department with the remark that no funds are available in the Department Public Works.

PUBLIC WORKS DEPT.,
24th July 1867. } (Signed) SHAW STEWART, Major, R. E.,
Under Secretary to Government.

ORDER, No. 2908, 7 August 1867.

Approved for execution if funds being available.

(True Fact.)

Maurilton Colonel.

Deputy Secretary to Government.

To the Public Works Department, with 1, estate

.. Quarter Master General.

and separation. *42 spare Copies*

Exd. A. W. Cooke.

1867
 No. 2985

No. of the Madras Govt
 Privy. Dept

Dated 7 Aug 67
 Recd 9 Aug 67
 No. 2908
 Encls: 3. 1 Plan given

Approving of an
 estimate of Rupees 825
 for the construction
 of a lake for the
 use of the artillery
 school at Bellary.

2458-12th Aug/67

With enclos

1158

1. Current & Madras Govt of the 3.82
2. As no funds are at present available
 the execution of the work must be deferred

0533 & with me specified 123
 in 1867
 Controller

12th Aug 1867
 12th Aug 1867

10. 10. 1867